



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD  
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN  
Director

## ADDENDUM #2

Date: May 9, 2007

To: Contractors

From: Wayne Smith, Project Manager, DFCM

Reference: Building 3020 Renovation – Camp Williams  
Utah National Guard – Bluffdale, Utah  
DFCM Project No. 05228480

Subject: **Addendum No. 2**

Pages	Addendum	1	page
	<u>Architects Specifications</u>	<u>1</u>	<u>page</u>
	<b>Total</b>	<b>2</b>	<b>pages</b>

---

**Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.**

- 1.1 **SCHEDULE CHANGES – There has been no changes to the Project Schedule.**
- 1.2 **GENERAL – Vincent Design Group – Specifications.**

**End of Addendum #2**



**ADDENDUM NO. 1**

Utah National Guard  
Camp Williams, Building 3020

Date: May 8, 2007  
File No.: 06-53

DFCM PROJECT NO. 05228480

TO ALL PLANHOLDERS:

BIDDERS on the above captioned project will be governed by the following changes, additions, and deletions in the Contract Documents.

This Addendum is to be attached to and is to be construed to become a part of the drawings and specifications similarly titled and prepared by Vincent Design Group, Inc. Said drawings and specifications are to apply insofar as consistent with items hereafter noted. Contractors are instructed to acknowledge receipt of this Addendum on their Proposals.

**ON THE DRAWINGS:**

**Sheet No. AE-101, Floor Plan:**

1. Door Schedule: Change the door frame on all three (3) door types, both new and existing, to painted hollow metal. Note that this requires removal of existing wood jambs and doors and replacing with 1-3/4" solid core doors. Delete Detail #2/101.
2. Room #106, Work Room: Note the existing countertops and cabinets are to be disassembled during demolition and supplied to Owner.
3. At the north entrance vestibule - Provide matching ceramic tile patch from existing west edge of existing tile floor to the new wall.
4. Mechanical Room #111 and Closet #112: Retain existing return air grille in existing wall and provide a new air grille to be located in the new wall above door #1 into closet.
5. Data Communications:
  - A. Add a new datacom receptacle to be located in Office #101 on the south wall between the window and the existing entrance door.
  - B. Add a new datacom receptacle to be located in Storage Room #110 centered on the east wall.
  - C. Mechanical Room #111 - Relocate new datacom board shown on the south wall to the east wall adjacent to the existing datacom panel.
  - D. The datacom receptacles shown as existing, which was called out in the schedule to be replaced with a new receptacle and cabling back to the telecom board, will require that a conduit be connected at the termination above the receptacle in the ceiling space and run back to the telecom board.
  - E. See attached Telecommunications Specification which was omitted from the specification. Also, note that all new and existing datacom installation will require a junction box and a conduit back to the telecom board per specification requirements.

Bid Date: Tuesday, May 16, 2007, at the DFCM Fairpark Office.