



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD  
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN  
Director

## ADDENDUM #2

Date: April 5, 2007

To: Contractors

From: Tim Parkinson, Project Manager, DFCM

Reference: Board of Education  
Sanitary Sewer Ejection Pump/Piping Replacement  
DFCM Project No. 05258200

Subject: **Addendum No. 2**

Pages	Addendum	1	page
	<u>Engineers Specs.</u>	<u>2</u>	<u>page</u>
	<b>Total</b>	<b>3</b>	<b>pages</b>

---

**Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.**

**1.1 SCHEDULE CHANGES – There are no project schedule changes per this Addendum.**

**1.2 GENERAL: WHW Engineering Clarifications to Specs.**

**End of Addendum #1**

# ADDENDUM

---

Project Name: Utah State Board of Education Building  
Sanitary Ejector Pumps and Sewer  
Pipe Replacement

Addendum No.: One (1)

DFCM Project # 05258200

Date: April 5, 2007

From: WHW Engineering Inc  
1354 East 3300 South Suite 200  
Salt Lake City, Utah 84106  
Phone (80) 466-4021 Fax (801) 466-8536

To: Tim Parkinson - Project Manager  
CC: Joni Aponte - CAD Services

---

This Addendum forms and becomes a part of the Contract Documents and modifies the original Bidding Documents dated June 2006 as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of two (2) pages.

---

**I - CHANGES TO PRIOR ADDENDA: N/A**

**II - CHANGES TO BIDDING REQUIREMENTS:**

**Item II -1.** Added Alternate Number One (#1). See bidding documents for description.

**III - CHANGES TO AGREEMENT & OTHER CONTRACT FORMS: N/A**

**IV – CHANGES/CLARIFICATIONS TO CONDITIONS OF THE CONTRACT: N/A**

**V - CHANGES/CLARIFICATIONS TO SPECIFICATIONS:**

**Item V-1.** Section 01100, Paragraph 1.2; add item J. Item J shall read, "All batt insulation located in the pipe chases shall be removed and properly disposed of off site."

**Item V-2.** Section 01100, Paragraph 1.2, item C; add the following sentences, "All sewer and waste piping refers to piping the Contractor can gain access for removal. Existing walls, furred spaces, tile, etc. is not to be removed. Sewer and water piping in these areas will remain."

**Item V-3.** Section 01100, Paragraph 1.2; add item K. Item K shall read, "Working hours and phasing shall be worked out between the Contractor and the User Representative. Much of the work will have to be done after hours and on weekends."

**Item V-4.** Section 01100, Paragraph 1.2; add Alternate #1: "Extend the scope of the project to include extending the gravity sewer and the pumped sewer to the street curb in lieu of stopping at the building exterior wall. Contractor shall include replacement of grass, sidewalk, etc. as required. Sidewalk width and depth shall match existing adjoining sidewalks and shall meet Salt Lake City requirements. Do not cut existing curb."

**Item V-5.** Section 15050, Paragraph 3.1; add item E. Item E shall read, "All batt insulation located in the pipe chases shall be removed and properly disposed of off site."

**Item V-6.** Section 15445, Paragraph 2.3 - Sewage Pump Basin; remove the last sentence starting with "field verify" and add new sentence. The new sentence shall read, "Existing sump for the new pumps is 6'-0" deep."

**VI - CHANGES/CLARIFICATIONS TO DRAWINGS: N/A**

- Item VI-1.** Sheet PD101 - Replace note 10 with the following: "Remove existing gravity and pumped sewer lines to street curb including sod cleanouts and sidewalk." Alternate #1.
- Item VI-2.** Sheet PD101 - Replace note 12 with the following: "Remove existing cleanouts." Alternate #1.
- Item VI-3.** Sheet PD102 - Replace note 9 with the following: "Remove existing batt insulation from walls of pipe chase, all floors, and properly dispose of off site."
- Item VI-4.** Sheet PE101 - Delete note 9 and replace with: Alternate #1. "Provide new gravity and pumped sewer mains to street curb including two new cleanouts. Caulk the new piping penetrations thru wall water- and air-tight. Use existing wall openings. Replace sod and sidewalk. Sidewalk construction shall meet city standards. With and depth shall match existing adjoining sidewalks. Connect to existing sewer piping at curbs."
- Item VI-5.** Sheet PE101 - Delete notes 10 and 11. Alternate #1.
- Item VI-6.** Sheet PE401 - Note 1. Delete sentence 3 from note 1 and replace with: "The depth of the existing sump is 6'-0". Coordinate with the exact sump cover diameter."