



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

Kim Hood  
Executive Director

Division of Facilities Construction and Management

DAVID G. BUXTON  
Director

## ADDENDUM

Date: 13 July 2007

To: Contractors

From: Darrell Hunting, DFCM – Project Manager

Reference: West Jordan Armory Roofing Improvements  
Utah National Guard – West Jordan, Utah

DFCM Project No. 07014470

Subject: **Addendum No. 1**

Pages	Addendum	1 page
	<u>Architects Addendum</u>	<u>1 page</u>
	<b>Total</b>	<b>2 pages</b>

---

**Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.**

**1.1 SCHEDULE CHANGES** – There are no Project Schedule changes per this addendum.

**1.2 GENERAL** – See attached “Addendum No. 01”



July 13, 2007

Darrell Hunting  
State of Utah  
Department of Administrative Services  
Division of Facilities Construction and Management  
State Office Building Room 4110  
Salt Lake City, UT 84114

Dear Darrell,

The following are items for your first addendum on the Utah National Guard Armory Roofing Improvements. DFCM job # 07014470

**ADDENDUM # 1 ITEMS:**

**Sheet AE101**

- Contractor to Field verify roof top equipment between grids 1-5 and C-H on upper roof levels. See project manual section 07025-3.2
- Change key note 1b to read, "New Mechanically fasten PVC or TPO Membrane over ½" of Polyisocyanurate Board Insulation over existing insulation and fasteners."

**Sheet AE102**

- Remove "General Demolition Notes and Demolition Key Note Legend. Use "General notes and Keynote legend as on sheet AE101

**Sheet AE103**

- Contractor to field verify roof top equipment between grids 11-12 and D-F on upper roof level. See project manual section 07025-3.2
- Please remove "General Demolition Notes and Demolition Key Note Legend. Use "General notes and Keynote legend as on sheet AE101.

**PROJECT MANUAL ITEMS:**

- Section 07540 2.1 – A manufactures. Please add GAF "EverGuard PVC and TPO products and John Manville TPO or PVC Mechanically attached system. All manufacturers shall meet the requirements in the project manual.
- (Note All approved roofing material manufacturers are required to meet or exceed the manufacturing UL assembly # as outlined in the Underwriters Laboratories, Inc. 2007 UL Roofing Materials and Systems Directory Book )
- Section 07540 2.4 Substrate boards A – 1 Change "Dens-Deck Prime" to read "1/2" Polyisocyanurate board"

**DETAILS ITEMS:**

- Detail RF-05 Building expansion joint @ roof. Please refer to Project manual section 07540-2.7 Bellows-type roof expansion Joint assemblies.

END OF ITEMS FOR ADDENDUM # 1