



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

KIMBERLY HOOD
Executive Director

Division of Facilities Construction and Management

DAVID G. BUXTON
Director

ADDENDUM

Date: 22 January 2008

To: Contractors

From: Bob Anderson, Project Manager, DFCM

Reference: Boiler Replacement Demolition Phase
Weber State University - Ogden, Utah

DFCM Project #: 07049810

Subject: **Addendum No. 1**

Pages: Addendum 1 page
Engineers Addendum 2 pages
Total Pages 3 pages

Note: *This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.*

1.1 **Schedule Changes** - There are no schedule changes per this Addendum.

1.2 **General** - WHW Engineering, Inc. – Changes/Clarifications to drawings.

End of Addendum

ADDENDUM

Project Name: Weber State University
Heat Plant - Boiler Replacement
Demolition Phase

Addendum No.: One (1)

DFCM Project # 07049810

Date: January 21, 2008

From: WHW Engineering Inc
8619 South Sandy Parkway Suite 101
Sandy, Utah 84070
Phone (80) 466-4021 Fax (801) 466-8536

To: Bob Anderson - DFCM

This Addendum forms and becomes a part of the Contract Documents and modifies the original Bidding Documents dated 11/9/2007 as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of 2 pages.

I - CHANGES TO PRIOR ADDENDA: N/A

II - CHANGES TO BIDDING REQUIREMENTS: N/A

III - CHANGES TO AGREEMENT & OTHER CONTRACT FORMS: N/A

IV – CHANGES/CLARIFICATIONS TO CONDITIONS OF THE CONTRACT: N/A

V - CHANGES/CLARIFICATIONS TO SPECIFICATIONS: N/A

VI - CHANGES/CLARIFICATIONS TO DRAWINGS:

- | | | |
|-------------------|---|---|
| Item VI-1. | Sheet MD101 Note #23: | Add "cap piping for boiler #1 feed water system in lieu of blind flange. Blind flange shall remain for boiler #2, feed water system. |
| Item VI-2. | Sheet MD101 Note #25:
Sheet MD103 Note #2 : | Information: The back pressure valve for either boiler #1 or boiler #2 shall be removed by University. |
| Item VI-3. | Sheet MD101 Note #26:
Sheet MD103 Note #23:
Sheet MD105 Note #23: | Delete existing note and replace with the following.
"Remove existing gas piping, gas train, PRV valves, valves, hangers supports, plug valves etc. back to west wall. Capped existing piping at both connections. This will occur during a planned gas shut-down by the University. This contractor is responsible for the gas line below down and purging until the piping is safe for welding the two new caps. |
| Item VI-4. | Sheet MD101 Note #28: | Delete arrows that point to gas piping between plug valve and header at west wall. Arrows that point to gas header located along the wall shall remain. |
| Item VI-5. | Information: | All piping associated with the two boilers being removed shall be removed. Piping that is to remain that is in the way of the boilers being removed or in the path |

of the new boiler shall be rerouted by this contractor. Routing of such piping shall be approved by engineer and University.

- Item VI-6.** Sheet MD103 Note #6: The steam header controller located North East of boiler shall be removed by the University. The remaining controllers at this location shall be removed as noted and given back to the University. See detail D3.
- Item VI-7.** Sheet MD103 Note #12: Delete note #7 From Detail A1.
- Item VI-8.** Sheet MD104 Note #7: The boiler feed water controller located North West of boiler #2 shall be removed by the University. The remaining controllers at this location shall be removed and given back to the University. See detail D4.
- Item VI-9.** Sheet MD105 Note #12: Note #12 shall read "Remove angle Valve."
- Item VI-10.** Sheet MD105 Note#13: Note #13 shall read "Remove gate Valve."
- Item VI-11.** Sheet MD105 Note #24: Delete note 24 and replace with new note per Item VI-3 this addendum. See detail D4.