



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD
Executive Director

Division of Facilities Construction and Management

DAVID G. BUXTON
Director

ADDENDUM #2

Date: September 11, 2007

To: Contractors

From: Wayne Smith, Project Manager, DFCM

Reference: Classroom Addition - Orange Street Community Correctional Center
Division of Adult Probation & Parole – Salt Lake City, Utah
DFCM Project No.07186120

Subject: Addendum No. 2

Pages	Addendum	1	page
	<u>Architects Addendum</u>	<u>2</u>	<u>pages</u>
	Total	3	pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.

- 1.1 **SCHEDULE CHANGES** – There are no changes to the project schedule.
- 1.2 **GENERAL** – Vincent Design Group, Inc. Specifications and drawings.

End of Addendum #2



ADDENDUM NO. 2

Corrections - Orange Street
Class Room Building

Date: Sep 10, 2007
File No.: 06-73

DFCM PROJECT NO. 06178120

TO ALL PLANHOLDERS:

BIDDERS on the above captioned project will be governed by the following changes, additions, and deletions in the Contract Documents.

This Addendum is to be attached to and is to be construed to become a part of the drawings and specifications similarly titled and prepared by Vincent Design Group, Inc. Said drawings and specifications are to apply insofar as consistent with items hereafter noted. Contractors are instructed to acknowledge receipt of this Addendum on their Proposals.

ON THE DRAWINGS:

Sheet No. AS-102, Site Plan

1. Note that existing modular class room is to remain in use by owner until the new building is completed before removal or demolition is to happen. Demolition is to include legal disposal.
2. The edge of new asphalt paving, other than at new or existing concrete curb or walks is to be rolled off to the existing fence or lawn.

Sheet No. E-101 Electrical Plan

1. This sheet is reprinted reflecting the new building change in location..

IN THE SPECIFICATIONS:

Section 09900 Painting

1. Section calls for all doors and frames to be finished. Wood doors to be stained and varnished, hollow metal doors & frames are to be painted, see specification.

Section 07514 Built Up Asphalt Bituminous Roofing

1. Delete reference to Built Up Asphalt Bituminous roofing change to the following as called out on the drawings sheet # s-101 & s-102.
Use a single ply TPO rubber roofing, specified as 'Firestone' or equal (white) or similar by GAF or John Mansville.

Bid Date: **Sep. 13, 2007**

