



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD
Executive Director

Division of Facilities Construction and Management

DAVID G. BUXTON
Director

ADDENDUM #1

Date: March 10, 2008

To: Contractors

From: Mike Ambre, Project Manager, DFCM

Reference: Roofing Improvements – Airport Aviation Hangar
Utah Valley State College – Provo Airport – Provo, Utah
DFCM Project No. 08012790

Subject: **Addendum No. 1**

Pages	<u>Addendum</u>	1	page
	Total	1	page

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.

- 1.1 **SCHEDULE CHANGES** – There are no changes to the project schedule.
- 1.2 **GENERAL** - This addendum includes a revision to the roof system that was specified.
 1. EPS insulation will use between each flute on the metal deck. The EPS should be the same thickness as the depth of flute and tapered to follow the contour of the flutes shape.
 2. Instead of two layers of ½” OSB or 1” plywood DFCM would like one layer of ¾” x 4’ x 10’ plywood. The plywood must be screwed securely to each structural member.
 3. The north side of the roof has unique structural supports holding the parapet detail. These braces shall be wrapped with wood sheathing and water proofed over.