



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD
Executive Director

Division of Facilities Construction and Management

DAVID G. BUXTON
Director

ADDENDUM NO. 1

Date: January 20, 2009

To: Contractors

From: Wayne Smith, Project Manager, DFCM

Reference: Dust Collection System Replacement – State Library
Department of Community and Culture
DFCM Project No. 08208200

Subject: **Addendum No. 1**

Pages: Total Addendum 2 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.

While we contend that SB220 should only be potentially applicable to a contract issued after the effective date of said bill, this is to clarify that for purposes of this contract, regardless of the execution or effective dates of this contract, the status of Utah Law and remedies available to the State of Utah and DFCM, as it relates to any matter referred to or affected by said SB220, shall be the Utah law in effect at the time of the issuance of this Addendum.

1.1 **SCHEDULE CHANGES:** No Project Schedule changes.

1.2 **GENERAL ITEMS:**

1.2.1 Provide for 10 drops to equipment and 4 floor sweeps for the collection system. Also provide for a 4' x 5' vacuum table for hand sanding in the shop area.

1.2.2 This is a state owned facility and must comply to all fire codes and drawings must be submitted and approved from the Utah State Fire Marshals Office.

1.2.3 Return air will not be returned back into the shop area

- 1.2.4 Electrical requirements to power the new equipment will need to be designed and determined by the new design. There are several electrical panels within the building and the panel will have to be field verified by the electrical engineer that is designing the system.
- 1.2.5 Any landscaping and/or irrigation systems that are disrupted or disturbed during the excavation and placement of the concrete equipment pad will need to be repaired and/or replaced as part of this project.
- 1.2.6 For bid purposes assume that the building roof is under warranty and that the penetrations required would need to be provided by the contractor holding the warranty in order not to violate that warranty. Roofing manufacturer is John Mansville 20 yr warranty. Roof was installed by Utah Tile and Roof. Installer of dust collection system must verify what must be done during installation of equipment with regard to roof penetrations to ensure that roofing warranty is maintained.