



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

Kim Hood  
Executive Director

Division of Facilities Construction and Management

David G. Buxton  
Director

## ADDENDUM

Date: 17 August 2009

To: Contractors

From: Brent Lloyd, DFCM – Project Manager

Reference: UDOT – Rampton Complex Parking Lot Addition  
DFCM Project No. 08213900

Subject: **Addendum No. 1**

Pages	Cover Page	1 page
	Addendum	1 pages
	<b>Total</b>	<b>2 pages</b>

---

***Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.***

**1.1 SCHEDULE CHANGES – None**

**1.2 GENERAL – See attached “Addendum No. 01”**

# State of Utah

## Division of Facilities Construction and Management

UDOT – Rampton Complex Parking Lot Addition  
DFCM No. 08213900

### Addendum I

Item #1 – The Steel Fabricator for the carport covers must meet certification as outlined by the State Building Official available on DFCM's web site at <http://dfcm.utah.gov>.

Item #2 – Sheet C1.04, legend showing box symbol for electrical light fixture should be omitted. Note shows on Electrical sheet E1.2 in light fixture schedule.

Item #3 – cover carport parking structures to be 260 feet from center line of post to center line of post on the west parking area. Structure on the east side to be 177 feet from center line of post to center line of post.

Item #4 – All steel posts and beams on carport structures are to be primed and [painted with two coats of grey paint to match existing color.

Item #5 – New catch basin to be installed will be a 2x2x4 cast in place around the existing pipe or precast with cutting pipe and installing new section. Connections into box to be watertight. Grate to be rectangular, to match existing catch basin to the north.

Item #5 – Recycled asphalt base material can be substituted for new roadbase material as per specification section 32 1216, Part 2 – Products, 2.1 – B, 2.

Item #6 – Remove and replace sections of existing sidewalk and bushes, as required, to install new electrical conduits that need to run into the south west corner of the existing building. Owner will install new bushes if they feel it is necessary. Contractor to leave area clean and smooth.