



STATE OF UTAH - DEPARTMENT OF ADMINISTRATIVE SERVICES

Division of Facilities Construction and Management

DFCM

**STANDARD LOW BID PROJECT
Project Budgets Over \$100,000**

January 22, 2009

**DEAD HORSE POINT STATE PARK PAVING
IMPROVEMENTS**

DIVISION OF PARKS & RECREATION

MOAB, UTAH

DFCM Project Number: 08278510

Johansen & Tuttle Engineering
P.O. Box 487
Castle Dale, Utah 84513

TABLE OF CONTENTS

	<u>Page Numbers</u>
Title Sheet	1
Table of Contents	2
Notice to Contractors	3
Project Description	4
Project Schedule	5
Bid Form	6
Instructions to Bidders	8
Bid Bond	12
Instructions and Subcontractors List Form	13
Contractor's Agreement	16
Performance Bond	21
Payment Bond	22
Certificate of Substantial Completion	23
General Contractor Past Performance Rating	

Current copies of the following documents are hereby made part of these contract documents by reference. These documents are available on the DFCM web site at <http://dfcm.utah.gov> or are available upon request from DFCM.

DFCM Supplemental General Conditions dated July 15, 2008
DFCM General Conditions dated May 25, 2005.
DFCM Application and Certification for Payment dated May 25, 2005.

Technical Specifications:
Drawings:

The Agreement and General Conditions dated May 25, 2005 have been updated from versions that were formally adopted and in use prior to this date. The changes made to the General Conditions are identified in a document entitled Revisions to General Conditions that is available on DFCM's web site at <http://dfcm.utah.gov>

NOTICE TO CONTRACTORS

Sealed bids will be received by the Division of Facilities Construction and Management (DFCM) for:

DEAD HORSE POINT STATE PARK PAVING IMPROVEMENTS
DEPARTMENT OF PARKS AND RECREATION – MOAB, UTAH
DFCM PROJECT NO: 08278510

Bids will be in accordance with the Contract Documents that will be available on **Thursday, January 22, 2009**, and distributed in electronic format only on CDs from DFCM, 4110 State Office Building, Salt Lake City, Utah and on the DFCM web page at <http://dfcm.utah.gov>. For questions regarding this project, please contact Brent Lloyd, DFCM, at 801-550-5882. No others are to be contacted regarding this bidding process. The construction estimate for this project is \$253,000.00.

A **mandatory** pre-bid meeting will be held at **1:00 PM** on **Wednesday, January 28, 2009** at Dead Horse Point State Park, located approximately 23 miles off Hwy 191 on State Road 313, 8 miles north of Moab, Utah. All bidders wishing to bid on this project are required to attend this meeting.

Bids will be received until the hour of **2:30 PM** on **Tuesday, February 10, 2009** at DFCM, 4110 State Office Building, Salt Lake City, Utah 84114. Bids will be opened and read aloud in the DFCM Conference Room, 4110 State Office Building, Salt Lake City, Utah. NOTE: Bids must be received at 4110 State Office Building by the specified time.

A bid bond in the amount of five percent (5%) of the bid amount, made payable to the Division of Facilities Construction and Management on DFCM's bid bond form, shall accompany the bid.

The Division of Facilities Construction and Management reserves the right to reject any or all bids or to waive any formality or technicality in any bid in the interest of DFCM.

DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT

Joanna Reese, Contract Coordinator
4110 State Office Building, Salt Lake City, Utah 84114

PROJECT DESCRIPTION

This project is located at the Visitor Center of Dead Horse Point State Park. The Park is located approximately 23 miles off Hwy 191, 8 miles north of Moab, Utah. The Contractor shall submit a bid proposal for overlay (approx. 17,100 SF) of the existing Visitor Center parking lot; construction of an expansion (approx. 17,400 SF) of the existing parking lot; new curb & gutter, sidewalk, and paint striping as detailed in the plans and specifications provided.

The challenge in this project will be careful coordination and communication skills necessary to work with park personnel and patrons. The park will be open to the public during this project. The Contractor shall provide barricades insuring safety, delineating traffic routes and protecting the work area for the duration of the project.

**PROJECT SCHEDULE**

PROJECT NAME: DEAD HORSE POINT STATE PARK PAVING IMPROVEMENTS
DIVISION OF PARKS & RECREATION – MOAB, UTAH
DFCM PROJECT NO. 08278510

Event	Day	Date	Time	Place
Bidding Documents Available	Thursday	January 22, 2009	10:00 AM	DFCM 4110 State Office Bldg SLC, UT and the DFCM web site *
Mandatory Pre-bid Site Meeting	Wednesday	January 28, 2009	1:00 PM	Visitor Center, Dead Horse Point State Park
Last Day to Submit Questions	Tuesday	February 3, 2009	10:00 AM	Brent Lloyd – DFCM E-mail – brentlloyd@utah.gov Fax 801-538-3267
Addendum Deadline (exception for bid delays)	Thursday	February 5, 2009	2:00 PM	DFCM web site *
Prime Contractors Turn In Bid and Bid Bond	Tuesday	February 10, 2009	2:30 PM	DFCM 4110 State Office Bldg SLC, UT
Sub-contractor List Due	Wednesday	February 11, 2009	2:30 PM	DFCM 4110 State Office Bldg SLC, UT Fax 801-538-3677
Substantial Completion Date	Thursday	April 30, 2009		

* **NOTE:** DFCM's web site address is <http://dfcm.utah.gov>



BID FORM

NAME OF BIDDER _____ DATE _____

To the Division of Facilities Construction and Management
4110 State Office Building
Salt Lake City, Utah 84114

The undersigned, responsive to the "Notice to Contractors" and in accordance with the "Instructions to Bidders", in compliance with your invitation for bids for the **Dead Horse Point State Park Paving Improvements, - Division of Parks & Recreation – Moab, Utah - DFCM Project #08278510** and having examined the Contract Documents and the site of the proposed Work and being familiar with all of the conditions surrounding the construction of the proposed Project, including the availability of labor, hereby proposes to furnish all labor, materials and supplies as required for the Work in accordance with the Contract Documents as specified and within the time set forth and at the price stated below. This price is to cover all expenses incurred in performing the Work required under the Contract Documents of which this bid is a part:

I/We acknowledge receipt of the following Addenda: _____

For all work shown on the Drawings and described in the Specifications and Contract Documents, I/we agree to perform for the sum of:

_____ DOLLARS (\$_____)
(In case of discrepancy, written amount shall govern)

I/We guarantee that the Work will be Substantially Complete by April 30, 2009, should I/we be the successful bidder, and agree to pay liquidated damages in the amount of **\$250.00** per day for each day after expiration of the Contract Time as stated in Article 3 of the Contractor's Agreement.

This bid shall be good for 45 days after bid opening.

Enclosed is a 5% bid bond, as required, in the sum of _____

The undersigned Contractor's License Number for Utah is _____.

Upon receipt of notice of award of this bid, the undersigned agrees to execute the contract within ten (10) days, unless a shorter time is specified in the Contract Documents, and deliver acceptable Performance and Payment bonds in the prescribed form in the amount of 100% of the Contract Sum for faithful performance of the contract.

The Bid Bond attached, in the amount not less than five percent (5%) of the above bid sum, shall become the property of the Division of Facilities Construction and Management as liquidated damages for delay and additional expense caused thereby in the event that the contract is not executed and/or acceptable 100% Performance and Payment bonds are not delivered within the time set forth.

Type of Organization:

(Corporation, Partnership, Individual, etc.)

Any request and information related to Utah Preference Laws:

Respectfully submitted,

Name of Bidder

ADDRESS:

Authorized Signature

**STATE OF UTAH
DEAD HORSE POINT STATE PARK
PAVING IMPROVEMENTS
PROJECT NO. 08278510**

BID SCHEDULE

ITEM	WORK OR MATERIAL	UNIT	QTY	UNIT PRICE	AMOUNT
1	CLEARING AND GRUBBING	L.S.	1	\$ _____	\$ _____
2	MOBILIZATION	L.S.	1	\$ _____	\$ _____
3	3" HMA AC-10 (1/2-INCH MAX.)	SQ.FT.	17,400	\$ _____	\$ _____
4	2" HMA OVERLAY AC-10 (1/2-INCH MAX.)	SQ.FT.	17,100	\$ _____	\$ _____
5	PAVEMENT & CONCRETE SAWING	L.F.	460	\$ _____	\$ _____
6	UNTREATED BASE COURSE 1-INCH MINUS	C.Y.	250	\$ _____	\$ _____
7	BORROW	C.Y.	300	\$ _____	\$ _____
8	OBLITERATE ROAD	L.S.	1	\$ _____	\$ _____
9	24-INCH COLORED CONCRETE CURB AND GUTTER	L.F.	215	\$ _____	\$ _____
10	RECONSTRUCT UTILITY ACCESS	EACH	4	\$ _____	\$ _____
11	5-FOOT COLORED CONCRETE SIDEWALK	L.F.	260	\$ _____	\$ _____
12	CURB INLET BOX	EACH	2	\$ _____	\$ _____
13	REMOVE 5-FOOT SIDEWALK	L.F.	75	\$ _____	\$ _____
14	18-INCH CSP CULVERT WITH M.E.S. (POLYMERIC COATED)	L.F.	15	\$ _____	\$ _____
15	PAVEMENT MARKING PAINT	L.S.	1	\$ _____	\$ _____
			TOTAL BID...\$	_____	

INSTRUCTIONS TO BIDDERS

1. Drawings and Specifications, Other Contract Documents

Drawings and Specifications, as well as other available Contract Documents, may be obtained as stated in the Invitation to Bid.

2. Bids

Before submitting a bid, each contractor shall carefully examine the Contract Documents, shall visit the site of the Work; shall fully inform themselves as to all existing conditions and limitations; and shall include in the bid the cost of all items required by the Contract Documents. If the bidder observes that portions of the Contract Documents are at variance with applicable laws, building codes, rules, regulations or contain obvious erroneous or uncoordinated information, the bidder shall promptly notify the DFCM Representative and the necessary changes shall be accomplished by Addendum.

The bid, bearing original signatures, must be typed or handwritten in ink on the Bid Form provided in the procurement documents and submitted in a sealed envelope at the location specified by the Invitation to Bid prior to the deadline for submission of bids.

Bid bond security, in the amount of five percent (5%) of the bid, made payable to the Division of Facilities Construction and Management, shall accompany bid. **THE BID BOND MUST BE ON THE BID BOND FORM PROVIDED IN THE PROCUREMENT DOCUMENTS IN ORDER TO BE CONSIDERED AN ACCEPTABLE BID.**

If the bid bond security is submitted on a bid bond form other than DFCM's required bid bond form, and the bid security meets all other legal requirements, the bidder will be allowed to provide an acceptable bid bond by the close of business on the next business day following notification by DFCM of submission of a defective bid bond security. **NOTE: A cashier's check cannot be used as a substitute for a bid bond.**

3. Contract and Bond

The Contractor's Agreement will be in the form found in the specifications. The Contract Time will be as indicated in the bid. The successful bidder, simultaneously with the execution of the Contract Agreement, will be required to furnish a performance bond and a payment bond, both bearing original signatures, upon the forms provided in the procurement documents. The performance and payment bonds shall be for an amount equal to one hundred percent (100%) of the contract sum and secured from a company that meets the requirements specified in the requisite forms. Any bonding requirements for subcontractors will be specified in the Supplementary General Conditions.

4. Listing of Subcontractors

Listing of Subcontractors shall be as summarized in the “Instructions and Subcontractor’s List Form”, which are included as part of these Contract Documents. The Subcontractors List shall be delivered to DFCM or faxed to DFCM at (801)538-3677 within 24 hours of the bid opening. Requirements for listing additional subcontractors will be listed in the Contract Documents.

DFCM retains the right to audit or take other steps necessary to confirm compliance with requirements for the listing and changing of subcontractors. Any contractor who is found to not be in compliance with these requirements is subject to a debarment hearing and may be debarred from consideration for award of contracts for a period of up to three years.

5. Interpretation of Drawings and Specifications

If any person or entity contemplating submitting a bid is in doubt as to the meaning of any part of the drawings, specifications or other Contract Documents, such person shall submit to the DFCM Project Manager a request for an interpretation thereof. The person or entity submitting the request will be responsible for its prompt delivery. Any interpretation of the proposed documents will be made only by addenda posted on DFCM’s web site at <http://dfcm.utah.gov>. Neither the DFCM nor A/E will be responsible for any other explanations or interpretations of the proposed documents. A/E shall be deemed to refer to the architect or engineer hired by DFCM as the A/E or Consultant for the Project.

6. Addenda

Addenda will be posted on DFCM’s web site at <http://dfcm.utah.gov>. Contractors are responsible for obtaining information contained in each addendum from the web site. Addenda issued prior to the submittal deadline shall become part of the bidding process and must be acknowledged on the bid form. Failure to acknowledge addenda may result in disqualification from bidding.

7. Award of Contract

The Contract will be awarded as soon as possible to the lowest, responsive and responsible bidder, based on the lowest combination of base bid and acceptable prioritized alternates, provided the bid is reasonable, is in the interests of the State of Utah to accept and after applying the Utah Preference Laws in U.C.A. Title 63, Chapter 56. DFCM reserves the right to waive any technicalities or formalities in any bid or in the bidding. Alternates will be accepted on a prioritized basis with Alternate 1 being highest priority, Alternate 2 having second priority, etc.

8. DFCM Contractor Performance Rating

As a contractor completes each DFCM project, DFCM, the architect/engineer and the using agency will evaluate project performance based on the enclosed “DFCM Contractor Performance Rating” form. The ratings issued on this project will not affect this project but may affect the award on future projects.

9. Licensure

The Contractor shall comply with and require all of its subcontractors to comply with the license laws as required by the State of Utah.

10. Permits

In concurrence with the requirements for permitting in the General Conditions, it is the responsibility of the Contractor to obtain the fugitive dust plan requirements from the Utah Division of Air Quality and the SWPPP requirements from the Utah Department of Environmental Quality and submit the completed forms and pay any permit fee that may be required for this specific project. Failure to obtain the required permit may result in work stoppage and/or fines from the regulating authority that will be the sole responsibility of the Contractor. Any delay to the project as a result of any such failure to obtain the permit or noncompliance with the permit shall not be eligible for any extension in the Contract Time.

11. Right to Reject Bids

DFCM reserves the right to reject any or all Bids.

12. Time is of the Essence

Time is of the essence in regard to all the requirements of the Contract Documents.

13. Withdrawal of Bids

Bids may be withdrawn on written request received from bidder prior to the time fixed for opening. Negligence on the part of the bidder in preparing the bid confers no right for the withdrawal of the bid after it has been opened.

14. Product Approvals

Where reference is made to one or more proprietary products in the Contract Documents, but restrictive descriptive materials of one or more manufacturer(s) is referred to in the Contract Documents, the products of other manufacturers will be accepted, provided they equal or exceed the standards set forth in the drawings and specifications and are compatible with the intent and purpose of

the design, subject to the written approval of the A/E. Such written approval must occur prior to the deadline established for the last scheduled addenda to be issued. The A/E's written approval will be in an issued addendum. If the descriptive material is not restrictive, the products of other manufacturers specified will be accepted without prior approval provided they are compatible with the intent and purpose of the design as determined by the A/E.

15. Financial Responsibility of Contractors, Subcontractors and Sub-subcontractors

Contractors shall respond promptly to any inquiry in writing by DFCM to any concern of financial responsibility of the contractor, subcontractor or sub-subcontractor.

16. Debarment

By submitting a bid, the Contractor certifies that neither it nor its principals, including project and site managers, have been, or are under consideration for, debarment or suspension, or any action that would exclude such from participation in a construction contract by any governmental department or agency. If the Contractor cannot certify this statement, attach to the bid a detailed written explanation which must be reviewed and approved by DFCM as part of the requirements for award of the Project.

BID BOND

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL PERSONS BY THESE PRESENTS:

That _____ hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____, with its principal office in the City of _____ and authorized to transact business in this State and U. S. Department of the Treasury Listed, (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); hereinafter referred to as the "Surety," are held and firmly bound unto the STATE OF UTAH, hereinafter referred to as the "Obligee," in the amount of \$ _____ (5% of the accompanying bid), being the sum of this Bond to which payment the Principal and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the Principal has submitted to Obligee the accompanying bid incorporated by reference herein, dated as shown, to enter into a contract in writing for the _____ Project.

NOW, THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that if the said principal does not execute a contract and give bond to be approved by the Obligee for the faithful performance thereof within ten (10) days after being notified in writing of such contract to the principal, then the sum of the amount stated above will be forfeited to the State of Utah as liquidated damages and not as a penalty; if the said principal shall execute a contract and give bond to be approved by the Obligee for the faithful performance thereof within ten (10) days after being notified in writing of such contract to the Principal, then this obligation shall be null and void. It is expressly understood and agreed that the liability of the Surety for any and all defaults of the Principal hereunder shall be the full penal sum of this Bond. The Surety, for value received, hereby stipulates and agrees that obligations of the Surety under this Bond shall be for a term of sixty (60) days from actual date of the bid opening.

PROVIDED, HOWEVER, that this Bond is executed pursuant to provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the above bounden parties have executed this instrument under their several seals on the date indicated below, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

DATED this _____ day of _____, 20_____.

Principal's name and address (if other than a corporation):

By: _____

Title: _____

Principal's name and address (if a corporation):

By: _____

Title: _____

(Affix Corporate Seal)

Surety's name and address:

By: _____

Attorney-in-Fact (Affix Corporate Seal)

STATE OF _____)
) ss.
COUNTY OF _____)

On this ___ day of _____, 20____, personally appeared before me _____, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney-in-fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this _____ day of _____, 20_____.

My Commission Expires: _____

Resides at: _____

NOTARY PUBLIC

Agency: _____
Agent: _____
Address: _____
Phone: _____

Approved As To Form: May 25, 2005
By Alan S. Bachman, Asst Attorney General



Division of Facilities Construction and

INSTRUCTIONS AND SUBCONTRACTORS LIST FORM

The three low bidders, as well as all other bidders that desire to be considered, are required by law to submit to DFCM within 24 hours of bid opening a list of **ALL** first-tier subcontractors, including the subcontractor's name, bid amount and other information required by Building Board Rule and as stated in these Contract Documents, based on the following:

DOLLAR AMOUNTS FOR LISTING

PROJECTS UNDER \$500,000: ALL FIRST-TIER SUBS \$20,000 OR OVER MUST BE LISTED
PROJECTS \$500,000 OR MORE: ALL FIRST-TIER SUBS \$35,000 OR OVER MUST BE LISTED

- Any additional subcontractors identified in the bid documents shall also be listed.
- The DFCM Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law.
- List subcontractors for base bid as well as the impact on the list that the selection of any alternate may have.
- Bidder may not list more than one subcontractor to perform the same work.
- If there are no subcontractors for the job that are required to be reported by State law (either because there are no subcontractors that will be used on the project or because there are no first-tier subcontractors over the dollar amounts referred to above), then you do not need to submit a sublist. If you do not submit a sublist, it will be deemed to be a representation by you that there are no subcontractors on the job that are required to be reported under State law. At any time, DFCM reserves the right to inquire, for security purposes, as to the identification of the subcontractors at any tier that will be on the worksite.

LICENSURE:

The subcontractor's name, the type of work, the subcontractor's bid amount, and the subcontractor's license number as issued by DOPL, if such license is required under Utah Law, shall be listed. Bidder shall certify that all subcontractors, required to be licensed, are licensed as required by State law. A subcontractor includes a trade contractor or specialty contractor and does not include suppliers who provide only materials, equipment, or supplies to a contractor or subcontractor.

'SPECIAL EXCEPTION':

A bidder may list 'Special Exception' in place of a subcontractor when the bidder intends to obtain a subcontractor to perform the work at a later date because the bidder was unable to obtain a qualified or reasonable bid under the provisions of U.C.A. Section 63A-5-208(4). The bidder shall insert the term 'Special Exception' for that category of work, and shall provide documentation with the subcontractor list describing the bidder's efforts to obtain a bid of a qualified subcontractor at a reasonable cost and why the bidder was unable to obtain a qualified subcontractor bid. The Director must find that the bidder complied in good faith with State law requirements for any 'Special Exception' designation, in order for the bid to be considered. If awarded the contract, the Director shall supervise the bidder's efforts to obtain a qualified subcontractor bid. The amount of the awarded contract may not be adjusted to reflect the actual amount of the subcontractor's bid. Any listing of 'Special Exception' on the sublist form shall also include amount allocated for that work.

GROUNDS FOR DISQUALIFICATION:

The Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law. Director may withhold awarding the contract to a particular bidder if one or more of the proposed subcontractors are considered by the Director to be unqualified to do the Work or for

INSTRUCTIONS AND SUBCONTRACTORS LIST FORM
Page No. 2

such other reason in the best interest of the State of Utah. Notwithstanding any other provision in these instructions, if there is a good faith error on the sublist form, at the sole discretion of the Director, the Director may provide notice to the contractor and the contractor shall have 24 hours to submit the correction to the Director. If such correction is submitted timely, then the sublist requirements shall be considered met.

CHANGES OF SUBCONTRACTORS SPECIFICALLY IDENTIFIED ON SUBLIST FORM:

Subsequent to twenty-four hours after the bid opening, the contractor may change its listed subcontractors only after receiving written permission from the Director based on complying with all of the following criteria.

- (1) The contractor has established in writing that the change is in the best interest of the State and that the contractor establishes an appropriate reason for the change, which may include, but not is not limited to, the following reasons: the original subcontractor has failed to perform, or is not qualified or capable of performing, and/or the subcontractor has requested in writing to be released.
- (2) The circumstances related to the request for the change do not indicate any bad faith in the original listing of the subcontractors.
- (3) Any requirement set forth by the Director to ensure that the process used to select a new subcontractor does not give rise to bid shopping.
- (4) Any increase in the cost of the subject subcontractor work is borne by the contractor.
- (5) Any decrease in the cost of the subject subcontractor work shall result in a deductive change order being issued for the contract for such decreased amount.
- (6) The Director will give substantial weight to whether the subcontractor has consented in writing to being removed unless the Contractor establishes that the subcontractor is not qualified for the work.

EXAMPLE:

Example of a list where there are only four subcontractors:

TYPE OF WORK	SUBCONTRACTOR, "SELF" OR "SPECIAL EXCEPTION"	SUBCONTRACTOR BID AMOUNT	CONTRACTOR LICENSE #
ELECTRICAL	ABCD Electric Inc.	\$350,000.00	123456789000
LANDSCAPING	"Self" *	\$300,000.00	123456789000
CONCRETE (ALTERNATE #1)	XYZ Concrete Inc	\$298,000.00	987654321000
MECHANICAL	"Special Exception" (attach documentation)	Fixed at: \$350,000.00	(TO BE PROVIDED AFTER OBTAINING SUBCONTRACTOR)

* Bidders may list "self", but it is not required.

PURSUANT TO STATE LAW - SUBCONTRACTOR BID AMOUNTS CONTAINED IN THIS SUBCONTRACTOR LIST SHALL NOT BE DISCLOSED UNTIL THE CONTRACT HAS BEEN AWARDED.



SUBCONTRACTORS LIST
FAX TO 801-538-3677

PROJECT TITLE: _____

Caution: You must read and comply fully with instructions.

Table with 4 columns: TYPE OF WORK, SUBCONTRACTOR, 'SELF' OR 'SPECIAL EXCEPTION', SUBCONTRACTOR BID AMOUNT, CONT. LICENSE #

We certify that:

- 1. This list includes all subcontractors as required by the instructions, including those related to the base bid as well as any alternates.
2. We have listed 'Self' or 'Special Exception' in accordance with the instructions.
3. All subcontractors are appropriately licensed as required by State law.

FIRM: _____

DATE: _____

SIGNED BY: _____

NOTICE: FAILURE TO SUBMIT THIS FORM, PROPERLY COMPLETED AND SIGNED, AS REQUIRED IN THESE CONTRACT DOCUMENTS, SHALL BE GROUNDS FOR OWNER'S REFUSAL TO ENTER INTO A WRITTEN CONTRACT WITH BIDDER. ACTION MAY BE TAKEN AGAINST BIDDERS BID BOND AS DEEMED APPROPRIATE BY OWNER. ATTACH A SECOND PAGE IF NECESSARY.

CONTRACTOR'S AGREEMENT

FOR:

THIS CONTRACTOR'S AGREEMENT, made and entered into this ____ day of _____, 20__, by and between the DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT, hereinafter referred to as "DFCM", and _____, incorporated in the State of _____ and authorized to do business in the State of Utah, hereinafter referred to as "Contractor", whose address is _____.

WITNESSETH: WHEREAS, DFCM intends to have Work performed at _____.

WHEREAS, Contractor agrees to perform the Work for the sum stated herein.

NOW, THEREFORE, DFCM and Contractor for the consideration provided in this Contractor's Agreement, agree as follows:

ARTICLE 1. SCOPE OF WORK. The Work to be performed shall be in accordance with the Contract Documents prepared by _____ and entitled "_____."

The DFCM General Conditions ("General Conditions") dated May 25, 2005 and Supplemental General Conditions dated July 15, 2008 ("also referred to as General Conditions") on file at the office of DFCM and available on the DFCM website, are hereby incorporated by reference as part of this Agreement and are included in the specifications for this Project. All terms used in this Contractor's Agreement shall be as defined in the Contract Documents, and in particular, the General Conditions.

The Contractor Agrees to furnish labor, materials and equipment to complete the Work as required in the Contract Documents which are hereby incorporated by reference. It is understood and agreed by the parties hereto that all Work shall be performed as required in the Contract Documents and shall be subject to inspection and approval of DFCM or its authorized representative. The relationship of the Contractor to the DFCM hereunder is that of an independent Contractor.

ARTICLE 2. CONTRACT SUM. The DFCM agrees to pay and the Contractor agrees to accept in full performance of this Contractor's Agreement, the sum of _____ DOLLARS AND NO CENTS (\$_____.00), which is the base bid, and which sum also includes the cost of a 100% Performance Bond and a 100%

CONTRACTOR'S AGREEMENT
PAGE NO. 2

Payment Bond as well as all insurance requirements of the Contractor. Said bonds have already been posted by the Contractor pursuant to State law. The required proof of insurance certificates have been delivered to DFCM in accordance with the General Conditions before the execution of this Contractor's Agreement.

ARTICLE 3. TIME OF COMPLETION AND DELAY REMEDY. The Work shall be Substantially Complete by _____. Contractor agrees to pay liquidated damages in the amount of \$_____ per day for each day after expiration of the Contract Time until the Contractor achieves Substantial Completion in accordance with the Contract Documents, if Contractor's delay makes the damages applicable. The provision for liquidated damages is: (a) to compensate the DFCM for delay only; (b) is provided for herein because actual damages can not be readily ascertained at the time of execution of this Contractor's Agreement; (c) is not a penalty; and (d) shall not prevent the DFCM from maintaining Claims for other non-delay damages, such as costs to complete or remedy defective Work.

No action shall be maintained by the Contractor, including its or Subcontractor or suppliers at any tier, against the DFCM or State of Utah for damages or other claims due to losses attributable to hindrances or delays from any cause whatsoever, including acts and omissions of the DFCM or its officers, employees or agents, except as expressly provided in the General Conditions. The Contractor may receive a written extension of time, signed by the DFCM, in which to complete the Work under this Contractor's Agreement in accordance with the General Conditions.

ARTICLE 4. CONTRACT DOCUMENTS. The Contract Documents consist of this Contractor's Agreement, the Conditions of the Contract (DFCM General Conditions, Supplementary and other Conditions), the Drawings, Specifications, Addenda and Modifications. The Contract Documents shall also include the bidding documents, including the Invitation to Bid, Instructions to Bidders/ Proposers and the Bid/Proposal, to the extent not in conflict therewith and other documents and oral presentations that are documented as an attachment to the contract.

All such documents are hereby incorporated by reference herein. Any reference in this Contractor's Agreement to certain provisions of the Contract Documents shall in no way be construed as to lessen the importance or applicability of any other provisions of the Contract Documents.

ARTICLE 5. PAYMENT. The DFCM agrees to pay the Contractor from time to time as the Work progresses, but not more than once each month after the date of Notice to Proceed, and only upon Certificate of the A/E for Work performed during the preceding calendar month, ninety-five percent (95%) of the value of the labor performed and ninety-five percent (95%) of the value of materials furnished in place or on the site. The Contractor agrees to furnish to the DFCM invoices for materials purchased and on the site but not installed, for which the Contractor requests payment and agrees to

safeguard and protect such equipment or materials and is responsible for safekeeping thereof and if such be stolen, lost or destroyed, to replace same.

Such evidence of labor performed and materials furnished as the DFCM may reasonably require shall be supplied by the Contractor at the time of request for Certificate of Payment on account. Materials for which payment has been made cannot be removed from the job site without DFCM's written approval. Five percent (5%) of the earned amount shall be retained from each monthly payment. The retainage, including any additional retainage imposed and the release of any retainage, shall be in accordance with UCA 13-8-5 as amended. Contractor shall also comply with the requirements of UCA 13-8-5, including restrictions of retainage regarding subcontractors and the distribution of interest earned on the retention proceeds. The DFCM shall not be responsible for enforcing the Contractor's obligations under State law in fulfilling the retention law requirements with subcontractors at any tier.

ARTICLE 6. INDEBTEDNESS. Before final payment is made, the Contractor must submit evidence satisfactory to the DFCM that all payrolls, materials bills, subcontracts at any tier and outstanding indebtedness in connection with the Work have been properly paid. Final Payment will be made after receipt of said evidence, final acceptance of the Work by the DFCM as well as compliance with the applicable provisions of the General Conditions.

Contractor shall respond immediately to any inquiry in writing by DFCM as to any concern of financial responsibility and DFCM reserves the right to request any waivers, releases or bonds from Contractor in regard to any rights of Subcontractors (including suppliers) at any tier or any third parties prior to any payment by DFCM to Contractor.

ARTICLE 7. ADDITIONAL WORK. It is understood and agreed by the parties hereto that no money will be paid to the Contractor for additional labor or materials furnished unless a new contract in writing or a Modification hereof in accordance with the General Conditions and the Contract Documents for such additional labor or materials has been executed. The DFCM specifically reserves the right to modify or amend this Contractor's Agreement and the total sum due hereunder either by enlarging or restricting the scope of the Work.

ARTICLE 8. INSPECTIONS. The Work shall be inspected for acceptance in accordance with the General Conditions.

ARTICLE 9. DISPUTES. Any dispute, PRE or Claim between the parties shall be subject to the provisions of Article 7 of the General Conditions. DFCM reserves all rights to pursue its rights and remedies as provided in the General Conditions.

ARTICLE 10. TERMINATION, SUSPENSION OR ABANDONMENT. This Contractor's Agreement may be terminated, suspended or abandoned in accordance with the General Conditions.

ARTICLE 11. DFCM'S RIGHT TO WITHHOLD CERTAIN AMOUNT AND MAKE USE THEREOF. The DFCM may withhold from payment to the Contractor such amount as, in DFCM's judgment, may be necessary to pay just claims against the Contractor or Subcontractor at any tier for labor and services rendered and materials furnished in and about the Work. The DFCM may apply such withheld amounts for the payment of such claims in DFCM's discretion. In so doing, the DFCM shall be deemed the agent of Contractor and payment so made by the DFCM shall be considered as payment made under this Contractor's Agreement by the DFCM to the Contractor. DFCM shall not be liable to the Contractor for any such payment made in good faith. Such withholdings and payments may be made without prior approval of the Contractor and may be also be prior to any determination as a result of any dispute, PRE, Claim or litigation.

ARTICLE 12. INDEMNIFICATION. The Contractor shall comply with the indemnification provisions of the General Conditions.

ARTICLE 13. SUCCESSORS AND ASSIGNMENT OF CONTRACT. The DFCM and Contractor, respectively bind themselves, their partners, successors, assigns and legal representatives to the other party to this Agreement, and to partners, successors, assigns and legal representatives of such other party with respect to all covenants, provisions, rights and responsibilities of this Contractor's Agreement. The Contractor shall not assign this Contractor's Agreement without the prior written consent of the DFCM, nor shall the Contractor assign any moneys due or to become due as well as any rights under this Contractor's Agreement, without prior written consent of the DFCM.

ARTICLE 14. RELATIONSHIP OF THE PARTIES. The Contractor accepts the relationship of trust and confidence established by this Contractor's Agreement and covenants with the DFCM to cooperate with the DFCM and A/E and use the Contractor's best skill, efforts and judgment in furthering the interest of the DFCM; to furnish efficient business administration and supervision; to make best efforts to furnish at all times an adequate supply of workers and materials; and to perform the Work in the best and most expeditious and economic manner consistent with the interests of the DFCM.

ARTICLE 15. AUTHORITY TO EXECUTE AND PERFORM AGREEMENT. Contractor and DFCM each represent that the execution of this Contractor's Agreement and the performance thereunder is within their respective duly authorized powers.

ARTICLE 16. ATTORNEY FEES AND COSTS. Except as otherwise provided in the dispute resolution provisions of the General Conditions, the prevailing party shall be entitled to reasonable attorney fees and costs incurred in any action in the District Court and/or appellate body to enforce this Contractor's Agreement or recover damages or any other action as a result of a breach thereof.

PAYMENT BOND

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL PERSONS BY THESE PRESENTS:

That _____ hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____ authorized to do business in this State and U. S. Department of the Treasury Listed (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); with its principal office in the City of _____, hereinafter referred to as the "Surety," are held and firmly bound unto the State of Utah hereinafter referred to as the "Obligee," in the amount of _____ Dollars (\$ _____) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the _____ day of _____, 20____, to construct _____ in the County of _____, State of Utah, Project No. _____ for the approximate sum of _____ Dollars (\$ _____), which contract is hereby incorporated by reference herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall pay all claimants supplying labor or materials to Principal or Principal's Subcontractors in compliance with the provisions of Title 63, Chapter 56, of Utah Code Annotated, 1953, as amended, and in the prosecution of the Work provided for in said Contract, then, this obligation shall be void; otherwise it shall remain in full force and effect.

That said Surety to this Bond, for value received, hereby stipulates and agrees that no changes, extensions of time, alterations or additions to the terms of the Contract or to the Work to be performed thereunder, or the specifications or drawings accompanying same shall in any way affect its obligation on this Bond, and does hereby waive notice of any such changes, extensions of time, alterations or additions to the terms of the Contract or to the Work or to the specifications or drawings and agrees that they shall become part of the Contract Documents.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this _____ day of _____, 20____.

WITNESS OR ATTESTATION:

PRINCIPAL:

By: _____ (Seal)

Title: _____

WITNESS OR ATTESTATION:

SURETY:

By: _____ Attorney-in-Fact (Seal)

STATE OF _____)
) ss.
COUNTY OF _____)

On this _____ day of _____, 20____, personally appeared before me _____, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney-in-fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this _____ day of _____, 20____.

My commission expires: _____
Resides at: _____

NOTARY PUBLIC

Agency: _____
Agent: _____
Address: _____
Phone: _____

Approved As To Form: May 25, 2005
By Alan S. Bachman, Asst Attorney General



CERTIFICATE OF SUBSTANTIAL COMPLETION

PROJECT _____ PROJECT NO: _____

AGENCY/INSTITUTION _____

AREA ACCEPTED _____

The Work performed under the subject Contract has been reviewed on this date and found to be Substantially Completed as defined in the General Conditions; including that the construction is sufficiently completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the State of Utah can occupy the Project or specified area of the Project for the use for which it is intended.

The DFCM - (Owner) accepts the Project or specified area of the Project as Substantially Complete and will assume full possession of the Project or specified area of the Project at _____ (time) on _____ (date).

The DFCM accepts the Project for occupancy and agrees to assume full responsibility for maintenance and operation, including utilities and insurance, of the Project subject to the itemized responsibilities and/or exceptions noted below:

The Owner acknowledges receipt of the following closeout and transition materials:

- As-built Drawings
- O & M Manuals
- Warranty Documents
- Completion of Training Requirements

A list of items to be completed or corrected (Punch List) is attached hereto. The failure to include an item on it does not alter the responsibility of the Contractor to complete all the Work in accordance with the Contract Documents, including authorized changes thereof. The amount of _____(Twice the value of the punch list work) shall be retained to assure the completion of the punch list work.

The Contractor shall complete or correct the Work on the list of (Punch List) items appended hereto within _____ calendar days from the above date of issuance of this Certificate. The amount withheld pending completion of the list of items noted and agreed to shall be: \$_____. If the list of items is not completed within the time allotted the Owner has the right to be compensated for the delays and/or complete the work with the help of independent contractor at the expense of the retained project funds. If the retained project funds are insufficient to cover the delay/completion damages, the Owner shall be promptly reimbursed for the balance of the funds needed to compensate the Owner.

_____ by: _____
CONTRACTOR (include name of firm) (Signature) DATE

_____ by: _____
A/E (include name of firm) (Signature) DATE

_____ by: _____
USING INSTITUTION OR AGENCY (Signature) DATE

_____ by: _____
DFCM (Owner) (Signature) DATE

**General Contractor Performance Rating Form**

Project Name:		DFCM Project#	
Contractor: (ABC Construction, John Doe, 111-111-1111)	A/E: (ABC Architects, Jane Doe, 222-222-2222)	Original Contract Amount:	Final Contract Amount:
DFCM Project Manager:		Contract Date:	
Completion Date:		Date of Rating:	

Rating Guideline	QUALITY OF PRODUCT OR SERVICES	COST CONTROL	TIMELINESS OF PERFORMANCE	BUSINESS RELATIONS
5-Exceptional	Contractor has demonstrated an exceptional performance level in any of the above four categories that justifies adding a point to the score. Contractor performance clearly exceeds the performance levels described as "Very Good"			
4-Very Good	Contractor is in compliance with contract requirements and/or delivers quality product/service.	Contractor is effective in managing costs and submits current, accurate, and complete billings	Contractor is effective in meeting milestones and delivery schedule	Response to inquiries, technical/service/administrative issues is effective
3-Satisfactory	Minor inefficiencies/errors have been identified	Contractor is usually effective in managing cost	Contractor is usually effective in meeting milestones and delivery schedules	Response to inquires technical/service/administrative issues is somewhat effective
2-Marginal	Major problems have been encountered	Contractor is having major difficulty managing cost effectively	Contractor is having major difficulty meeting milestones and delivery schedule	Response to inquiries, technical/service/administrative issues is marginally effective
1-Unsatisfactory	Contractor is not in compliance and is jeopardizing achievement of contract objectives	Contractor is unable to manage costs effectively	Contractor delays are jeopardizing performance of contract objectives	Response to inquiries, technical/service/administrative issues is not effective

1. Rate Contractors quality of workmanship, management of sub contractor performance, project cleanliness, organization and safety requirement.	Score
<u>Agency Comments:</u>	
<u>A & E Comments:</u>	
<u>DFCM Project Manager Comments:</u>	

2. Rate Contractor administration of project costs, change orders and financial management of the project budget.	Score
<u>Agency Comments:</u>	
<u>A & E Comments:</u>	
<u>DFCM Project Manager Comments:</u>	

3. Rate Contractor's performance and adherence to Project Schedule, delay procedures and requirements of substantial completion, inspection and punch-list performance.	Score
<u>Agency Comments:</u>	
<u>A & E Comments:</u>	
<u>DFCM Project Manager Comments:</u>	

4. Evaluate performance of contractor management team including project manager, engineer and superintendent also include in the rating team's ability to work well with owner, user agency and consultants.	Score
<u>Agency Comments:</u>	
<u>A & E Comments:</u>	
<u>DFCM Project Manager Comments:</u>	

5. Rate success of Contractor's management plan, completion of the plans mitigation of project risks and performance of value engineering concepts.	Score
<u>Agency Comments:</u>	
<u>A & E Comments:</u>	
<u>DFCM Project Manager Comments:</u>	

Signed by:	Date:	Mean Score
-------------------	--------------	-------------------

Additional Comments:

CONSTRUCTION SPECIFICATION

SPECIAL CONDITIONS

1. **SCOPE**

This section of the specifications cover specific requirements, instructions and conditions applicable to this project only, which are not covered by the General Conditions or detailed specifications. Should there be conflicting statements between this section and other sections of these specifications, this section shall govern.

2. **STANDARD PRODUCTS**

The material brand names and catalog numbers shown on the drawings or called out in the specifications are meant to set a standard that all other materials should meet. The Contractor or supplier is encouraged to submit information and data to show his material is equal. The decision of the Engineer shall be final in this section.

3. **MAINTENANCE OF TRAFFIC**

The Contractor shall at all times conduct his operations so that there is a minimum of interruptions of the use of any road involved. Timing and methods of any road closure shall be approved by the Owner and the Engineer. The exact procedure for any interruption of traffic, for providing detours when required, for providing flag men when required, and for providing passage into and through work areas for essential traffic shall be worked out in advance of the phase of construction involved, between the Contractor, Engineer, and the appropriate State Park and state officials.

4. **CONTRACTOR TO MAINTAIN AND REPLACE STAKES**

The Contractor shall furnish without charge, competent men from his force, stakes, tools and other materials, for the proper staking out of the work, in making measurements and surveys, and in establishing temporary or permanent reference marks in connection with the work. This does not mean to imply, the Contractor is to pay for initial staking, as this will be the cost of the Owner.

Initial staking to be provided by the Owner will be the establishment of:

- a. Bench Marks.
 - b. Original lines and grades necessary for horizontal and vertical control of the construction of the permanent works.
 - c. Right-of-way limits acquired through permits from Federal Agencies.
- The Contractor shall provide surveys necessary to maintain the lines and grades during the

construction of the permanent works.

5. **LINES AND GRADES**

All work done under this contract shall be done to the line, grades, and elevations shown on the plans, or as directed by the Engineer. The Contractor shall keep the Engineer informed, a reasonable time in advance, of the times and places at which he intends to do work, in order that lines and grades may be furnished and necessary measurements for record and payment may be made with the minimum of inconvenience to the Engineer and delay to the Contractor.

6. **PAYMENT OF SUPPLIES AND SUBCONTRACTORS**

It is intended that the Contractor and subcontractor make full monthly payments to their suppliers and subcontractors as invoices are rendered. Such invoices shall be deemed as paid at the time each monthly certificate of payment is prepared by the Engineer. Affidavits will be submitted by the Contractor each as means of certifying to the Engineer that all equipment and materials delivered has been paid for. This will be the normal proof of payment; however, the Engineer will have the right at any time to demand copies of certified paid invoices. Failure or inability to provide such paid invoices will be sufficient cause for hold-up for further monthly pay estimates.

7. **GENERAL SAFETY REQUIREMENTS**

Excavations

- a. This section shall apply to all excavations in which workmen may be exposed to hazard of collapse of the banks, sides, or walls, during the time construction work is in process.
- b. All excavations shall be guarded by shoring, bracing or underpinning, or other methods as may be necessary to prevent injury to workmen resulting from the sides caving in.
- c. Excavated or other material must be deposited a safe distance from the edge of the excavation so as to prevent its falling or sliding back into the excavation.
- d. No trenches shall be left open at any time unless guarded with adequate barricades, warning lamps, and signs.
- e. Contractor's foremen and superintendents shall know where to obtain an oxygen resuscitator for use in an emergency. The phone number to call for immediate resuscitator and ambulance service shall be posted in all Contractors trench and at conspicuous places on the project at all times.

8. **CERTIFICATIONS**

Certifications that all materials used in the construction of the permanent works meet these specifications will be required. These certifications shall include the contract number, project name, bid item number, material furnished, applicable specification number and quantity furnished.

9. **TEST**

Test results that are required from the Contractor at the Contractor's expense will be performed as specified in the specifications. Duplicate copies of the test results shall be furnished to the Engineer for his approval at least 10 days prior to the use of the materials in the permanent works. All "on site" testing shall be made in the presence of and be approved by the Engineer or his representative. Written test results for "on site" tests will not be required.

10. **LIQUIDATED DAMAGES**

If the work, or any part thereof, is not completed within the time agreed upon in this contract or any extension thereof, the contractor shall be liable to the owner in the amount of \$1,000.00 per day for each and every calendar day the completion of the work is delayed beyond the time provided in this contract, as fixed and agreed liquidated damages and not as a penalty, and the Owner shall have the right to deduct from the retainage of the moneys which may be then due or which may be due and payable to the Contractor, the amount of the liquidated damages; and if the amount so retained by the owner is insufficient to pay in full such liquidated damages, the Contractor shall pay to the Owner the amount necessary to effect payment in full of such liquidated damages.

11. **EXISTING UTILITIES**

The Contractor will be responsible for crossing existing utilities such as gas lines, water lines, telephone lines, irrigation crossings, etc., with the construction equipment. If the utility or service lateral must be relocated due to the grade of the pipe, it shall be done by the Contractor under the direction of the Engineer. If the utility or service lateral is damaged by the Contractor's negligence, it shall be restored at the Contractor's expense.

The Contractor shall notify all utility companies 48 hours prior to excavating to ensure as nearly uninterrupted service as is reasonably proper. The Contractor shall not claim extra compensation or time extensions due to delays resulting from private utilities.

12. **EXAMINATION OF PLANS, SPECIFICATIONS, SPECIAL PROVISIONS, AND SITES**

The bidder is required to examine carefully the site of the proposed work, the proposal, plans, specifications, supplemental specification, special provision, and contract forms before submitting a proposal.

The submission of a bid shall be considered PRIMA FACIE evidence that the Bidder has made the required examinations and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the contract.

13. **WORK SCHEDULE**

The Contractor shall not work after the hours of 5:00 p.m., before 8:00 a.m., or on Saturdays, Sundays, or holidays without written consent of the Engineer.

14. **AVAILABILITY OF MEN AND EQUIPMENT**

The Contractor shall have men and equipment available on weekends and holidays to cope with emergency conditions, line breaks, flooding, etc., which may arise as a result of his operations. Phone numbers or addresses shall be provided in writing to the Owner.

15. **DUST CONTROL**

The Contractor will be required to provide dust control through the use of water truck when, in the opinion of the Engineer, dust becomes excessive.

16. **WASTE MATERIAL**

The Contractor shall be responsible for disposal of waste material from the site. Disposal area must be approved by the Engineer prior to use.

17. **SUPERVISION BY CONTRACTOR**

The Contractor will supervise and direct work. He will be solely responsible for the means, techniques, sequences and procedures of construction. The Contractor will employ and maintain on the work site a qualified supervisor or superintendent who shall have been designated in writing by the Contractor as the contractor's representative at the site. The supervisor or superintendent shall have full authority to act on behalf of the contractor and all communications given to the supervisor shall be as binding as if given to the contractor. The supervisor shall be present on the site at all times as required to perform adequate supervision and coordination of the work.

18. **CONTRACTOR'S PERSONNEL**

All work under this contract shall be performed in a skillful and workmanlike manner. The

Owner may, in writing, require the Contractor to remove from the work any employee the Owner deems incompetent, careless, or otherwise objectionable.

19. **GUARANTEE OF THE WORK**

The Contractor shall, for a period of one (1) year after completion and acceptance of the work, maintain and repair any defective work which may occur to the permanent work.

20. **PAVEMENT CUTTING**

Prior to removal, all paved surfaces shall be cut with a pavement cutter.

21. **RETAINAGE ON PROGRESS PAYMENTS**

Five percent (5%) will be retained on each progress payment to the Contractor until final completion and acceptance of all work.

22. **LIABILITY INSURANCE**

Before the contract is executed the Contractor with the successful bid shall be required to furnish to Owner, a copy of the public liability and property damage insurance policy in an amount of no less than \$2,000,000 each occurrence, which is to be in force and applicable to the project. In addition, the Contractor shall be required to furnish, at the same time a letter from agent for the company holding said policy, stating that he will inform Owner of any change in the status of the policy.

CONSTRUCTION SPECIFICATION

2. CLEARING AND GRUBBING

1. **SCOPE**

The work shall consist of the clearing and grubbing of designated areas by removal and disposal of trees, snags, logs, stumps, shrubs, and rubbish.

2. **MARKING**

The limits of the areas to be cleared and grubbed will be marked by means of stakes, flags, tree markings, or other suitable methods. Trees to be left standing and uninjured will be designated by special markings placed on the trunks at a height of about six feet above the ground surface.

3. **REMOVAL**

All trees and brush within the designated clearing and grubbing limits will be removed. Unless otherwise specified, all stumps, roots, and root clusters having a diameter of one inch or larger shall be grubbed out to a depth of at least two feet below subgrade elevation for concrete structures.

4. **DISPOSAL**

All trees and brush removed will be disposed of by the Contractor at locations approved by the Engineer.

5. **MEASUREMENT AND PAYMENT**

(Method 1) For items of work for which specific unit prices are established in the contract, the cleared and grubbed areas will be measured to the nearest 0.1 acre. Payment for clearing and grubbing will be made at the contract unit price and shall constitute full compensation for all labor, equipment, tools, and all other items necessary and incidental to the completion of the work.

(Method 2) For items of work for which specific unit prices are established in the contract, each tree, stump and snag having a diameter of 4-inches or greater and each log having a diameter of 4-inches or greater and length of 10-feet or greater will be measured prior to removal. The size of each tree and snag will be determined by measuring its trunk at breast height above the natural ground surface. The size of each log will be determined by measuring the butt and by measuring its length from butt to tip. The size of each stump will be measured at the top. Diameter shall be determined by dividing the measured circumference by 3.14.

Payment for clearing and disposal of each tree, stump and snag having a diameter of 4-inches or greater and each log having a diameter of 4-inches or greater and a length of 10-feet or greater will be made at the contract unit price for its size designation as determined by the following schedule:

<u>Measured Diameter</u>	<u>Size Designation</u>
4 inches to 8 inches	6-inch size
Over 8 inches to 12 inches	10-inch size
Over 12 inches to 24 inches	18-inch size
Over 24 inches to 36 inches	30-inch size
Over 36 inches to 60 inches	48-inch size
Over 60 inches	60-inch size

The sum of such payments shall constitute full compensation for all labor, equipment, tools, and all other items necessary and incidental to the work of completely clearing and grubbing the designated areas, including clearing, grubbing, and disposal of smaller trees, stumps, snags, and logs and brush, shrubs, roots and rubbish.

(Method 3) For items of work for which specific lump sum prices are established in the contract, payment for clearing and grubbing will be made at the contract lump sum price. Such payment shall constitute full compensation for all labor, equipment, tools, and all other items necessary and incidental to completion of the work.

(Use with all Methods) Compensation for any item of work described in the contract but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and the items to which they are made subsidiary are identified in Section 6 of this specification.

6. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

a. Bid Item 1, Clearing and Grubbing

1. This item shall consist of removing and disposing of all trees, brush, debris, and rubbish within the designated clearing and grubbing limits, or as directed by the Engineer.
2. Contractor will be required to dispose of all trees, brush, and debris. Disposal area will be approved by the Engineer.
3. Measurement and Payment will be by Method 3.

CONSTRUCTION SPECIFICATION

8. MOBILIZATION

1. **SCOPE**

The work shall consist of mobilization of the Contractor's forces and equipment necessary for performing the work required under the contract.

It shall include the purchase of contract bonds, transportation of the personnel, equipment, and operating supplies to the site; establishing of office, buildings, construction signing in accordance with the manual on "Uniform Traffic Control Device", and other necessary facilities at the site; and other preparatory work at the site.

It shall not include mobilization for any specific item of work for which payment for mobilization is provided elsewhere in the contract.

This specification covers mobilization of work required by the contract at the time of award. If additional mobilization costs are incurred during performance of the contract as a result of change or added items of work for which the Contractor is entitled to an adjustment in contract price, compensation for such costs will be included in the price adjustment for the items of work changed or added.

2. **PAYMENT**

Payment will be made as the work proceeds, after presentation of invoices by the contractor showing his own mobilization costs and evidence of the charges of suppliers, subcontractors, and others for mobilization work performed by them. If the total of such payments is less than the contract lump sum for mobilization, the unpaid balance will be included in the final contract payment. Total payment will be the lump sum contract price for mobilization, regardless of actual cost to the Contractor.

Payment will not be made under this item for the purchase costs of materials having a residual value, the purchase costs of materials to be incorporated into the project, or the purchase costs of operating supplies.

Payment of the lump sum contract price for mobilization will constitute full compensation for all labor, materials, equipment, and all other items necessary and incidental to completion of the work.

Compensation for any item of work described in the contract but not listed on the bid

schedule will be included in the payment for the item or work to which it is made subsidiary. Such items and the items to which they are made subsidiary in Section 3 of this specification.

3. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

Items of work to be performed in conformance with this specification and the construction details are:

a. **Bid Item 2- Mobilization**

1. This item shall consist of the contract bonds, insurance, construction safety signing, flagging, and mobilization of the Contractor's forces and equipment, as defined in Section 1, required for performing the work under this contract.
2. Contractor shall provide, erect, and maintain all necessary traffic control devices in conformance with the Manual on Uniform Traffic Control Devices. The cost of traffic control, flagging, and providing for public safety will be paid for under this bid item
3. Payment will be made in accordance with Section 2.

CONSTRUCTION SPECIFICATIONS

10. BITUMINOUS SURFACE COURSE

1. SCOPE

The work shall consist of the construction of a surface course composed of mineral aggregate and bituminous binder, placed and compacted within the lines and grades shown on the plans.

2. MATERIALS

- a. Asphaltic Cements: Viscosity grades of asphalt cement prepared from petroleum shall conform to the requirements of AASHTO Designation M-226.
- b. Asphaltic Emulsions: Anionic emulsified asphalt shall conform to the requirements of AASHTO Designation M-140.
- c. Mineral Aggregate: Mineral aggregate shall consist of crusher processed virgin aggregate material consisting of crushed stone, and gravel, conforming to the following requirements:
 1. Course aggregate retained on the No. 4 sieve shall consist of clean, hard, tough, durable, and sound fragments, with not more than 3 percent by weight of flat, elongated, soft or disintegrated particles, and shall be free from vegetable matter or other deleterious substances.
 2. That portion of the aggregate retained as the No. 4 sieve shall have not less than 50% of particles by weight with at least two mechanically fractured face, or clean angular face.
 3. The aggregate shall have a percentage of wear not exceeding 50% for road mix and 40% for plant mix, when tested in accordance with AASHTO Designation T-96. The Contractor shall certify that the mineral aggregate used on the job shall meet this wear test prior to its placement in the surface course.
 4. Fine aggregate passing the No. 4 sieve, may be either a natural or manufactured product. The aggregate shall be clean, hard-grained and moderately sharp, and shall contain not more than 2 percent by weight of vegetable matter or other deleterious substances.
 5. That portion of the fine aggregate passing the No. 40 sieve shall be

nonplastic when tested in accordance with AASHTO Designation T-90.

6. The weight of minus 200 mesh sieve material retained in the aggregate as determined by the difference in percent passing a No. 200 sieve by washing and dry sieving without washing shall not exceed 6 percent of the total sample weight.
7. The combined mineral aggregate plus any specified additives, when mixed with the specified bituminous binder in accordance with ASTM Designation D-1559, shall conform to the following requirements:

Marshall Stability.....1200-2500 lbs.
Flow (0.01 inch).....10-18
Voids content.....1.5% to 3.0%

The requirements specified in this subsection shall be used to determine the suitability of the aggregate sources.

8. The combined dry mineral aggregate shall be uniformly graded and of such size that it meets one of the following gradation bands:

½" Gradation

	<u>Ideal Gradation of Passing Band</u>	<u>% Passing Gradation Band</u>
½"	100	100
#4	70	60-80
#16	35	28-42
#50	17	11-23
#200	7	5-9

Any deviation from the above gradation Bands must be approved in writing by the Engineer.

9. Contractor will be required to supply the Engineer with a job mix formula based on the proceeding criteria. Job mix formula must be approved by the Engineer

3. CONSTRUCTION METHODS

- a. Hot Mix Plant: The mineral aggregate and bituminous binder shall be mixed at a central mixing plant. The shortest mixing time consistent with satisfactory coating of the aggregate shall be used, as determined by the Engineer. The mineral aggregate shall be considered satisfactorily coated with bitumen when all of the particles passing the No. 4 sieve and 98 percent of the particles retained on the No.4 sieve are coated.
- b. Spreading and Compaction: Place asphalt concrete pavement of 3-inches or more, in total compacted thickness, in two equal courses. The mixture shall be spread and struck-off in such a manner that finished surface shall conform to the elevations, grades, and cross-sections shown on the drawings or as staked in the field.

After the mixture has been spread, the surface shall be longitudinally rolled, beginning at the outside edge or lower side and proceeding toward the high side. Each pass of one roller shall overlap the proceeding pass by at least one-half the width of the roller. The surface shall be rolled by 4 passes with a pneumatic or steel-wheel exerting a minimum pressure of 40 psi., or by an approved equal method. Rolling operations shall be conducted in such a manner that shoving or distortion will not develop beneath the roller.

- c. Finishing: The surface shall be finished to a smooth, uniform line and grade with surface deviations not exceeding 3/8-inch in 10 feet. Determination of compliance with smoothness may be made with a straight edge, chalk-line, or profilograph at the option of the Engineer. Any irregularities shall be satisfactorily corrected at the expense of the Contractor.
- d. Temperature Control: The minimum temperature of the bituminous material at the time of application shall be 250 degrees Fahrenheit.
- e. Weather Limitations: Bituminous material shall not be placed when weather conditions are unfavorable or when the air temperature in the shade is less than 50 degrees Fahrenheit.
- f. Weight Devices: When the method of measurement is by weight, the Contractor shall provide weigh scales, at the job site. Scales will be certified by the Department of Agriculture.

The scales shall be accurate to within 1 percent of the correct weight throughout the range of use. Before using the scales and as frequently thereafter as the Engineer determines necessary to insure accuracy, the Contractor shall have the scales checked, adjusted, and certified by a representative of the State agency. The Contractor shall maintain the scales to the required accuracy.

- g. Sampling of Aggregate: The Contractor shall submit test results and a certification of compliance that states that the gradation of the aggregate meets the contract requirements. The Contractor shall equip crushing, screening, and mixing plants with sampling devices. The Contractor shall take additional samples of material for testing as directed by the Engineer. These samples may be required at any time to validate the certification furnished by the Contractor.

Provisions shall be made for accurate proportioning. Each compartment shall have an outlet feed that can be shut off completely when any bin becomes empty. The bins or aggregate feeding system shall be constructed so samples can be readily obtained.

Positive weight measurement of the combined cold feed shall be maintained to allow regulation of the feed gate and permit automatic correction for variations in load.

The bitumen feed control shall be coupled with the total aggregate weight measurement device to automatically vary the bitumen feed rate and to maintain the required proportion. Means shall be provided for checking the quantity or rate of flow of bitumen into the mixing unit. Thermometers shall be fixed in the bitumen feed line at the charging valve of the mixer unit and at the discharge chute of the mixer unit. The Engineer may require replacement of any thermometer by an approved temperature-recording apparatus to allow better regulation of the material temperature.

A method shall be provided to automatically adjust the bituminous content in the mix for moisture variations in the cold feed.

- h. Hauling Equipment: Trucks used for hauling bituminous mixtures shall have tight, clean, smooth metal beds that have been thinly coated with a material to prevent the moisture from adhering to the beds. Truck beds shall be drained prior to loading. Each truck shall have a cover to protect the mixture from the weather. When necessary to insure that the mixture will be delivered at the specified temperature, truck beds shall be insulated and covers shall be securely fastened.
- I. Bituminous Pavers: Bituminous pavers shall be self-contained, power-propelled units, provided with an adjustable activated-screed or strike-off assembly heated, if necessary, and capable of spreading and finishing courses of bituminous plant mix material in lane widths and thicknesses shown on the drawings. When shown on the drawings, pavers shall be equipped with a control system capable of automatically maintaining the proper screed elevation. The control system shall be automatically actuated from either a reference line or surface through a system of sensors that will maintain the paver screed at a predetermined transverse slope and at the proper elevation to obtain the required surface.

The transverse slope control system shall be capable of being made inoperative so that the screed can be controlled by mechanisms that will independently control the elevation of each end of the screed from reference line or surfaces.

The controls shall be capable of working in conjunction with any of the following attachments:

1. Ski-type device of not less than 40 feet in length.
 2. Taut stringline (wire) set to grade.
 3. Short ski or shoe.
- j. Compaction shall be performed with either vibratory steel-wheel or steel-wheel and pneumatic-tire rollers.

Rolling shall begin at the sides and proceed longitudinally parallel to the road centerline, each trip overlapping one-half the roller width, gradually progressing to the center. When paving in echelons or abutting a previously placed land, the longitudinal joint shall be rolled first, then followed by the above rolling procedure. On superelevated curves the rolling shall begin at the low side and progress to the high side.

Along forms, curbs, header walls, and other places not accessible to the rollers, the mixture shall be thoroughly compacted with hot hand tampers, smoothing irons, or mechanical tampers.

- k. Joints, trimming edges, and cleanup: Placing of the bituminous mixture shall be continuous. Rollers shall not pass over the unprotected end of a freshly laid mixture. Transverse joints shall be formed by cutting back into the previous run to expose the full depth of the course. Heat shall be applied to contact surfaces or transverse joints just before any additional mixture is placed against the previously rolled material.

4. FLUSH COAT

When required, the coat shall be placed on the completed surface course. The coat shall not be placed within 7 days after the surface course is laid. Prior to placing the coat, the existing surface shall be cleaned of all dirt, sand, dust, or other objectionable material.

The material shall be sprayed over the prepared surface by means of a pressure distributor.

5. ACCEPTANCE SAMPLING AND TESTING

- a. Finished work samples. When required by the Engineer, the Contractor shall cut samples from the pavement. Samples size and locations will be designated by the Engineer. Samples shall be neatly cut with a saw or core drill. Voids left by sampling shall be backfilled and compacted to the density of the surrounding material.
- b. The Engineer will perform the testing of bituminous mixture (gradation and bituminous content). Acceptance samples of the mixture will be taken after it has been placed on the finished surface and just prior to compaction. Samples will be selected on a random basis and taken as frequently as the Engineer elects.
- c. Acceptance and testing bituminous mixture (compaction). After the bituminous mixture has been placed and compacted, the pavement shall meet the following density requirements.

Percent of Relative
Maximum Density
From Job Mix Formula
93 min.

Samples and test will be taken as frequently and at such locations as the Engineer elects. Compaction testing will be done by the Engineer.

- d. Acceptance sampling and testing of bituminous mixture (surface and thickness tolerance).
 1. Surface. Acceptance testing will be performed on the top surface. The surface will be tested by the Engineer with a straightedge. The variation of the surface from the testing edge of the straightedge shall not deviate at any point more than 1/8-inch.
 2. Thickness. The total compacted thickness of the mixture shall not vary more than 1/4-inch from the specified thickness. The compacted thickness shall not consistently be below nor consistently above the specified thickness. The Engineer reserves the right to test areas which appear defective and require immediate correction.

6. Price Adjustments

1. Gradation and Asphalt Content – See Table A. The computation of the adjusted unit price will be based upon the minimum pay factor determined from Table A.
 - a. The Engineer may order the removal of the mix if the acceptance tests deviate from the job-mix formula for a particular sieve or sieves, or if the asphalt content is more than the values shown under the 0.70 pay factor for asphalt concrete in Table A.
 - b. The pay factor for material allowed to remain will be 0.50 for asphalt concrete.
 - c. A lot is the average of three tests taken in the same day and represents the number of square feet placed during each production day.

2. Density

- a. Areas with deficient density will be subject to the following price reductions:

TABLE A	PAY FACTOR
AVERAGE DENSITY IN PERCENT	ASPHALT CONCRETE
93 or more	1.00
91 to 92.9	0.90
Less than 91	0.50

TABLE A		
ACCEPTANCE SCHEDULE FOR GRADATION		
(Percentage Points)		
SIEVE SIZE	PAY FACTOR A.C.	DEVIATIONS OF THE IDEAL GRADATION ACCEPTANCE TESTS FROM THE JOB-MIX (PERCENTAGE POINTS)
Asphalt Content	1.00	0-0.38
	0.95	0.39-0.43
	0.90	0.44-0.47
	0.80	0.48-0.52
	0.70	0.53-0.56

½ inch & larger	1.00	0-1
	0.95	1.0-2.0
	0.90	2.0-3.0
	0.80	3.0-4.0
	0.70	4.0-5.0
No. 4	1.00	0-10
	0.95	10-11.4
	0.90	11.5-11.9
	0.80	11.9-12.5
	0.70	12.5-13.0
No. 16	1.00	0-7.0
	0.95	7.0-7.3
	0.90	7.4-7.7
	0.80	7.8-8.1
	0.70	8.2-8.4
No. 50	1.00	0-6.0
	0.95	6.0-6.5
	0.90	6.6-6.8
	0.80	6.9-7.1
	0.70	7.2-7.5
No. 200	1.00	0-2.0
	0.95	2.0-2.9
	0.90	3.0-3.1
	0.80	3.2-3.3
	0.70	3.4-3.5

7. MEASUREMENT AND PAYMENT

- a. The bituminous material and mineral aggregate shall be measured by the square foot.
- b. Tack coat is required on all seams and overlays and will be subsidiary to this Bid Item and not paid for separately.
- c. Payment for the bituminous material, mineral aggregate will be made at the contract unit price. Such payment shall constitute full compensation for furnishing, mixing, spreading, the bituminous material and mineral aggregate, compacting all other items necessary and incidental to the performance of the work.

8. ITEMS OF WORK AND CONSTRUCTION DETAILS

Items of work to be performed in conformance with this specification and construction details are:

a. Bid Item 3, 3" HMA AC-10 (1/2-inch Max.)

1. This item shall consist of furnishing the mineral aggregate, bituminous material, mixing the aggregate and bituminous material, spreading, and compacting the mixture as shown on the drawings.
2. Contractor will supply the Engineer with the mix calibration factor, and a set of calibration samples 7 days prior to placement of asphalt.
3. The aggregate shall meet the gradation requirements as listed in Section 2.C.8 of these specifications. The gradation of the aggregate shall be submitted in writing to the Engineer for his approval prior to the placing of the asphalt. The borrow area selected by the Contractor must meet the approval of the Engineer.
4. The asphalt shall be grade AC-10, viscosity graded.
5. The aggregates and the bituminous material shall be measured or gaged and introduced into the mixer in the amount specified by the job mix formula.

After the required amounts of aggregate and bituminous material have been introduced into the mixer, the materials shall be mixed until a complete and uniform coating of particles and a thorough distribution of the bituminous material throughout the aggregate is obtained.
6. On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture may be placed and finished by hand tools.
7. Hot mixture shall be placed at a temperature not less than 250 degrees Fahrenheit.
8. Material trimmed from the edges and any other discarded bituminous mixture shall be removed from the runway and disposed of by the Contractor in an approved area.
9. Contractor will be required to hand rake all seams.
10. Testing noted in Section 5.a will not be required.

11. Asphalt shall be placed at the finished depth noted on the plans. Tack coat will be required on all asphalt edges.
12. Contractor will not stockpile hot asphalt on existing asphalt roads prior to placement.
13. Bituminous surface course will not be placed during rain, when the roadbed is wet or during other adverse weather conditions. The owner will not be responsible for any bituminous surface course that is on the project site, but unable to spread due to adverse weather.
14. Contractor will be required to deliver to the Engineer a weight invoice prior to placement of the asphalt surface course, invoices not received the day of placement will not be paid for.
15. Contractor will hand sweep and remove all sluffage on and against asphalt and concrete gutters just prior to bituminous surface course placement to assure a clean surface and proper depth.
16. Measurement and payment shall be in accordance with Section 7a and c for each type of asphalt concrete pavement actually placed.

b. Bid Item 4, 2" HMA Overlay AC-10 (1/2-inch Max.)

1. This item shall consist of furnishing the mineral aggregate, bituminous material, mixing the aggregate and bituminous material, spreading, and compacting the mixture as shown on the drawings.
2. Contractor will supply the Engineer with the mix calibration factor, and a set of calibration samples 7 days prior to placement of asphalt.
3. The aggregate shall meet the gradation requirements as listed in Section 2.C.8 of these specifications. The gradation of the aggregate shall be submitted in writing to the Engineer for his approval prior to the placing of the asphalt. The borrow area selected by the Contractor must meet the approval of the Engineer.
4. The asphalt shall be grade AC-10, viscosity graded.
5. The aggregates and the bituminous material shall be measured or gaged and introduced into the mixer in the amount specified by the job mix formula.

After the required amounts of aggregate and bituminous material have been introduced into the mixer, the materials shall be mixed until a complete and uniform coating of particles and a thorough distribution of the bituminous material throughout the aggregate is obtained.

6. On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture may be placed and finished by hand tools.
7. Hot mixture shall be placed at a temperature not less than 250 degrees Fahrenheit.
8. Material trimmed from the edges and any other discarded bituminous mixture shall be removed from the runway and disposed of by the Contractor in an approved area.
9. Contractor will be required to hand rake all seams.
10. Testing noted in Section 5.a will not be required.
11. Asphalt shall be placed at the finished depth noted on the plans. Tack coat will be required on all asphalt edges.
12. Contractor will not stockpile hot asphalt on existing asphalt roads prior to placement.
13. Bituminous surface course will not be placed during rain, when the roadbed is wet or during other adverse weather conditions. The owner will not be responsible for any bituminous surface course that is on the project site, but unable to spread due to adverse weather.
14. Contractor will be required to deliver to the Engineer a weight invoice prior to placement of the asphalt surface course, invoices not received the day of placement will not be paid for.
15. Contractor will hand sweep and remove all sluffage on and against asphalt and concrete gutters just prior to bituminous surface course placement to assure a clean surface and proper depth.
16. Measurement and payment shall be in accordance with Section 7a and c for each type of asphalt concrete pavement actually placed.

c. Bid Item 5, Pavement and Concrete Sawing

1. This item shall consist of furnishing the equipment and labor required to saw cut the existing asphalt pavement and existing sidewalk as staked in the field.
2. Saw cut edges shall be required where existing bituminous surface and new bituminous surface join. The edge shall be clean, vertical and full depth of bituminous surface. Cutting the edge shall be made just prior to placing new bituminous pavement. A tack coat will be applied to the edge prior to placing new bituminous pavement.
3. A diamond saw shall be required to make a vertical cut through the full depth of the asphalt surfacing and concrete sidewalk.
4. Traffic or construction equipment shall not be allowed to cross the saw cut edge. If sawed edges are broken due to construction equipment the damaged area will be recut at the Contractor's expense, Owner will not pay for recutting of damaged areas.
5. Measurement will be by the linear foot actually cut. Payment shall be at the contract unit price. Such payment shall constitute full compensation for saw cutting the existing asphalt surface, and sidewalk, including all equipment and labor as necessary or incidental to the completion of the work.

CONSTRUCTION SPECIFICATION

23. EARTH FILL

1. **SCOPE**

The work shall consist of the construction of earth embankments and other earth fills required by the drawings and specifications.

2. **MATERIALS**

All fill materials shall be obtained from required excavations and designated borrow areas. The selection, blending, routing and disposition of materials in the various fills shall be subject to approval by the Engineer.

Fill materials shall contain no sod, brush, roots or other perishable materials. Rock particles larger than the maximum size specified for each type of fill shall be removed prior to compaction of the fill.

The type of material used in the various fills shall be as listed and described in the specifications and drawings.

3. **FOUNDATION PREPARATION**

Foundations for earth fill shall be stripped to remove vegetation and other unsuitable materials or shall be excavated as specified.

Except as otherwise specified, earth foundation surfaces shall be graded to remove surface irregularities and shall be scarified parallel to the axis of the fill or otherwise acceptably scored and loosened material shall be controlled as specified for the earth fill, and the surface materials of the foundation shall be compacted and bonded with the first layer of earth fill as specified for subsequent layers of earth fill.

Earth abutment surfaces shall be free of loose, un-compacted earth in excess of two inches in depth normal to the slope and shall be at such a moisture content that the earth fill can be compacted against them to effect a good bond between the fill and the abutments.

Rock foundation and abutment surfaces shall be cleared of all loose materials by hand or other effective means and shall be free of standing water when fill is placed upon them.

Occasional rock outcrops in earth foundations for earth fill, except in dams and other structures designed to restrain the movement of water, shall not require special treatment if they do not interfere with compaction of the foundation of initial layers of the fill or the bond between the foundation and the fill.

Foundation and abutment surfaces shall be not steeper than 1 horizontal to 1 vertical unless otherwise specified. Test pits or other cavities shall be filled with compacted earth fill conforming to the specifications for the earth fill to be placed upon foundation.

4. **PLACEMENT**

Fill shall not be placed until the required excavation and foundation preparation have been completed and the foundation has been inspected and approved by the Engineer. Fill shall not be placed upon a frozen surface, nor shall snow, ice, or frozen material be incorporated in the fill.

Fill shall be placed in approximately horizontal layers, The thickness of each layer before compaction shall not exceed the maximum thickness specified. Materials placed by dumping in piles or windows shall be spread uniformly to no more than the specified thickness before being compacted. Hand compacted fill, including fill compacted by manually directed power tampers, shall be placed in layers whose thickness before compaction does not exceed 4-inches.

Adjacent to structures, fill shall be placed in a manner which will prevent damage to the structures and will allow the structures to assure the loads from the fill gradually and uniformly. The height of the fill adjacent to a structure shall be increased at approximately the same rate on all sides of the structure.

Earth fill in dams, levees and other structures designed to restrain the movement of water shall be placed so as to meet the following additional requirements:

- a. The distribution of materials throughout each zone shall be essentially uniform, and the fill shall be free from lenses, pockets, streaks or layers of material differing substantially in texture or gradation from the surrounding material.
- b. If the surface of any layer becomes too hard and smooth for proper bond with the succeeding layer, it shall be scarified parallel to the axis of the fill to a depth of not less than 2 inches before the next layer is placed.
- c. The top surface of embankments shall be maintained approximately level during construction, except that a crown or cross-slope of not less than 2 percent shall be maintained to insure effective drainage, and except as otherwise specified for drain fill zones. If the drawings or specifications require, or the Engineer directs, that the fill be placed at a higher level in one part of an embankment than another, the top surface of each part shall be maintained as specified above.
- d. Dam embankments shall be constructed in continuous layers from abutment to abutment except where openings to facilitate construction, or to allow the passage of stream flow during construction, is specifically authorized in the contract.

- e. Embankment built at different levels as described under c or d above shall be constructed so that the slope of the bonding surfaces between embankment to be placed is not steeper than 3 feet horizontal to 1 foot vertical. The bonding surface of the embankment in place shall be stripped of all loose material, and shall be scarified, moistened and recompacted when the new fill is placed against it as needed to insure a good bond with the new fill and to obtain the specified moisture content and density in the junction of the place and new fill.

5. **CONTROL OF MOISTURE CONTENT**

During placement and compaction of fill, the moisture content of the materials being placed shall be maintained within the specified range.

The application of water to the fill materials shall be accomplished at the borrow areas insofar as practicable. Water may be applied by sprinkling the materials after placement on the fill, if necessary. Uniform moisture distribution shall be obtained by dicing, blending or other approved methods prior to compaction of the layer.

Material that is too wet when deposited on the fill shall either be removed or be dried to the specified content prior to compaction.

If the top surface of the preceding layer of compacted fill or a foundation or abutment surface in the zone of contact with the fill becomes too dry to permit suitable bond it shall be scarified and moistened by sprinkling to an acceptable moisture content prior to placement of the next layer of fill.

6. **COMPACTION**

Earth fill shall be compacted according to the following requirements for the class of compaction specified:

Class A compaction. Each layer of fill shall be compacted as necessary to make the density of the fill matrix not less than the minimum density specified. The fill matrix is defined as the portion of the fill material finer than the maximum particle size used in the compaction test method specified.

Class B compaction. Each layer of fill shall be compacted as to a mass density not less than the minimum density specified.

Class C compaction. Each layer of fill shall be compacted by the specified number of passes of the type and weight of roller or other equipment specified or by an approved equivalent method. Each pass shall consist of at least one passage of the roller wheel or drum over the entire surface of the layer.

Fill adjacent to structures shall be compacted a density equivalent to that of the surrounding fill by means of hand tamping if permitted by the Contracting Officer, or manually directed power tampers or plate vibrators. Heavy equipment shall not be operated within 2 feet of any structure. Vibrating rollers shall not be operated within 5 feet of any structure. Compaction by means of drop weights operating from a crane or hoist will not be permitted.

The passage of heavy equipment will not be allowed: (1) over cast-in-place conduits prior to 14 days after placement of the concrete; (2) over cradled precast conduits prior to 7 days after placement of the concrete cradle, or (3) over any type of conduit until the backfill has been placed above the top surface of the structure to a height equal to one-half the clear span width of the structure or pipe or 2 feet, whichever is greater.

Compacting of fill adjacent to structures shall not be started until the concrete has attained the strength specified in Specification No. 32, Concrete, for this purpose.

The strength will be determined by compression testing of test cylinders cast by the Engineer for this purpose and cured at the work site in the manner specified in ASTM Method C 31 for determining when a structure may be put into service.

When the required strength of the concrete is not specified as described above, compaction of fill adjacent to structures shall not be started until the following time intervals have elapsed after placement of the concrete.

<u>Structure</u>	<u>Time Interval</u>
Retaining walls and counterforts	14 days
Walls backfilled on both sides simultaneously	7 days
Conduits and spillway risers, cast-in- place (with inside forms in place)	7 days
Conduits and spillway risers, cast-in- place (inside forms removed)	14 days

<u>Structure</u>	<u>Time Interval</u>
Conduits, precast & cradled	2 days
Conduits, precast & bedded	1 day

Antiseep collars and cantilever
outlet bents

3 days

7. **REMOVAL AND PLACEMENT OF DEFECTIVE FILL**

Fill placed at densities lower than the specified minimum density or at moisture contents outside the specified acceptable range of moisture content or otherwise not conforming to the requirements of the specifications shall be reworked to meet the requirements or removed and replaced by acceptable fill. The replacement fill and the foundation, abutment and fill surfaces upon which it is placed shall conform to all requirements of this specification for foundation preparation, approval, placement, moisture control and compaction.

8. **TESTING**

During the course of the work, the Contractor will perform such tests as are required to identify materials, to determine compaction characteristics, to determine content, and to determine density of fill in place. These tests performed by the Contractor will be used to verify that the fills conform to the requirements of the specifications.

Densities of fill requiring Class A compaction will be determined by the Engineer in accordance with ASTM Method D 1557 (or by equivalent methods), except that the volume and moist weight of included rock particles larger than those used in the compaction test method specified for the type of fill will be determined and deducted from the volume and moist weight of the total sample prior to computation of density. The density so computed will be used to determine the percent compaction of the fill matrix.

9. **MEASUREMENT AND PAYMENT**

For items of work for which specific unit prices are established in the contract, the volume of each type and compaction class of earth fill within the specified zone boundaries and pay limits will be measured and computed to the nearest cubic yard by the method of average cross-sectional end areas. Unless otherwise specified, no deduction in volume will be made for embedded conduits and appurtenances.

The pay limits shall be as defined below, with the further provision that earth fill required to fill voids resulting from over-excavation of the foundation, outside specified lines and grades, will be included in the measurement for payment only where such over-excavation is directed by the Engineer to remove unsuitable material and where the unsuitable condition is not a result of the Contractor's operations.

(Method 1) The pay limits shall be as designated on the drawings.

(Method 2) The pay limits shall be the measured surface of the foundation when approved for placement of the fill and the specified neat lines of the fill surface.

(Method 3) The pay limits shall be the measured surface of the foundation when approved for placement of the fill and the measured surface of the completed fill.

(Method 4) The pay limits shall be the specified pay limits for excavation and the specified neat lines of the fill surface.

(Method 5) The pay limit shall be the specified pay limits for excavation and the measured surface of the completed fill.

(Use Method 6 or 7 with all Methods 1 through 5)

(Method 6) Payment for each type and compaction class of earth fill will be made at the contract unit price for that type and compaction class of fill. Such payment will constitute full compensation for all labor, materials, equipment and all other items necessary and incidental to the performance of the work.

(Method 7) Payment for each type and compaction class of earth fill will be made at the contract unit price for that type and compaction class of fill. Such payment will constitute full compensation for all labor, materials, equipment and all other items necessary and incidental to the performance of the work, except furnishing, transportation, and applying water to the foundation and fill materials.

Water applied to the foundation and fill materials will be measured and payment will be made as specified in Construction Specification.

(Use with All Methods) Compensation for any item of work described in the contract but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and the items to which they are made subsidiary are identified in Section 10 of this specification.

10. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

Items of work to be performed in conformance with this specification and the construction details are:

- a. Bid Item 6, Untreated Base Course, 1-inch Minus.
 1. This item shall consist of providing, placing, watering, blading and compacting the untreated base course to the lines and grades as shown on the drawings or staked in the field.
 2. The dry mineral aggregate shall conform to the following gradation:

1 inch Gradation

<u>Sieve Size</u>	<u>Ideal Gradation % Passing</u>	<u>% Passing Gradation Band</u>
1"	100	100
½"	85	79-91
#4	55	49-61
#16	31	27-35
#200	9	7-11

3. Price Adjustments - Gradation - See Table 1. The computation of the adjusted unit price will be based upon the minimum pay factor determined from Table 1.
 - a. The Engineer may order the removal of the material if the acceptance tests deviate more than the 0.70 pay factor from the gradation specifications outlined.
 - b. The Engineer will determine the area requiring adjustment. This will be accomplished by additional testing.
 - c. If the material is allowed to remain the pay factor will be 0.50.

Table 1 Follows.

TABLE 1 ACCEPTANCE SCHEDULE FOR GRADATION (Percentage Points) – IDEAL GRADATION		
SIEVE SIZE	PAY FACTOR	DEVIATION
½ inch & larger	1.00	0-6.0
	0.95	6.0-9.0
	0.90	9.0-12.0
	0.80	12.0-14.0
	0.70	14.0-15.0
No. 4	1.00	0-6
	0.95	6.1-7.0
	0.90	7.1-7.7

	0.80	7.8-8.0
	0.70	8.1-8.8
No. 16	1.00	0-4.0
	0.95	4.0-5.4
	0.90	5.5-6.0
	0.80	6.1-7.0
	0.70	7.1-7.7
No. 50	1.00	0-5.2
	0.95	5.3-6.0
	0.90	6.1-6.5
	0.80	6.6-7.4
	0.70	7.5-8.1
No. 200	1.00	0-2.0
	0.95	2.0-2.6
	0.90	2.7-2.9
	0.80	3.0-3.3
	0.70	3.4-3.6

4. The base course gravel shall uniformly be mixed with water prior to compaction.
5. Compaction shall be by Method A. Also the earth foundation shall be moistened and compacted to acquire at least ninety-five percent (95%) of the maximum density as determined in accordance with AASHTO Designation T-99, method D.
6. The aggregate shall have a percentage wear not exceeding 50% when tested in accordance with AASHTO designation T-96. Certification that the aggregate meets this wear test will be required of the Contractor prior to his placement of the base course.
7. The moisture content of the material at the time of compaction shall be between + 2% optimum and - 2% of optimum.
8. The Contractor shall select the material source and submit certification the material meets these specifications to the Engineer for approval.
9. Measurement and Payment.

- a. The 1-inch Untreated Base Course shall be measured by the cubic yard in-place.
 - b. Payment for the 1-inch untreated base course will be made at the contract unit price. Such payment will constitute full compensation for furnishing, transporting and installing the 1-inch untreated base course and all other items necessary and incidental to the performance of the work.
- b. Bid Item 7, Borrow
1. This item shall consist of furnishing and placing the borrow material required to complete the parking area to the lines and grades shown on the drawings or as directed by the Engineer.
 2. Borrow will be supplied by the Park at the location shown on the drawings.
 3. The moisture content of the material at the time of compaction shall be between +2% optimum and -2% of optimum.
 4. Compaction shall be by Method A. Also, the earth foundation shall be moistened and compacted to acquire at least ninety-five percent (95%) of the maximum density as determined in accordance with AASHTO Designation T-99, Method D.
 5. Measurement and Payment shall be by Method 4 and Method 6 respectively.
- c. Bid Item 8, Obliterate Road
1. This item shall consist of the obliteration of the road as shown on the plans, or as directed by the Engineer. The top 6-inches of gravel material will be removed and used for borrow on the new parking lot as shown on drawings and shall include all labor and equipment necessary to complete the work.
 2. All asphalt and the existing culvert will be removed from the Park and disposed of correctly.
 2. Scarify the remaining surface with scarifications not more than 6-inches apart.
 3. Measurement will not be made. Payment will be at the contract unit price for this bid item. Such payment shall constitute full compensation for labor, equipment, and all other items necessary and incidental to completion of the

work.

CONSTRUCTION SPECIFICATION

32. CONCRETE FOR MINOR STRUCTURES

1. **SCOPE**

The work shall consist of furnishing, forming, placing, finishing and curing portland cement concrete as required to build the structure named in Section 25 of this Specification.

2. **MATERIALS**

Portland cement shall conform to the requirements of ASTM Specification C-150 for the specified type.

Aggregates shall conform to the requirements of ASTM Specification C-33 unless otherwise specified. The grading of coarse aggregates shall be as specified in Section 25.

Water shall be clean and free from injurious amounts of oil, salt, acid, alkali, organic matter or other deleterious substances.

Performed expansion joint filler shall conform to the requirements of ASTM Specification D 1752.

Waterstops shall conform to the requirements of the applicable ASTM specification for the specified kinds.

3. **CLASS OF CONCRETE**

Concrete for minor structure shall be classified as follows:

<u>Class of Concrete</u>	<u>Maximum Water Content (gallons/bag)</u>	<u>Minimum Cement Content (bags/cu.yd.)</u>
4000 PSI	7	6

4. **AIR CONTENT AND CONSISTENCY**

Unless otherwise specified, the slump shall be 2 to 4 inches. If air entrainment is specified, the air content by volume shall be 5 to 8 percent of the volume of the concrete.

When specified or when directed by the Engineer, a water-reducing, set-retarding admixture approved by the Engineer shall be used.

5. **DESIGN OF THE CONCRETE MIX**

The proportions of the aggregates shall be such as to produce a concrete mixture that will work readily into the corners and angles of the forms and around reinforcement when consolidated, but will not segregate or exude free water during consolidation.

Prior to placement of concrete, the Contractor shall furnish the Engineer, for approval, a statement of the materials and mix proportions (including admixtures, if any) he intends to use. The statement shall include evidence satisfactory to the Engineer that the materials and proportions will produce concrete conforming to this specification. The materials and proportions so stated shall constitute the "job mix." After a job mix has been approved, neither the source, character or grading of the aggregates nor the type or brand of cement or admixture shall be changed without prior notice to the Engineer. If such changes are necessary, no concrete containing such new or altered materials shall be placed until the Engineer has approved a revised job mix.

6. **INSPECTION AND TESTING**

The Engineer will have free entry to the plant and equipment furnishing concrete under the contract. Proper facilities shall be provided for the Engineer to inspect materials, equipment and processes and to obtain samples of the concrete. All tests and inspections will be conducted so as not to interfere unnecessarily with manufacture and delivery of the concrete.

7. **HANDLING AND MEASUREMENT OF MATERIALS**

Materials shall be stockpiled and batched by methods that shall prevent segregation or contamination of aggregates and insure accurate proportioning of the ingredients of the mix.

Cement shall be measured by weight or in bags of 94 pounds each. When cement is measured in bags, no fraction of a bag shall be used unless weighed.

Aggregates shall be measured by weight. Mix proportions shall be based on saturated, surface-dry weights. The batch weight of each aggregate shall be the required saturated, surface-dry weight plus the weight of surface moisture it contains.

Water shall be measured, by volume or by weight, to an accuracy within one percent of the total quantity of water required for the batch.

Admixtures shall be measured within a limit of accuracy of three percent.

8. **MIXERS AND MIXING**

Concrete shall be uniform and thoroughly mixed when delivered to the work. Variations in slump of more than 1 inch within a batch will be considered evidence of inadequate mixing and shall be corrected by increasing mixing time or other means.

For stationary mixers, the mixing time after all cement and aggregates are in the mixer drum shall not be less than 1 ½ minutes. When concrete is mixed in a truck mixer, the number of revolutions of the drum or blades at mixing speed shall be not less than 70 nor more than 100.

No mixing water in excess of the amount called for by the job mix shall be added to the concrete during mixing or hauling or after arrival at the delivery point.

9. **FORMS**

Forms shall be of wood, plywood, steel or other approved material and shall be mortar tight. The forms and associated false work shall be substantial and unyielding and shall be constructed so that the finished concrete will conform to the specified dimensions and contours. Form surfaces shall be smooth and free from holes, dents, sags or other irregularities. Forms shall be coated with a nonstaining form oil before being set into place.

Metal ties or anchorages within the forms shall be equipped with cones, she-bolts or other devices that permit their removal to a depth of at least one inch without injury to the concrete. Ties designed to break off below the surface of the concrete shall not be used without cones.

All edges that will be exposed to view when the structure is completed shall be chamfered, unless finished with molding tools as specified in Section 18.

10. **PREPARATION OF FORMS AND SUBGRADE**

Prior to placement of concrete the forms and subgrade shall be free of chips, sawdust debris, water, ice, snow, extraneous oil, mortar, or other harmful substances or coatings.

Any oil on the reinforcing steel or other surfaces required to be bonded to the concrete shall be removed. Rock surfaces shall be cleaned by air-water cutting, wet sandblasting or wire brush scrubbing, as necessary, and shall be wetted immediately prior to placement of concrete. Earth surfaces shall be firm and damp. Placement of concrete on mud, dried earth or uncompacted fill frozen subgrade will not be permitted.

Unless otherwise specified, when concrete is to be placed over drain fill, the contact surface of the drain fill shall be covered with a layer of asphalt-impregnated building paper or polyvinyl sheeting prior to placement of the concrete. Forms for weepholes shall extend through this layer into the drain fill.

Items to be embedded in the concrete shall be positioned accurately and anchored firmly.

Weepholes in walls or slabs shall be formed with nonferrous materials.

11. **CONVEYING**

Concrete shall be delivered to the site and discharged into the forms within 1 ½ hours after the introduction of the cement to the aggregates. In hot weather or under conditions contributing to quick stiffening of the concrete, the time between the introduction of the cement to the aggregates and discharge shall not exceed 45 minutes. The Engineer may allow a longer time, provided the setting time of the concrete is increased a corresponding amount by the addition of an approved set-retarding admixture. In any case, concrete shall be conveyed from the mixer to the forms as rapidly as practicable by methods that will prevent segregation of the aggregates or loss of mortar. Concrete shall not be dropped more than five feet vertically unless suitable equipment is used to prevent segregation.

12. **PLACING**

Concrete shall not be placed until the subgrade, forms and steel reinforcement have been inspected and approved. No concrete shall be placed except in the presence of the Engineer. The Contractor shall give reasonable notice to the Engineer each time he intends to place concrete. Such notice shall be far enough in advance to give the Engineer adequate time to inspect the subgrade, forms, steel reinforcement and other preparations for compliance with the specifications before concrete is delivered for placing.

The concrete shall be deposited as closely as possible to its final position in the forms and shall be worked into the corners and angles of the forms and around all reinforcement and embedded items in a manner to prevent segregation of aggregates or excessive laitance. Unless otherwise specified, slab concrete shall be placed to design thickness in one continuous layer. Formed concrete shall be placed in horizontal layers not more than 20 inches thick. Hoppers and chutes, pipes or “elephant trunks” shall be used as necessary to prevent splashing of mortar on the forms and reinforcing steel above the layer being placed.

Immediately after the concrete is placed in the forms, it shall be consolidated by spading, hand tamping or vibration as necessary to insure smooth surfaces and dense concrete. Each layer shall be consolidated to insure monolithic bond with the preceding layer. If the surface of a layer of concrete in place sets to the degree that it will not flow and merge with the succeeding layer when spaded or vibrated, the Contractor shall discontinue placing concrete and shall make a construction joint according to the procedure specified in Section 13.

If placing is discontinued when an incomplete horizontal layer is in place, the unfinished end of the layer shall be formed by a vertical bulkhead.

13. **CONSTRUCTION JOINTS**

Construction joints shall be made at the location shown on the drawings. If construction joints are needed which are not shown on the drawings, they shall be placed in locations approved by the Engineer.

Where a feather edge would be produced at a construction joint, as in the top surface of a sloping wall, an insert form shall be used so that the resulting edge thickness on either side of the joint is not less than 6 inches.

In walls and columns, as each lift is completed, the top surfaces shall be immediately and carefully protected from any condition that might adversely affect the hardening of the concrete.

Steel tying and form construction adjacent to concrete in place shall not be started until the concrete has cured at least 12 hours. Before new concrete is deposited on or against concrete that has hardened, the forms shall be retightened. New concrete shall not be placed until the hardened concrete has cured at least 12 hours.

Surfaces of construction joints shall be cleaned of all unsatisfactory concrete, laitance, coating or debris by washing and scrubbing with a wire brush or wire broom or by other means approved by the Engineer. The surfaces shall be kept moist for at least one hour prior to placement of the new concrete.

14. **EXPANSION AND CONTRACTION JOINTS**

Expansion and contraction joints shall be made only at locations shown on the drawings.

Exposed concrete edges and expansion and contraction joints shall be carefully tooled or chamfered, and the joints shall be free of mortar and concrete. Joint filler shall be left exposed for its full length with clean and true edges.

Preformed expansion joint filler shall be held firmly in the correct position as the concrete is placed.

When open joints are specified, they shall be constructed by insertion and subsequent removal of a wooden strip, metal plate or other suitable template in such a manner that the corners of the concrete will not be chipped or broken. The edges of open joints shall be finished with an edging tool prior to removal of the joint strips.

15. **WATERSTOPS**

Waterstops shall be held firmly in the correct position as the concrete is placed. Joints in the metal waterstops shall be soldered, brazed or welded. Joints in rubber or plastic waterstops shall be cemented, welded or vulcanized as recommended by the Manufacturer.

16. **REMOVAL OF FORMS**

Forms shall not be removed without the approval of the Engineer. Forms shall be removed in such a way as to prevent damage to the concrete. Supports shall be removed in a manner that will permit the concrete to take the stresses due to its own weight uniformly and gradually.

17. **FINISHING FORMED SURFACES**

Immediately after the removal of the forms:

- a. All fins and irregular projections shall be removed from exposed surfaces.
- b. On all surfaces, the holes produced by the removal of form ties, cone-bolts, and she-bolts, shall be cleaned, wetted and filled with a dry-pack mortar consisting of one part portland cement, three parts sand that will pass a No. 16 sieve, and water just sufficient to produce a consistency such that the filling is at the point of becoming rubbery when the material is solidly packed.

18. **FINISHING UNFORMED SURFACES**

All exposed surfaces of the concrete shall be accurately screened to grade and then wood float finished, unless specified otherwise.

Excessive floating or troweling of surfaces while the concrete is soft shall not be permitted.

The addition of dry cement or water to the surface of the screened concrete to expedite finishing shall not be allowed.

Joints and edges on unformed surfaces that will be exposed to view shall be chamfered or finished with molding tools.

19. **CURING**

Concrete shall be prevented from drying for a curing period of at least 7 days after it is placed. Exposed surfaces shall be kept continuously moist for the entire period, or until

curing compound is applied as specified below. Moisture shall be maintained by sprinkling, flooding, or fog spraying or by covering with continuously moistened canvas, cloth mats, straw, sand or approved material. Wood forms (except plywood) left in place during the curing period shall be kept wet. Formed surfaces shall be thoroughly wetted immediately after forms are removed and shall be kept wet until patching and repairs are completed. Water or covering shall be applied in such a way that the concrete surface is not eroded or otherwise damaged.

Concrete, except at construction joints, may be coated with an approved curing compound in lieu of continued application of moisture. The compound shall be sprayed on the moist concrete surfaces as soon as free water has disappeared, but shall not be applied to any; surface until patching, repairs and finishing of that surface are completed. The compound shall be applied at a uniform rate of not less than one gallon per 150 square feet of surface and shall form a continuous adherent membrane over the entire surface. Curing compound shall not be applied to surfaces requiring bond to subsequently placed concrete, such as construction joints, shear plates, reinforcing steel and other embedded items. If the membrane is damaged during the curing period, the damaged area shall be resprayed at the rate of application specified above.

20. **REMOVAL OF REPAIR**

When concrete is honeycombed, damaged or otherwise defective, the Contractor shall remove and replace the structure or structural member containing the defective concrete or, where feasible, correct or repair the defective parts. The Engineer will determine the required extent of removal, replacement or repair.

Prior to starting repair work the Contractor shall obtain the Engineer's approval of his plan for effecting the repair. The Contractor shall perform all repair work in the presence of the Engineer.

21. **CONCRETE IN COLD WEATHER**

Concrete shall not be mixed nor placed when the daily minimum atmospheric temperature is less than 40° F unless facilities are provided to prevent the concrete from freezing. The use of accelerators or antifreeze compounds will not be allowed.

22. **CONCRETE IN HOT WEATHER**

The Contractor shall apply effective means to maintain the temperature of the concrete below 90° F during mixing, conveying and placing.

23. **PRICE ADJUSTMENTS FOR STRENGTH**

When concrete is below specified strength:

1. Owner may accept item at a reduced price
2. The pay factor will be applied to the portion of the item which is represented by the strength tests that fall below specified strength.
3. Owner will calculate the pay factor as follows:

Psi below specified strength:	Pay Factor:
1 - 100	0.90
101 - 200	0.94
201-300	0.88
301 - 400	0.80
More than 400	0.50 or Engineer may reject

24. **MEASUREMENT AND PAYMENT**

For items of work for which specific unit prices are established in the contract, concrete will be measured to the neat lines shown on the drawings and the volume of the concrete will be computed to the nearest 0.1 cubic yard. Measurement of concrete placed against the sides of an excavation without the use of intervening forms will be made only to the neat lines or pay limits shown on the drawings. No deduction in volume will be made for chamfers, rounded or beveled edges or for any void or embedded item that is less than 3 cubic feet in volume.

Payment for each item of concrete for minor structures will be made at the contract unit price or the contract lump sum, whichever is applicable, for that item. Such payment will constitute full compensation for all labor, materials, equipment, transportation, tools, forms, false work, bracing and all other items necessary and incidental to the completion of the work, except items listed for payment elsewhere in the contract.

Compensation for any item of work described in the contract but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and the items to which they are made subsidiary are identified in Section 24 of this specification.

25. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

Items of work to be performed in conformance with this specification and the construction details include:

- a. Bid Item 9, 24-inch Colored Concrete Curb & Gutter

1. This item shall consist of furnishing materials, equipment and labor required to construct the concrete curb and gutter as shown on the drawings or as directed by the Engineer.
2. All cement used shall be Type V, meeting the requirements of ASTM C 150.
3. Concrete mix design will be in accordance with Section 5.
4. Minimum cement content will be 6 bags per cubic yard.
5. Class 2 course aggregate shall be size 57 (1" to No.4, ASTM C-33 Table II).
6. Air entrainment shall be required. Air content by volume shall be 5 to 8 percent of the volume of the cement.
7. The foundation shall be clean and free of all foreign material. The earth foundation shall be moistened and compacted to acquire at least 95 percent (95%) of the maximum density as determined in accordance with AASHTO Designation T-99, Method D.
8. Contractor will be required to apply curing compound as soon as finishing has been completed.
9. All concrete will be colored to match the existing concrete sidewalk and shall be mixed integrally.
10. Measurement and payment shall be at the contract unit and unit price. Such payment shall constitute full compensation for all materials, equipment and labor necessary or incidental to the completion of the work.

b. Bid Item 10, Reconstruct Utility Access

1. This item shall consist of adjusting the Utility Accesses to a grade which is flush with the improved surface of the parking lot in accordance with these Specifications.
2. Steel grade rings shall be of sufficient size to raise the existing utilities.
3. A steel ring shall be required around the finished asphalt grade as shown on the drawings.
4. Utilities in the new parking lot will be adjusted to the final HMA grade.

5. Contractor shall not allow dirt, rock or any other material to fall into the utilities.
6. Measurement will be by the number of utilities which are actually raised in accordance with these specifications. Payment will be at the contract unit price for each utility that is raised. Such payment shall constitute full and complete compensation for all labor, materials, equipment and other items necessary or incidental to the completion of the work.

c. Bid Item 11, 5-foot Colored Concrete Sidewalk

1. This item shall consist of forming, furnishing and placing the portland cement concrete, as required to construct the sidewalk, as shown on the drawings along with the necessary untreated base, excavation and fill.
2. All cement used shall be Type V.
3. Concrete shall be Class 4000.
4. Concrete mix design will be in accordance with Section 5.
5. Minimum cement content will be 6 bags per cubic yard.
6. Class 2 course aggregate shall be size 57 (1" to No. 4, ASTM C-33 Table II).
7. Air entrainment shall be required. Air content by volume shall be 5 to 8 percent of the volume of the cement.
8. The earth foundation under the base course shall be moistened and rolled by means of sheeps foot compactors.
9. Contractor will be required to apply curing compound as soon as finishing has been completed.
10. Fly ash will not be allowed in the concrete.
11. Three-inches of untreated base is required under the sidewalk and will not be measured but will be subsidiary to this Bid Item.
12. All concrete will be colored to match the existing sidewalk and shall be mixed integrally.
13. Contractor will be required to hand rake to a smooth surface all material

placed in back of the curb and gutter

14. Measurement and payment will be measured by the linear foot of sidewalk actually installed. Payment will be made at the contract unit price. The payment will constitute full compensation for all labor, materials, equipment, transportation, tools, forms, bracing, excavation, compacted fill, untreated base course, and all other items incidental to the completion of the concrete work.

d. Bid Item 12, Curb Inlet Box

1. This item shall consist of furnishing, and placing the concrete, reinforcing steel, frame, grate, and hood as required to construct the curb inlet boxes as required and as shown on the drawings, along with the necessary excavation, backfill, forming and curing to the lines and grades shown on the drawings
2. The curb inlet frame, “vv” grate, and curb hood shall be Model D&L I-3518, or an approved equal. It shall be installed on the drain box as shown on the drawings.
3. The top of the concrete box will be fitted to receive this curb inlet. The inlet will be graded to fit the flow line of the curb and gutter.
4. The cost of the inlet frame and attaching it to the concrete structure is paid for under this item.
5. Curb inlets will be flush with finished curb and gutter grade.
6. All material shown on the drawings will be paid for under this item.
7. Contractor will be required to cut the existing CMP and construct box as shown on the drawings.
8. Measurement shall be based upon the number of curb inlet boxes actually installed according to these specifications. Payment will be made according to the contract unit price for this bid item. Such payment shall constitute full compensation for all labor, materials (including excavations and backfill), equipment, transportation and all other items necessary and incidental to the completion of the work.

e. Bid Item 13, Remove 5-foot Sidewalk

1. This item shall consist of removing and disposing of the existing concrete sidewalks and ADA ramps as shown on the drawings.

2. Contractor shall be required to remove and dispose of the existing concrete as directed by the Engineer.
3. Removal will be paid by the linear foot.
4. Measurement will be by the linear foot of sidewalk removed. Payment will be made at the unit price for this item. Such payment will constitute full compensation for all labor, materials, equipment, transportation, tools, excavation, and all other items necessary and incidental to the completion of the work.

CONSTRUCTION SPECIFICATION

51. CORRUGATED METAL PIPE CONDUITS

1. **SCOPE**

The work shall consist of furnishing and placing circular, arched or elliptical corrugated metal pipe and the necessary fittings.

2. **MATERIALS**

Pipe and fittings shall conform to the requirements of AASHTO M 36 with corrugations in accordance with AASHTO M 218.

3. **LAYING AND BEDDING THE PIPE**

Unless otherwise specified, the pipe shall be installed in accordance with the manufacturer's recommendations. The pipe shall be laid with the outside laps of circumferential joints pointing upstream and with longitudinal laps at the sides at about the vertical mid-height of the pipe. Field welding of corrugated galvanized iron or steel pipe will not be permitted. Unless otherwise specified, the pipe section shall be joined with standard coupling bands. The pipe shall be firmly and uniformly bedded throughout its entire length to the depth and in the manner specified on the drawings.

Perforated pipe shall be laid with the perforations down and oriented symmetrically about a vertical center line. Perforations shall be clear of any obstructions at the time the pipe is laid.

The pipe shall be loaded sufficiently during backfilling around the sides to prevent its being lifted from the bedding.

4. **STRUTTING**

When required, struts or horizontal ties shall be installed in the manner specified on the drawings. Struts and ties shall remain in place until the backfill has been placed at a height of 5 feet above the top of the pipe, or has been completed if the finished height is less than 5 feet above the top of the pipe, at which time they shall be removed by the Contractor.

5. **HANDLING THE PIPE**

The Contractor shall furnish such equipment as is necessary to place the pipe without damaging the pipe or coatings. The pipe shall be transported and handled in such a manner as to prevent bruising, scaling or breaking of the spelter coating or bituminous coating.

6. **REPAIR OF DAMAGED COATINGS**

Any damage to the zinc coating shall be repaired by thoroughly wire brushing the damaged area, removing all loose and cracked coating, removing all dirt and greasy material with solvent, and painting with two coats of zinc dust-zinc oxide primer conforming to the requirements of Federal Specification TT-P- 641, Type III. If the coating is damaged in any individual area larger than 12 square inches, or if more than 0.2 percent of a total surface area of a length of pipe is damaged, the length will be rejected.

Breaks or scuffs in bituminous coatings that are less than 36 square inches in area shall be repaired by the application of two coats of hot asphaltic paint or a coating of cold-applied bituminous mastic. The repair coating shall be at least 0.05 inches thick after hardening and shall bond securely and permanently to the pipe. The material shall meet the physical requirements for bituminous coatings in accordance with AASHTO M-90. Whenever individual breaks exceed 36 square inches in area or when the total area of breaks exceeds 0.5 percent of the total surface area of the pipe, the pipe will be rejected.

Bituminous coating damaged by welding of coated pipe or pipe fittings shall be repaired as specified in this section for breaks and scuffs in bituminous coatings.

7. **MEASUREMENT AND PAYMENT**

(Method 1) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined to the nearest 0.1 foot by measurement of the laid length of pipe along the centerline of the pipe. Payment for each type, class, size and gage of pipe will be made at the contract unit price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing, transporting and installing the pipe and fittings and all other items necessary and incidental to the completion of the work.

(Method 2) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined as the sum of the nominal laying lengths of the pipe sections and fittings used. Payment for each type, class, size and gage of pipe will be made at the contract unit price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing, transporting and installing the pipe and fittings and all other items necessary and incidental to the completion of the work.

(Method 3) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined to the nearest 0.1 foot by measurement of the laid length of pipe along the centerline of the pipe. Payment for each type, class, size and gage of pipe will be made at the contract unit price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing,

transporting and installing the pipe and fittings and all other items necessary and incidental to the completion of the work except items designated as "special fittings." Payment for special fittings will be made at the contract lump sum price for special fittings (CMP).

(Method 4) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined as the sum of the nominal laying lengths of the pipe sections and fitting used. Payment for each type, class, size and gage of pipe will be made at the contract unit price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing, transporting and installing the pipe and fittings and all other items necessary and incidental to the completion of the work except items designated as "special fittings." Payment for special fittings will be made at the contract lump sum price for special fittings (CMP).

(Method 5) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined to the nearest 0.1 foot by measurement of the laid length of pipe along the centerline of the pipe. Payment for each type, class, size and gage of pipe will be made at the contract unit price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing, transporting and installing the pipe, including the necessary fittings and all other items necessary and incidental to the completion of the work except the special fittings and appurtenances listed separately in the bid schedule. Payment for each special fitting and appurtenance will be made at the contract unit price for that type and size of fitting or appurtenance.

(Method 6) For items of work for which specific unit prices are established in the contract, the quantity of each type, class, size and gage of pipe will be determined as the sum of the nominal laying lengths of the pipe sections used. Payment for each type, class, size and gage of pipe will be made at the contract price for that type, class, size and gage of pipe. Such payment will constitute full compensation for furnishing, transporting and installing the pipe, including the necessary fittings and all other items necessary and incidental to the completion of the work except for the special fittings and appurtenances listed separately in the bid schedule. Payment for each special fitting and appurtenance will be made at the contract unit price for that type and size of fitting or appurtenance.

(Use with All Methods) Compensation for any item of work described in the contract but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and the items to which they are made subsidiary are identified in Section 8 of this specification.

8. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

Items of work to be performed in conformance with this specification and the construction details include:

- a. Bid Item 14, 18-inch CSP Culvert (Polymeric Coated) with M.E.S.
 1. This item shall consist of furnishing and installing the corrugated metal pipe culverts as shown on the drawings, or as directed by the Engineer, including connecting bands, metal end sections, excavation, bedding and backfill.
 2. The CSP shall have a minimum gage of 16. All metal pipe shall be polymeric coated in accordance with AASHTO Designation M-246-1. The coating shall be a minimum of 0.010 inches on the interior and 0.010 inches on the exterior.
 3. All culverts will be backfilled with 2-inch minus granular material approved by the Engineer. The backfill material shall be placed and compacted in 8-inch lifts.
 4. Metal end sections will be installed on the 18-inch CSP. Sections will not be paid for separately but will be subsidiary to the 18-inch CSP Bid Item.
 5. Backfill shall be compacted to at least 95% AASHTO Designation T-99, Method D. Moisture content shall be within 2% of the optimum moisture.
 6. Measurement and payment shall be by Method 2. Such payment will constitute full compensation for furnishing and installing the CSP culverts and metal end sections and all other items necessary and incidental to completion of the work.

CONSTRUCTION SPECIFICATION

93. PAVEMENT MARKING PAINT

1. **SCOPE**

The work shall consist of furnishing and applying ready mixed traffic paint to asphaltic or concrete pavement.

2. **MATERIALS**

Furnish VOC Compliant Solvent Based or Acrylic Water Based Pavement marking paint meeting Federal Specification TTP-115 F for Low Volatile Organic Compounds (VOC) of 1.25 lbs/gal.

Apply to asphaltic or concrete pavement as edge lines, center lines, broken lines, guide lines, symbols and other related markings.

Remove pavement markings.

REFERENCES

1. AASHTO M247: Glass Beads Used in Traffic Paint.
2. ASTM D 562: Consistency of Paints Measuring Krebs Unit (KU) Viscosity Using the Stormer-Type Viscometer.
3. ASTM D 711: No-Pick-Up Time of Traffic Paint.
4. ASTM D 2205: Selection of Tests for Traffic Paints.
5. ASTM D 2743: Uniformity of Traffic Paint Vehicle Solids by Spectroscopy and Gas Chromatography.
6. ASTM D 3723: Pigment Content of Water-Emulsion Paints.
7. ASTM D 3960: Determining Volatile Organic Compound (VOC) Content of Paints and Related Coatings.
8. ASTM D 4451: Pigment Content of Paints
9. ASTM D 5381: S-Ray Fluorescence (XRF) Spectroscopy of Pigments and and Extenders.

10. Federal Standards 595B, 37875, 33538, and 11105.

ACCEPTANCE

1. Repaint any line or symbol failing to meet bead adherence and dimensional requirements.
2. Repaint any line or symbol failing to meet the minimum application requirements for paint or beads. (Road Only)

PAINT

1. Choose an approved pavement marking paint UDOT’s “Accepted Products Listing”. Follow Federal Standards 595B, 37875, 33538, and 11105. Meet the following requirements for VOC Compliant Solvent Based Paint or Acrylic Water Based Paint:

CIELAB (L*a*b*) D65/10°		
White	Yellow	Red
L* 91.9 to 95.6	L* 70.0 to 72.7	L* 31.4 to 33.4
a* -1.8 to -2.1	a* 22.5 to 24.8	a* 51.6 to 52.6
b* 3.8 to 2.2	b* 89.7 to 73.9	b* 34.1 to 35.1

- a. No-track time: Not more than 5 minutes when tested according to ASTM D 711.
- b. Volatile Organic Compounds Content: Less than 1.25 lbs/gal ASTM D 3960.
- c. Free of lead, chromium, or other related heavy metals ASTM D 5381.
- d. Pigment: Percent by weight: Acrylic Water Based minimum of 62.0 ± 2.0 VOC Compliant Solvent minimum of 52.0. ASTM D 3723.
- e. Total Solids: Percent by weight: Acrylic Water Based minimum of 77.0 VOC Compliant Solvent minimum of 70.0 ASTM D 2205.
- f. Acrylic water based paint must contain a minimum of 40 percent, by weight, 100 percent acrylic cross-linkable emulsion as determined by infrared analysis and other chemical analysis available to UDOT. ASTM D 2205 and UDOT Manual of Instruction Section 996.
- g. VOC compliant solvent based paint must contain 37.5 percent, by weight, copolymer alkyd-resin ASTM D 2205.

- h. ASTM D 562, ASTM D 2743, ASTM D 4451 and ASTM D 5381: Tests used to verify paint samples meet “Accepted Products Listing.”

GLASS SPHERE (BEADS) USED IN PAVEMENT MARKING PAINT

- 1. Specific Properties:
 - a. Meet AASHTO M 247.
 - b. Meet type II, uniform gradation.

3. **PREPARATION**

- 1. Line Control.
 - a. Establish control points as required.
 - b. Maintain the line within 0 inches of the established control points and mark the roadway and parking stalls.
 - 1. Remove paint that is not placed within tolerance of the established control points and replace at no expense to the Owner.
- 2. Remove dirt, loose aggregate and other foreign material and follow manufacturer’s recommendations for surface preparation.

4. **APPLICATION**

- 1. Pavement Marking Paint: Apply at the following rates:
 - a. 4 inch Solid Line: From 270 to 350 ft/gal
 - b. 4 inch Broken Line: From 1080 to 1400 ft/gal
 - c. 8 inch Solid Line: From 135 to 175 ft/gal
- 2. Replace pavement markings that are less than 14 wet mils in thickness.
- 3. No payment for pavement markings placed in excess of 18 wet mils in thickness.
- 4. Painted Legends and Symbols 1 gallon per 100 square feet.
- 5. Glass Sphere (Beads): Apply a minimum of 8 lbs/gal of paint, the full length and width of line and pavement markings.
- 6. Begin striping operations no later than 24 hours after ordered by the Engineer.
- 7. At time of application apply lines and pavement markings only when the air and pavement temperature are:
 - a. 40 degrees F and rising for VOC Compliant Solvent Based Paint.
 - b. 50 degrees F and rising for Acrylic Water Based Paint.

8. Comply with Traffic Control Drawing TC-16

5. **CONTRACTOR QUALITY CONTROL**

1. Application Rate: Verify that the paint and beads are being applied within specified tolerances prior to striping.

6. **ITEMS OF WORK AND CONSTRUCTION DETAILS**

Items of work to be performed in conformance with this specification and the construction details are:

a. **Bid Item 15, Pavement Marking Paint**

1. This item shall consist of the striping as required for performing the work under this contract including all labor, materials, and equipment necessary.
2. Line Control
 - Establish control points for parking stalls as shown on the drawings.
 - Maintain the line within 1 inch of the established control points and mark the parking lot as needed.
 - Paint handicap symbols as shown on the drawings.
 - Glass sphere (beads) will be required.
3. Broom or Sweep the pavement surface and remove dirt, loose stones and other foreign material.
4. Equipment

Equipment manufactured specifically for applying paint.
Use only workmen experienced in operating the equipment.
5. Restrictions
 - The Contractor shall begin striping operations no later than 24 hours after written order by the Engineer.

- Apply traffic striping only when the air and pavement temperature are 40°F. or higher.

6. Application Rates

Paint - apply at the following rates:

	<u>Linear Feet/Gallon</u>
4" Solid Stripe	From 190 to 240
4" Dashed Stripe	From 760 to 960
8" Solid Stripe	From 95 to 120

Beads

- A minimum of 6 pounds/gallon of paint (**Not Required**)
- Apply beads the full length of the line (**Not Required**)

7. **MEASUREMENT**

Measurement shall be by Lump Sum.

8. **PAYMENT**

The accepted quantities will be paid for at the contract unit price. Such payment will constitute full compensation for all labor, materials, equipment, transportation, tools, and all other items necessary and incidental to the completion of this item.