



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

Kim Hood
Executive Director

Division of Facilities Construction and Management

David G. Buxton
Director

ADDENDUM

Date: 17 February 2010

To: Contractors

From: Brent Lloyd, DFCM – Project Manager

Reference: Utah National Guard, Veteran’s Memorial Cemetery Paving
Improvements
DFCM Project No. 09111490

Subject: **Addendum No. 1**

Pages	Cover Page	1 page
	<u>Addendum</u>	<u>1 pages</u>
	Total	2 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

1.1 SCHEDULE CHANGES – No Schedule changes

1.2 GENERAL – See attached “Addendum No. 01”

Addenda No. 1
Veterans Memorial Cemetery Pavement Rehabilitation
DFCM Project No. 09111490
February 15, 2010

Item	Description
1	The project shall be completed by Thursday, May 13, 2010.
2	Where the new roll gutter (24") is to replace existing concrete mow strip (+/- 18") the roll gutter expanded width shall be extended to the sod or landscaped side.
3	The widened roadway shall have a 2% grade draining towards the sod. The Contractor shall remove the existing sod where the pavement is to be widened and dispose of at a location on-site, and may reuse the existing topsoil, native material to reshape and/or regrade the replaced sod at the new edge of asphalt.
4	The Contractor shall provide forming on both sides of the new concrete roll gutter. The Contractor shall saw cut the existing asphalt along the interior edge of the new concrete roll gutter and shall remove and replace (patch) the asphalt according to detail A sheet C-501, (leaving a 2" of exposed concrete at the lip for the 2" Asphalt overlay) to provide forms for the concrete. The contractor shall replace and restore the sod and irrigation system after removing the forms on the landscaped side of the new concrete roll gutter. The cost of the saw cut, asphalt patch and landscaped and irrigation restoration shall be included in the unit price for item No. 6, Furnish and Install Concrete Roll Gutter.
5	The Contractor shall tie the new concrete roll gutter into two (2) existing drains along the west side of the existing roadway.
6	Alternate Bid Item No. 6, Furnish and Install 12" Gravel, shall be changed to Furnish and Install 2" of APWA Sewer Rock over 6" of compacted untreated base course. The quantity shall remain the same. Those notes on the plan referencing the 12" of Gravel shall be replaced with 2" of APWA Sewer Rock over 6" of compacted untreated base course.
7	The Contractor shall work with the Veteran's Cemetery Administration to accommodate all funerals that may be scheduled during work hours.