



STATE OF UTAH - DEPARTMENT OF ADMINISTRATIVE SERVICES

**Division of Facilities Construction and Management**

**DFCM**

**MULTI-STEP BIDDING PROCESS  
FOR  
GENERAL CONTRACTORS**

**Single Project---Short-Listing**

**Request for Submittals**

**February 17, 2011**

**STEWART STADIUM TRACK RESURFACING**

**WEBER STATE UNIVERSITY**

**OGDEN, UTAH**

DFCM Project Number: 10282810

MHTN Architects  
420 East South Temple  
SLC Utah 84111

# TABLE OF CONTENTS

	<b>Page #</b>
Title Sheet	1
Table of Contents	2
Notice to Contractors	3
Description of Work	4
Multi-Step Bidding Process	5
Multi-Step Project Schedule	12
Bid Form	13
Bid Bond	15
Instructions and Subcontractors List Form	16
Contractor's Agreement	19
Performance Bond	24
Payment Bond	25

Current copies of the following documents are hereby made part of these contract documents by reference. These documents are available on the DFCM web site at <http://dfcm.utah.gov/StdDocs/index.html> "Standard Documents" – "Reference Documents I" – "Item 7. Supplemental General Conditions" or are available upon request from DFCM:

DFCM Supplemental General Conditions dated July 1, 2010 \*  
DFCM Supplemental General Conditions revised May 11, 2010  
DFCM Supplemental General Conditions dated July 1, 2009  
DFCM Supplemental General Conditions dated July 15, 2008  
DFCM General Conditions dated May 25, 2005

**\* NOTE: THE NEW SUPPLEMENTAL GENERAL CONDITIONS EFFECTIVE JULY 1, 2010 ADDRESSING DRUG AND ALCOHOL TESTING ARE REFERENCED AT THE LINK ABOVE.**

The Agreement and General Conditions dated May 25, 2005 have been updated from versions that were formally adopted and in use prior to this date. The changes made to the General Conditions are identified in a document entitled Revisions to General Conditions that is available on DFCM's web site at <http://dfcm.utah.gov>

# NOTICE TO CONTRACTORS

The State of Utah - Division of Facilities Construction and Management (DFCM) is requesting submissions for the following project:

**Project Name:** Weber State University Stewart Stadium Track Resurfacing  
**Project No.** 10282810  
**Project Description:** Demolition of existing track surface and interior track curb with drain.  
There will be some asphalt repair on the edge of the track.  
**Cost Estimate:** \$600,000.00

DFCM is entering into a Multi-Step Bidding Process for Construction services. A short-listing of contractors will be based on the selection criteria outlined in the bidding documents contained herein. Short-listed contractors will be invited to submit bids on the project described above. **The only contractors allowed to bid on this project will be contractors short-listed by the selection committee.**

All contractors responding to this procurement must comply with and require all of their subcontractors to comply with the license laws as required by the State of Utah.

The bidding documents including plans and specification, short-listing requirements and schedule will be available at **4:00 PM on February 17, 2011** on the DFCM web page at <http://dfcm.utah.gov> and from DFCM, 4110 State Office Building, Salt Lake City, Utah 84114, telephone 801-538-3018. For questions regarding this solicitation, please contact **Tim K Parkinson** DFCM, at 801-450-2478. No others are to be contacted regarding this solicitation.

A **mandatory** pre-submittal meeting to discuss the multi-step bidding process will be held at **10:00 AM on February 24, 2011** at Weber State University Facilities Management Office, Ogden Utah.

When bidding on this project, short-listed contractors will be required to submit a Bid Bond in the amount of five percent (5%) of the bid amount, made payable to the Division of Facilities Construction and Management on DFCM's Bid Bond Form. A Bid Bond must accompany each bid.

The Division of Facilities Construction & Management reserves the right to reject any or all submittals/bids or to waive any formality or technicality in any submittal/bid in the interest of the State.

DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT  
JOANNA REESE, CONTRACT COORDINATOR  
4110 State Office Bldg., Salt Lake City, Utah 84114

## DESCRIPTION OF WORK

The only contractors allowed to bid on this project will be contractors short-listed by the selection committee.

**Project Description:** This project consists of the demolition of existing track surface and interior track curb with drain will be included as part of the new construction bid document. Detail a new interior track drain which will tie into the new synthetic football field drainage system. This may require some asphalt repairs on the edge of the track.

Individual contractors or alliances between two or more contractors are allowed in this process to form a team. However, one contractor or firm MUST be declared as the lead firm representing the team. If the team is short-listed through this multi-step process, the state will only enter into contracts with the lead contractor or firm. The lead contractor or firm must be licensed by the State of Utah and comply with and require all of its subcontractors to comply with the license laws as required by the State of Utah.

# MULTI-STEP BIDDING PROCESS

## SHORT-LISTING OF GENERAL CONTRACTORS

The short-listing of contractors will be based on the selection criteria outlined in this document.

### 1. Multi-Step Bidding Documents

The Multi-Step bidding documents consist of all of the information contained in this solicitation and all documents listed in the Table of Contents. All said documents are incorporated in this document by reference.

### 2. Availability of Documents

Bidding documents are available free of charge at the locations stated on the Schedule. The bidding documents are also available at DFCM's internet web site at <http://dfcm.utah.gov>.

### 3. Drawings and Specifications and Interpretations

Drawings, specifications and other contract documents may be obtained as stated in the Notice to Contractors. If any firm is in doubt as to the meaning or interpretation of any part of the drawings, specifications, scope of work or contract documents, they shall submit, in writing, a request for interpretation to the authorized DFCM representative by the deadline identified in the schedule. Answers to questions and interpretations will be made via addenda issued by DFCM. Neither DFCM nor the designer shall be responsible for incorrect information obtained by contractors from sources other than the official drawings/specifications and addenda issued by DFCM.

### 4. Contact Information

Except as authorized by the DFCM Representative or as otherwise stated in the bidding documents or the pre-submittal meeting, communication during the multi-step bidding process shall be directed to the specified DFCM's Representative. In order to maintain the fair and equitable treatment of everyone, contractors shall not unduly contact or offer gifts or gratuities to owners, users or selection committee members in an effort to influence the selection process or in a manner that gives the appearance of influencing the selection process. This prohibition applies before the bidding documents are issued as the project is developed, and extends through the award of a contract. Failure to comply with this requirement may result in a disqualification from the multi-step bidding process. Contractors should be aware that selection committee members will be required to certify that they have not been contacted by any of the contractors in an attempt to influence the selection process.

### 5. Requests for Information

All requests for information shall be in writing and directed to:

**Project Manager Tim K Parkinson**

Division of Facilities Construction and Management

4110 State Office Building

Salt Lake City, Utah 84114

**E-mail: [tparkins@utah.gov](mailto:tparkins@utah.gov)**

**Phone: 801-450-2478**

**Facsimile: 801-538-3267**

6. **Schedule**

The Schedule lists the important events, dates, times and locations of meetings and submittals that must be met by the contractor.

7. **Pre-Submittal Meeting**

A **mandatory** pre-submittal meeting will be held on the date and time and at the location listed on the Schedule. During the meeting, questions will be answered about the multi-step bidding process. Questions about the project, plans and specifications will also be addressed. Attendance at this meeting is mandatory for General Contractors.

8. **Submittal Due Dates and Times**

All required submittals must be delivered to, and received by, the Division of Facilities Construction and Management by the time deadline established in the Schedule. Submittals received after the specified time deadline will not be accepted. Please allow adequate time for delivery. If using a courier service, the contractor is responsible for ensuring that delivery will be made directly to the required location prior to the deadline.

9. **Last Day to Submit Questions**

Questions must be submitted in writing to the DFCM project manager by the deadline listed on the Schedule.

10. **Addendum**

All clarifications will be in writing and issued as addenda to the RFS. Addenda will be posted on DFCM's web site at <http://dfcm.utah.gov>. **Contractors are responsible for obtaining information contained in the addenda from the web site. Any addenda issued prior to the submittal deadline shall become part of the multi-step bidding process and any information required must be included in the contractor's submittal.** Addenda issued prior to the submittal deadline shall become part of the bidding process and must be acknowledged on the bid form. Failure to acknowledge addenda may result in disqualification from bidding. DFCM shall not be responsible for incorrect information obtained by contractors from sources other than official addenda issued by DFCM.

11. **Bid Bond Requirements**

A bid bond properly signed by a qualified surety, as indicated on the DFCM Bid Bond form provided along with this Instruction to Bidders, in the amount of 5% of the bid, shall accompany the bid submission to DFCM. **THIS BID BOND MUST BE ON THE DFCM BID BOND FORM PROVIDED WITH THIS INSTRUCTION TO BIDDERS IN ORDER TO BE CONSIDERED AN ACCEPTABLE BID** unless only one bid is received by DFCM, or the failure to comply with the bid bond requirements is determined by the Director of DFCM to be nonsubstantial based on the following:

- (a) the bid bond is submitted on a form other than DFCM's required Bid Bond form and the bid bond meets all other requirements including being issued by a surety firm authorized to do business in the State of Utah and be listed in the U.S. Department of the Treasury Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies for an amount not less than the amount of the bond to be issued. A co-surety may be utilized to satisfy this requirement; and

- (b) the contractor provides a bid bond properly signed by a qualified surety and on the required DFCM Bid Bond form by the close of business of the next succeeding business day after the DFCM notifies the bidder of the defective bid bond.

**12. Performance and References**

DFCM will rate each firm's performance on every project worked on (rating scale: 1 = low; 5 = high). The rating may include comments from agencies. The firm will have an opportunity to review and comment on their ratings. Ratings on DFCM projects over the previous five years will be provided to the selection committee for their consideration in evaluating and scoring the past performance of each firm. If a firm has not completed at least three DFCM projects in the last five years, they shall provide by the time indicated on the Schedule, a list of references on additional projects for a total of five projects. References should include: (a) name and address of the project; (b) name and phone number of the person able to answer questions about the project; (c) date of when the work was completed; (d) the cost of the project and the type of project (school, office, warehouse, etc).

**13. Statement of Qualifications**

The Contractor (firm) shall provide five copies of a statement of qualifications by the time indicated on the Schedule. The statement should describe: (a) the financial viability of your firm; (b) the experience, skill level and qualifications of your firm - identify the specific project manager and site superintendent that will be assigned to this project; (c) provide examples of similar projects completed by your firm and the specific project manager and site superintendent that will be assigned to this project; (d) describe your firm's areas of expertise and other special qualifications as they pertain to this project; (e) document your firm's track record of completing projects on time and within budget; (f) explain your firm's reputation and commitment to high-quality workmanship; and (g) document your firm's ability to comply with the bonding requirements outlined earlier in this document. The statement of qualifications should be concise (**limit three pages**) yet contain sufficient information for evaluation by the selection committee. Note: If multiple firms combine to form a team, only the lead contractor or firm will be allowed to bid on projects. In addition, if any member of the team (contractor or firm) withdraws from the team, the entire team is disqualified and will not be allowed to bid.

**14. Termination or Debarment Certification**

Each firm must submit a certification that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from soliciting work by any governmental department or agency. The firm must also certify that neither the firm nor its principals have been terminated during the performance of a contract or withdrew from a contract to avoid termination. If the firm cannot certify to these statements, the firm shall submit a written explanation. Firms are to submit the certifications with their Statement of Qualifications.

**15. Project Management Plan**

Each Contractor (firm) shall provide five copies of a document describing their management plan by the time indicated on the Schedule. The document should include: (a) the process used for selecting and managing subcontractors; (b) a description of how the your firm is organized - pertaining to this project, document who will be in charge with decision making authority; (c) a project schedule detailing your firm's plan to ensure that the project will be completed on time (include timeline for ordering long lead materials and equipment); (d) a description of the process (action plan) your firm will take to bring the project back on schedule if it falls behind; (e) the procedures your firm has in place to minimize change

orders; (f) the methodology used to ensure the accuracy of your bid; (g) your firm's approach to site security and project safety; (h) your firm's understanding of DFCM's construction general conditions and contract requirements; and (i) any other information that will assist the selection committee in evaluating your firm's approach to project management.

Include an organization chart of key personnel and a description of their duties. The management plan document should be concise (**limit three pages**) yet contain sufficient information for evaluation by the selection committee. The organization chart is a separate document and is not counted as one of the three pages.

**16. Selection Committee**

The selection committee will evaluate and score each firm/team. Committee members may include individuals from DFCM, User Agency/Institution, and a representative from the design or construction disciplines.

**17. Interviews.**

If interviews are required, firms will be notified of the date and time of their interview. Otherwise, the selection committee reserves the right to short-list firms/teams based on their submitted past performance ratings/references, statement of qualifications and project management plan.

If necessary, interviews will be conducted with all responsive and responsible contractors. Firms that are late or do not appear for the interview may be disqualified by the committee. The evaluation will be made using the selection criteria contained in this document. Information provided by the past performance/references, statement of qualifications, project management plan and the interview will be evaluated using the selection criteria as the basis for the selection. The purpose of the interview is to allow contractors an opportunity to present their qualifications, discuss past performance/references and describe their project management plan. It will also provide an opportunity for the selection committee to ask questions about these items. Firms may elect to have management personnel, project managers and superintendents in attendance. Attendance of subcontractors is at the discretion of the contractor. The method of presentation is at the discretion of the contractor.

**18. Selection Criteria**

The following criteria and weighting will be used in evaluating each firm/team. The selection committee will consider all criteria in performing a comprehensive evaluation of each firm/team. Each firm/team will be scored by each selection committee member in the categories listed below.

- A. Performance Rating/References.** The committee will receive a past performance rating and/or reference score for each firm/team. DFCM will compute the score for each firm/team based upon the information outlined earlier in this document. **Possible Points: 35**
- B. Statement of Qualifications.** The committee will evaluate and score each firm's/team's qualifications in accordance with the information outlined earlier in this document as well as additional information about the firm's/team's qualifications presented during the interview. **Possible Points: 35**

- C. **Project Management Plan.** The committee will evaluate and score each firm's/team's project management approach in accordance with the information outlined earlier in this document as well as additional information about the firm's/team's project management approach presented during the interview. **Possible Points: 30**

**TOTAL POINTS = 100 POINTS**

**19. Short-Listing**

DFCM will **short-list all firms** receiving a score of 85 points or above from the selection committee. No firms receiving fewer than 85 points will be short-listed. Only short-listed firms will be invited to bid on this project. During the bidding process, the final contractor selection will be based on the lowest responsive and responsible bidder.

**20. Product Approvals**

Where reference is made to one or more proprietary products in the contract documents, but restrictive descriptive materials of one or more manufacturer(s) is referred to in the contract documents, the products of other manufacturers will be accepted, provided they equal or exceed the standards set forth in the drawings and specifications and are compatible with the intent and purpose of the design, subject to the written approval of the Designer. Such written approval must occur prior to the deadline established for the last scheduled addendum to be issued. The Designer's written approval will be included as part of the addendum issued by DFCM. If the descriptive material is not restrictive, the products of other manufacturers specified will be accepted without prior approval provided they are compatible with the intent and purpose of the design as determined by the Designer.

**21. Trade Secrets or Confidential Matters**

Any submitter may designate those portions of the submittals which contain trade secrets or other confidential matters that the Governmental Records and Access Management Act (GRAMA) would allow to be a protected record. Any disclosure of submittals or portions thereof shall be in accordance with GRAMA and State law.

**22. Financial Responsibility of Contractors, Subcontractors and Sub-subcontractors**

Contractors shall respond promptly to any inquiry in writing by DFCM to any concern of financial responsibility of the Contractor, Subcontractor or Sub-subcontractor. Failure to respond may result in the Contractor (firm) receiving a poor performance rating on this project.

**23. Licensure**

The Contractor shall comply with and require all of its Subcontractors to comply with the license laws as required by the State of Utah.

**24. Permits**

In concurrence with the requirements for permitting in the General Conditions, it is the responsibility of the Contractor to obtain the fugitive dust plan requirements from the Utah Division of Air Quality and the SWPPP requirements from the Utah Department of Environmental Quality and submit the

completed forms and pay any permit fee that may be required for this specific project. Failure to obtain the required permit may result in work stoppage and/or fines from the regulating authority that will be the sole responsibility of the Contractor. Any delay to the project as a result of any such failure to obtain the permit or noncompliance with the permit shall not be eligible for any extension in the Contract Time.

**25. Time is of the Essence**

Time is of the essence in regard to all the requirements of the contract documents.

**26. Bids**

Before submitting a bid, each bidder shall carefully examine the contract documents; shall visit the site of the work; shall fully inform themselves as to all existing conditions and limitations; and shall include in the bid the cost of all items required by the contract documents including those added via addenda. If the bidder observes that portions of the contract documents are at variance with applicable laws, building codes, rules, regulations or contain obvious erroneous or uncoordinated information, the bidder shall promptly notify the DFCM Project Manager. Changes necessary to correct these issues will be made via addenda issued by DFCM.

The bid, bearing original signatures, must be typed or handwritten in ink on the Bid Form provided in the procurement documents and submitted in a sealed envelope at the location specified by the Notice to Contractor's prior to the published deadline for the submission of bids.

Bid bond security, in the amount of five percent (5%) of the bid, made payable to the Division of Facilities Construction and Management, shall accompany bid. **THE BID BOND MUST BE ON THE BID BOND FORM PROVIDED IN THE PROCUREMENT DOCUMENTS IN ORDER TO BE CONSIDERED AN ACCEPTABLE BID.**

If the bid bond security is submitted on a form other than the Owner's required bid bond form, and the bid security meets all other legal requirements, the bidder will be allowed to provide an acceptable bid bond by the close of business on the next business day following notification by DFCM of submission of a defective bid bond security. **A cashier's check cannot be used as a substitute for a bid bond.**

**27. Listing of Subcontractors**

Listing of Subcontractors shall be as summarized in the "Instructions and Subcontractors List Form", included as part of the contract documents. The Subcontractors List shall be delivered to DFCM or faxed to DFCM at (801)538-3677 within 24 hours of the bid opening. Requirements for listing additional subcontractors will be listed in the contract documents.

DFCM retains the right to audit or take other steps necessary to confirm compliance with requirements for the listing and changing of subcontractors. Any contractor who is found to not be in compliance with these requirements may receive a poor performance rating on this project.

**28. Contract and Bond**

The Contractor's Agreement will be in the form provided in this document. The contract time will be as indicated in the bid. The successful bidder, simultaneously with the execution of the Contract Agreement, will be required to furnish a performance bond and a payment bond, both bearing original signatures, upon the forms provided in the procurement documents. The performance and payment bonds shall be for an amount equal to one hundred percent (100%) of the Contract Sum and secured from a company that meets the requirements specified in the requisite forms. Any bonding requirements for Subcontractors will be specified in the Supplementary General Conditions.

**29. Award of Contract**

The Contract will be awarded as soon as possible to the lowest, responsive and responsible bidder, based on the lowest combination of base bid and acceptable prioritized alternates, provided the bid is reasonable, is in the interests of DFCM to accept and after applying the Utah Preference Laws in U.C.A. Title 63, Chapter 56. DFCM reserves the right to waive any technicalities or formalities in any bid or in the bidding. Alternates will be accepted on a prioritized basis with Alternate 1 being highest priority, Alternate 2 having second priority, etc.

**30. Right to Reject Bids**

DFCM reserves the right to reject any or all Bids.

**31. Withdrawal of Bids**

Bids may be withdrawn on written request received from bidders within 24 hours after the bid opening if the contractor has made an error in preparing the bid.



**MULTI-STEP PROJECT SCHEDULE**

<b>PROJECT NAME:</b>		<b>Weber State University Stewart Stadium Track Resurfacing</b>		
<b>DFCM PROJECT NO. :</b>		<b>10282810</b>		
<b>Event</b>	<b>Day</b>	<b>Date</b>	<b>Time</b>	<b>Place</b>
Document Available, including Plans and Specifications	Thursday	February 17, 2011	4:00 PM	DFCM 4110 State Office Building SLC, UT and DFCM web site*
<b>Mandatory</b> Pre-Submittal Meeting	Thursday	February 24, 2011	10:00 AM	Weber State University Facilities Management Office Skyline Dr. Ogden Ut
Last Day to Submit Questions on Shortlisting (In Writing)	Wednesday	March 1, 2011	8:00 AM	Tim K Parkinson - DFCM E-mail <a href="mailto:tparkins@utah.gov">tparkins@utah.gov</a> Fax 801-538-3267
Addendum on Shortlisting	Tuesday	March 8, 2011	5:00 PM	DFCM web site*
List of References, Statement of Qualifications, Project Management Plan, and Termination/Debarment Certification Due	Thursday	March 10, 2011	12:00 NOON	DFCM 4110 State Office Building SLC, UT
Interviews by Selection Committee (if necessary)	Tuesday	March 15, 2011	10:00 AM	Weber State University Facilities Management Office
Short-List Announced	Wednesday	March 16, 2011	12:00 Noon	DFCM Website *
<b>Notice: Only Short-Listed Firms Will Be Allowed To Bid On This Project</b>				
Last Day to Submit Questions (In Writing)	Monday	March 21, 2011	8:00 AM	Tim K Parkinson - DFCM E-mail <a href="mailto:tparkins@utah.gov">tparkins@utah.gov</a> Fax 801-538-3267
Final Addendum (exception for bid delays)	Thursday	March 24, 2011	5:00 PM	DFCM web site*
Prime Contractors Turn in Bid and Bid Bond/Bid Opening in DFCM Conference Room	Tuesday	March 29, 2011	2:00 PM	DFCM 4110 State Office Building SLC, UT
Subcontractors List Due	Wednesday	March 30, 2011	2:00 PM	DFCM 4110 State Office Building SLC, UT Fax 801-537-9188
Project Completion Date	Monday	August 1, 2011	5:00 PM	Onsite

\* DFCM's web site address is <http://dfcm.utah.gov>



### BID FORM

NAME OF BIDDER \_\_\_\_\_ DATE \_\_\_\_\_

To the Division of Facilities Construction and Management  
4110 State Office Building  
Salt Lake City, Utah 84114

The undersigned, responsive to the "Notice to Contractors" and in accordance with the "Instructions to Bidders", in compliance with your invitation for bids for the Weber State University Stewart Stadium Track Resurfacing DFCM PROJECT NO. 10282810 and having examined the Contract Documents and the site of the proposed Work and being familiar with all of the conditions surrounding the construction of the proposed Project, including the availability of labor, hereby proposes to furnish all labor, materials and supplies as required for the Work in accordance with the Contract Documents as specified and within the time set forth and at the price stated below. This price is to cover all expenses incurred in performing the Work required under the Contract Documents of which this bid is a part:

I/We acknowledge receipt of the following Addenda: \_\_\_\_\_

For all work shown on the Drawings and described in the Specifications and Contract Documents, I/we agree to perform for the sum of:

\_\_\_\_\_ DOLLARS (\$ \_\_\_\_\_)  
(In case of discrepancy, written amount shall govern)

I/We guarantee that the Work will be Substantially Complete by August 1, 2011, should I/we be the successful bidder, and agree to pay liquidated damages in the amount of **\$250.00** per day for each day after expiration of the Contract Time as stated in Article 3 of the Contractor's Agreement.

This bid shall be good for 45 days after bid opening.

Enclosed is a 5% bid bond, as required, in the sum of \_\_\_\_\_

The undersigned Contractor's License Number for Utah is \_\_\_\_\_.

Upon receipt of notice of award of this bid, the undersigned agrees to execute the contract within ten (10) days, unless a shorter time is specified in the Contract Documents, and deliver acceptable Performance and Payment bonds in the prescribed form in the amount of 100% of the Contract Sum for faithful performance of the contract.

The Bid Bond attached, in the amount not less than five percent (5%) of the above bid sum, shall become the property of the Division of Facilities Construction and Management as liquidated damages for delay and additional expense caused thereby in the event that the contract is not executed and/or acceptable 100% Performance and Payment bonds are not delivered within the time set forth.

Type of Organization:

\_\_\_\_\_  
(Corporation, Partnership, Individual, etc.)

Any request and information related to Utah Preference Laws:

\_\_\_\_\_

Respectfully submitted,

\_\_\_\_\_  
Name of Bidder

ADDRESS:

\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
Authorized Signature





## INSTRUCTIONS AND SUBCONTRACTORS LIST FORM

The three low bidders, as well as all other bidders that desire to be considered, are required by law to submit to DFCM within 24 hours of bid opening a list of **ALL** first-tier subcontractors, including the subcontractor's name, bid amount and other information required by Building Board Rule and as stated in these Contract Documents, based on the following:

### **DOLLAR AMOUNTS FOR LISTING**

**PROJECTS UNDER \$500,000: ALL FIRST-TIER SUBS \$20,000 OR OVER MUST BE LISTED**  
**PROJECTS \$500,000 OR MORE: ALL FIRST-TIER SUBS \$35,000 OR OVER MUST BE LISTED**

- Any additional subcontractors identified in the bid documents shall also be listed.
- The DFCM Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law.
- List subcontractors for base bid as well as the impact on the list that the selection of any alternate may have.
- Bidder may not list more than one subcontractor to perform the same work.
- If there are no subcontractors for the job that are required to be reported by State law (either because there are no subcontractors that will be used on the project or because there are no first-tier subcontractors over the dollar amounts referred to above), then you do not need to submit a sublist. If you do not submit a sublist, it will be deemed to be a representation by you that there are no subcontractors on the job that are required to be reported under State law. At any time, DFCM reserves the right to inquire, for security purposes, as to the identification of the subcontractors at any tier that will be on the worksite.

### **LICENSURE:**

The subcontractor's name, the type of work, the subcontractor's bid amount, and the subcontractor's license number as issued by DOPL, if such license is required under Utah Law, shall be listed. Bidder shall certify that all subcontractors, required to be licensed, are licensed as required by State law. A subcontractor includes a trade contractor or specialty contractor and does not include suppliers who provide only materials, equipment, or supplies to a contractor or subcontractor.

### **'SPECIAL EXCEPTION':**

A bidder may list 'Special Exception' in place of a subcontractor when the bidder intends to obtain a subcontractor to perform the work at a later date because the bidder was unable to obtain a qualified or reasonable bid under the provisions of U.C.A. Section 63A-5-208(4). The bidder shall insert the term 'Special Exception' for that category of work, and shall provide documentation with the subcontractor list describing the bidder's efforts to obtain a bid of a qualified subcontractor at a reasonable cost and why the bidder was unable to obtain a qualified subcontractor bid. The Director must find that the bidder complied in good faith with State law requirements for any 'Special Exception' designation, in order for the bid to be considered. If awarded the contract, the Director shall supervise the bidder's efforts to obtain a qualified subcontractor bid. The amount of the awarded contract may not be adjusted to reflect the actual amount of the subcontractor's bid. Any listing of 'Special Exception' on the sublist form shall also include amount allocated for that work.

### **GROUND FOR DISQUALIFICATION:**

The Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law. Director may withhold awarding the contract to a particular bidder if one or more of the proposed subcontractors are considered by the Director to be unqualified to do the Work or for

INSTRUCTIONS AND SUBCONTRACTORS LIST FORM  
PAGE NO. 2

such other reason in the best interest of the State of Utah. Notwithstanding any other provision in these instructions, if there is a good faith error on the sublist form, at the sole discretion of the Director, the Director may provide notice to the contractor and the contractor shall have 24 hours to submit the correction to the Director. If such correction is submitted timely, then the sublist requirements shall be considered met.

**CHANGES OF SUBCONTRACTORS SPECIFICALLY IDENTIFIED ON SUBLIST FORM:**

Subsequent to twenty-four hours after the bid opening, the contractor may change its listed subcontractors only after receiving written permission from the Director based on complying with all of the following criteria.

- (1) The contractor has established in writing that the change is in the best interest of the State and that the contractor establishes an appropriate reason for the change, which may include, but not is not limited to, the following reasons: the original subcontractor has failed to perform, or is not qualified or capable of performing, and/or the subcontractor has requested in writing to be released.
- (2) The circumstances related to the request for the change do not indicate any bad faith in the original listing of the subcontractors.
- (3) Any requirement set forth by the Director to ensure that the process used to select a new subcontractor does not give rise to bid shopping.
- (4) Any increase in the cost of the subject subcontractor work is borne by the contractor.
- (5) Any decrease in the cost of the subject subcontractor work shall result in a deductive change order being issued for the contract for such decreased amount.
- (6) The Director will give substantial weight to whether the subcontractor has consented in writing to being removed unless the Contractor establishes that the subcontractor is not qualified for the work.

**EXAMPLE:**

Example of a list where there are only four subcontractors:

TYPE OF WORK	SUBCONTRACTOR, "SELF" OR "SPECIAL EXCEPTION"	SUBCONTRACTOR BID AMOUNT	CONTRACTOR LICENSE #
ELECTRICAL	ABCD Electric Inc.	\$350,000.00	123456789000
LANDSCAPING	"Self" *	\$300,000.00	123456789000
CONCRETE (ALTERNATE #1)	XYZ Concrete Inc	\$298,000.00	987654321000
MECHANICAL	"Special Exception" (attach documentation)	Fixed at: \$350,000.00	(TO BE PROVIDED AFTER OBTAINING SUBCONTRACTOR)

\* Bidders may list "self", but it is not required.

**PURSUANT TO STATE LAW - SUBCONTRACTOR BID AMOUNTS CONTAINED IN THIS SUBCONTRACTOR LIST SHALL NOT BE DISCLOSED UNTIL THE CONTRACT HAS BEEN AWARDED.**



SUBCONTRACTORS LIST
FAX TO 801-537-9188

PROJECT TITLE: \_\_\_\_\_

Caution: You must read and comply fully with instructions.

Table with 4 columns: TYPE OF WORK, SUBCONTRACTOR, 'SELF' OR 'SPECIAL EXCEPTION', SUBCONTRACTOR BID AMOUNT, CONT. LICENSE #. The table contains 15 empty rows for data entry.

We certify that:

- 1. This list includes all subcontractors as required by the instructions, including those related to the base bid as well as any alternates.
2. We have listed 'Self' or 'Special Exception' in accordance with the instructions.
3. All subcontractors are appropriately licensed as required by State law.

FIRM: \_\_\_\_\_

DATE: \_\_\_\_\_

SIGNED BY: \_\_\_\_\_

NOTICE: FAILURE TO SUBMIT THIS FORM, PROPERLY COMPLETED AND SIGNED, AS REQUIRED IN THESE CONTRACT DOCUMENTS, SHALL BE GROUNDS FOR OWNER'S REFUSAL TO ENTER INTO A WRITTEN CONTRACT WITH BIDDER. ACTION MAY BE TAKEN AGAINST BIDDERS BID BOND AS DEEMED APPROPRIATE BY OWNER. ATTACH A SECOND PAGE IF NECESSARY.

### CONTRACTOR'S AGREEMENT

FOR:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

THIS CONTRACTOR'S AGREEMENT, made and entered into this \_\_ day of \_\_\_\_\_, 2006, by and between the DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT, hereinafter referred to as "DFCM", and \_\_\_\_\_, incorporated in the State of Utah and authorized to do business in the State of Utah, hereinafter referred to as "Contractor", whose address is \_\_\_\_\_ Utah \_\_\_\_\_.

WITNESSETH: WHEREAS, DFCM intends to have \_\_\_\_\_ Work performed at \_\_\_\_\_

WHEREAS, Contractor agrees to perform the Work for the sum stated herein.

NOW, THEREFORE, DFCM and Contractor for the consideration provided in this Contractor's Agreement, agree as follows:

**ARTICLE 1. SCOPE OF WORK.** The Work to be performed shall be in accordance with the Contract Documents prepared by \_\_\_\_\_ and entitled "\_\_\_\_\_."

The DFCM General Conditions ("General Conditions") dated May 25, 2005 and all Supplemental General Conditions ("also referred to as General Conditions") on file at the office of DFCM and available on the DFCM website (<http://dfcm.utah.gov/StdDocs/index.html>), are hereby incorporated by reference as part of this Agreement and are included in the specifications for this Project. All terms used in this Contractor's Agreement shall be as defined in the Contract Documents, and in particular, the General Conditions.

The Contractor Agrees to furnish labor, materials and equipment to complete the Work as required in the Contract Documents which are hereby incorporated by reference. It is understood and agreed by the parties hereto that all Work shall be performed as required in the Contract Documents and shall be subject to inspection and approval of DFCM or its authorized representative. The relationship of the Contractor to the DFCM hereunder is that of an independent Contractor.

**ARTICLE 2. CONTRACT SUM.** The DFCM agrees to pay and the Contractor agrees to accept in full performance of this Contractor's Agreement, the sum of \_\_\_\_\_ **DOLLARS AND NO CENTS** (\$ \_\_\_\_\_), which is the base bid, and includes the cost of a 100%

CONTRACTOR'S AGREEMENT  
PAGE NO. 2

Performance Bond and a 100% Payment Bond as well as all insurance requirements of the Contractor. Said bonds have already been posted by the Contractor pursuant to State law. The required proof of insurance certificates have been delivered to DFCM in accordance with the General Conditions before the execution of this Contractor's Agreement.

**ARTICLE 3. TIME OF COMPLETION AND DELAY REMEDY.** The Work shall be Substantially Complete by \_\_\_\_\_ after the date of the Notice to Proceed. Contractor agrees to pay liquidated damages in the amount of \_\_\_\_\_ per day for each day after expiration of the Contract Time until the Contractor achieves Substantial Completion in accordance with the Contract Documents, if Contractor's delay makes the damages applicable. The provision for liquidated damages is: (a) to compensate the DFCM for delay only; (b) is provided for herein because actual damages can not be readily ascertained at the time of execution of this Contractor's Agreement; (c) is not a penalty; and (d) shall not prevent the DFCM from maintaining Claims for other non-delay damages, such as costs to complete or remedy defective Work.

No action shall be maintained by the Contractor, including its or Subcontractor or suppliers at any tier, against the DFCM or State of Utah for damages or other claims due to losses attributable to hindrances or delays from any cause whatsoever, including acts and omissions of the DFCM or its officers, employees or agents, except as expressly provided in the General Conditions. The Contractor may receive a written extension of time, signed by the DFCM, in which to complete the Work under this Contractor's Agreement in accordance with the General Conditions.

**ARTICLE 4. CONTRACT DOCUMENTS.** The Contract Documents consist of this Contractor's Agreement, the Conditions of the Contract (DFCM General Conditions, Supplementary and other Conditions), the Drawings, Specifications, Addenda and Modifications. The Contract Documents shall also include the bidding documents, including the Notice to Contractors, Instructions to Bidders/Proposers and the Bid/Proposal, to the extent not in conflict therewith and other documents and oral presentations that are documented as an attachment to the contract.

All such documents are hereby incorporated by reference herein. Any reference in this Contractor's Agreement to certain provisions of the Contract Documents shall in no way be construed as to lessen the importance or applicability of any other provisions of the Contract Documents.

**ARTICLE 5. PAYMENT.** The DFCM agrees to pay the Contractor from time to time as the Work progresses, but not more than once each month after the date of Notice to Proceed, and only upon Certificate of the A/E for Work performed during the preceding calendar month, ninety-five percent (95%) of the value of the labor performed and ninety-five percent (95%) of the value of materials furnished in place or on the site. The Contractor agrees to furnish to the DFCM invoices for materials purchased and on the site but not installed, for which the

Contractor requests payment and agrees to safeguard and protect such equipment or materials and is responsible for safekeeping thereof and if such be stolen, lost or destroyed, to replace same.

Such evidence of labor performed and materials furnished as the DFCM may reasonably require shall be supplied by the Contractor at the time of request for Certificate of Payment on account. Materials for which payment has been made cannot be removed from the job site without DFCM's written approval. Five percent (5%) of the earned amount shall be retained from each monthly payment. The retainage, including any additional retainage imposed and the release of any retainage, shall be in accordance with UCA 13-8-5 as amended. Contractor shall also comply with the requirements of UCA 13-8-5, including restrictions of retainage regarding subcontractors and the distribution of interest earned on the retention proceeds. The DFCM shall not be responsible for enforcing the Contractor's obligations under State law in fulfilling the retention law requirements with subcontractors at any tier.

**ARTICLE 6. INDEBTEDNESS.** Before final payment is made, the Contractor must submit evidence satisfactory to the DFCM that all payrolls, materials bills, subcontracts at any tier and outstanding indebtedness in connection with the Work have been properly paid. Final Payment will be made after receipt of said evidence, final acceptance of the Work by the DFCM as well as compliance with the applicable provisions of the General Conditions.

Contractor shall respond immediately to any inquiry in writing by DFCM as to any concern of financial responsibility and DFCM reserves the right to request any waivers, releases or bonds from Contractor in regard to any rights of Subcontractors (including suppliers) at any tier or any third parties prior to any payment by DFCM to Contractor.

**ARTICLE 7. ADDITIONAL WORK.** It is understood and agreed by the parties hereto that no money will be paid to the Contractor for additional labor or materials furnished unless a new contract in writing or a Modification hereof in accordance with the General Conditions and the Contract Documents for such additional labor or materials has been executed. The DFCM specifically reserves the right to modify or amend this Contractor's Agreement and the total sum due hereunder either by enlarging or restricting the scope of the Work.

**ARTICLE 8. INSPECTIONS.** The Work shall be inspected for acceptance in accordance with the General Conditions.

**ARTICLE 9. DISPUTES.** Any dispute, PRE or Claim between the parties shall be subject to the provisions of Article 7 of the General Conditions. DFCM reserves all rights to pursue its rights and remedies as provided in the General Conditions.

**ARTICLE 10. TERMINATION, SUSPENSION OR ABANDONMENT.** This Contractor's Agreement may be terminated, suspended or abandoned in accordance with the General Conditions.

**ARTICLE 11. DFCM'S RIGHT TO WITHHOLD CERTAIN AMOUNT AND MAKE USE THEREOF.** The DFCM may withhold from payment to the Contractor such amount as, in DFCM's judgment, may be necessary to pay just claims against the Contractor or Subcontractor at any tier for labor and services rendered and materials furnished in and about the Work. The DFCM may apply such withheld amounts for the payment of such claims in DFCM's discretion. In so doing, the DFCM shall be deemed the agent of Contractor and payment so made by the DFCM shall be considered as payment made under this Contractor's Agreement by the DFCM to the Contractor. DFCM shall not be liable to the Contractor for any such payment made in good faith. Such withholdings and payments may be made without prior approval of the Contractor and may be also be prior to any determination as a result of any dispute, PRE, Claim or litigation.

**ARTICLE 12. INDEMNIFICATION.** The Contractor shall comply with the indemnification provisions of the General Conditions.

**ARTICLE 13. SUCCESSORS AND ASSIGNMENT OF CONTRACT.** The DFCM and Contractor, respectively bind themselves, their partners, successors, assigns and legal representatives to the other party to this Agreement, and to partners, successors, assigns and legal representatives of such other party with respect to all covenants, provisions, rights and responsibilities of this Contractor's Agreement. The Contractor shall not assign this Contractor's Agreement without the prior written consent of the DFCM, nor shall the Contractor assign any moneys due or to become due as well as any rights under this Contractor's Agreement, without prior written consent of the DFCM.

**ARTICLE 14. RELATIONSHIP OF THE PARTIES.** The Contractor accepts the relationship of trust and confidence established by this Contractor's Agreement and covenants with the DFCM to cooperate with the DFCM and A/E and use the Contractor's best skill, efforts and judgment in furthering the interest of the DFCM; to furnish efficient business administration and supervision; to make best efforts to furnish at all times an adequate supply of workers and materials; and to perform the Work in the best and most expeditious and economic manner consistent with the interests of the DFCM.

**ARTICLE 15. AUTHORITY TO EXECUTE AND PERFORM AGREEMENT.** Contractor and DFCM each represent that the execution of this Contractor's Agreement and the performance thereunder is within their respective duly authorized powers.

**ARTICLE 16. ATTORNEY FEES AND COSTS.** Except as otherwise provided in the dispute resolution provisions of the General Conditions, the prevailing party shall be entitled to reasonable attorney fees and costs incurred in any action in the District Court and/or appellate body to enforce this Contractor's Agreement or recover damages or any other action as a result of a breach thereof.



**PERFORMANCE BOND**  
(Title 63, Chapter 56, U. C. A. 1953, as Amended)

That \_\_\_\_\_ hereinafter referred to as the "Principal" and \_\_\_\_\_, a corporation organized and existing under the laws of the State of \_\_\_\_\_, with its principal office in the City of \_\_\_\_\_ and authorized to transact business in this State and U. S. Department of the Treasury Listed (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); hereinafter referred to as the "Surety," are held and firmly bound unto the State of Utah, hereinafter referred to as the "Obligee," in the amount of \_\_\_\_\_ DOLLARS (\$ \_\_\_\_\_) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

**WHEREAS**, the Principal has entered into a certain written Contract with the Obligee, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, to construct \_\_\_\_\_ in the County of \_\_\_\_\_, State of Utah, Project No. \_\_\_\_\_, for the approximate sum of \_\_\_\_\_ Dollars (\$ \_\_\_\_\_), which Contract is hereby incorporated by reference herein.

**NOW, THEREFORE**, the condition of this obligation is such that if the said Principal shall faithfully perform the Contract in accordance with the Contract Documents including, but not limited to, the Plans, Specifications and conditions thereof, the one year performance warranty, and the terms of the Contract as said Contract may be subject to Modifications or changes, then this obligation shall be void; otherwise it shall remain in full force and effect.

No right of action shall accrue on this bond to or for the use of any person or corporation other than the state named herein or the heirs, executors, administrators or successors of the Owner.

The parties agree that the dispute provisions provided in the Contract Documents apply and shall constitute the sole dispute procedures of the parties.

**PROVIDED, HOWEVER**, that this Bond is executed pursuant to the Provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

**IN WITNESS WHEREOF**, the said Principal and Surety have signed and sealed this instrument this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

**WITNESS OR ATTESTATION:**

\_\_\_\_\_

**PRINCIPAL:**

\_\_\_\_\_

By: \_\_\_\_\_

(Seal)

Title: \_\_\_\_\_

**WITNESS OR ATTESTATION:**

\_\_\_\_\_

**SURETY:**

\_\_\_\_\_

By: \_\_\_\_\_  
Attorney-in-Fact

(Seal)

STATE OF \_\_\_\_\_ )  
 ) ss.  
COUNTY OF \_\_\_\_\_ )

On this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, personally appeared before me \_\_\_\_\_, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney in-fact of the above-named Surety Company and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.  
My commission expires: \_\_\_\_\_  
Resides at: \_\_\_\_\_

\_\_\_\_\_  
NOTARY PUBLIC

<b>Agency:</b> _____
<b>Agent:</b> _____
<b>Address:</b> _____
<b>Phone:</b> _____

Approved As To Form: May 25, 2005  
By Alan S. Bachman, Asst Attorney General

**PAYMENT BOND**

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

**KNOW ALL PERSONS BY THESE PRESENTS:**

That \_\_\_\_\_ hereinafter referred to as the "Principal," and \_\_\_\_\_, a corporation organized and existing under the laws of the State of \_\_\_\_\_ authorized to do business in this State and U. S. Department of the Treasury Listed (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); with its principal office in the City of \_\_\_\_\_, hereinafter referred to as the "Surety," are held and firmly bound unto the State of Utah hereinafter referred to as the "Obligee," in the amount of \_\_\_\_\_ Dollars (\$ \_\_\_\_\_) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

**WHEREAS**, the Principal has entered into a certain written Contract with the Obligee, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, to construct \_\_\_\_\_ in the County of \_\_\_\_\_, State of Utah, Project No. \_\_\_\_\_ for the approximate sum of \_\_\_\_\_ Dollars (\$ \_\_\_\_\_), which contract is hereby incorporated by reference herein.

**NOW, THEREFORE**, the condition of this obligation is such that if the said Principal shall pay all claimants supplying labor or materials to Principal or Principal's Subcontractors in compliance with the provisions of Title 63, Chapter 56, of Utah Code Annotated, 1953, as amended, and in the prosecution of the Work provided for in said Contract, then, this obligation shall be void; otherwise it shall remain in full force and effect.

That said Surety to this Bond, for value received, hereby stipulates and agrees that no changes, extensions of time, alterations or additions to the terms of the Contract or to the Work to be performed thereunder, or the specifications or drawings accompanying same shall in any way affect its obligation on this Bond, and does hereby waive notice of any such changes, extensions of time, alterations or additions to the terms of the Contract or to the Work or to the specifications or drawings and agrees that they shall become part of the Contract Documents.

**PROVIDED, HOWEVER**, that this Bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

**IN WITNESS WHEREOF**, the said Principal and Surety have signed and sealed this instrument this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

**WITNESS OR ATTESTATION:**

\_\_\_\_\_

(Seal)

**WITNESS OR ATTESTATION:**

\_\_\_\_\_

STATE OF \_\_\_\_\_ )  
 ) ss.  
COUNTY OF \_\_\_\_\_ )

**PRINCIPAL:**

\_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

**SURETY:**

\_\_\_\_\_

By: \_\_\_\_\_  
Attorney-in-Fact (Seal)

On this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, personally appeared before me \_\_\_\_\_, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney-in-fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.  
My commission expires: \_\_\_\_\_  
Resides at: \_\_\_\_\_

\_\_\_\_\_  
NOTARY PUBLIC

**Agency:** \_\_\_\_\_  
**Agent:** \_\_\_\_\_  
**Address:** \_\_\_\_\_  
**Phone:** \_\_\_\_\_

Approved As To Form: May 25, 2005  
By Alan S. Bachman, Asst Attorney General

# P R O J E C T M A N U A L

## WEBER STATE UNIVERSITY

## STEWART STADIUM TRACK REPLACEMENT

### CONSTRUCTION DOCUMENTS

MHTN PROJECT NO 2010576.00  
DFCM PROJECT NO 10282810

3 FEBRUARY 2011



vision made **real**

# CERTIFICATIONS PAGE

	LANDSCAPE ARCHITECT	
	CIVIL ENGINEER	

All professional seals (stamps) to be signed and dated; Architect Licensing Act Rules R156-3a, Utah Administrative Code, paragraph 601 and Professional Engineers Licensing Act Rules R156-22, Utah Administrative Code, paragraph 601.

# STEWART STADIUM TRACK RENOVATION

Table of Contents

3 FEBRUARY 2011

## CONSTRUCTION DOCUMENTS

### TECHNICAL SPECIFICATIONS

Division	Section Title	Pages
<b>DIVISION 1 - GENERAL REQUIREMENTS</b>		
011000	SUMMARY	2
012200	UNIT PRICES	2
012500	SUBSTITUTION PROCEDURES	2
	SUBSTITUTION REQUEST FORM (After the Bidding Phase)	2
012900	PAYMENT PROCEDURES	4
013100	PROJECT MANAGEMENT AND COORDINATION	5
013200	CONSTRUCTION PROGRESS DOCUMENTATION	4
013300	SUBMITTAL PROCEDURES	7
	LICENSE AND INDEMNIFICATION AGREEMENT	1
014000	QUALITY REQUIREMENTS	2
014200	REFERENCES	2
014533	STRUCTURAL TESTS AND SPECIAL INSPECTIONS	5
015000	TEMPORARY FACILITIES AND CONTROLS	5
016000	PRODUCT REQUIREMENTS	5
017000	EXECUTION REQUIREMENTS	4
	REQUEST FOR INTERPRETATION	1
017310	CUTTING AND PATCHING	4
017700	CLOSEOUT PROCEDURES	5
<b>DIVISION 31 - EARTHWORK</b>		
310700	GENERAL SITE CONSTRUCTION REQUIREMENTS	2
311000	SITE CLEARING	4
312000	EARTH MOVING	14
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>		
321216	ASPHALT PAVING	12
321313	CONCRETE PAVING	16
321373	CONCRETE PAVING JOINT SEALANTS	8
321823	POURED ATHLETIC TRACK SURFACE SYSTEMS	8
<b>APPENDIX</b>		
	GEOTECHNICAL REPORT	3

## SECTION 011000 - SUMMARY

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Identification: Project consists of removal of existing track surface , repair of asphaltic base layer and installation of new poured track surfacing. Installation of the track follows immediately behind installation of new turf on the stadium playing field
- B. Utility location drawings are provided as part of the Contract Documents, Contractor must verify locations prior to excavating to avoid damage to lines, conduit and piping that remains.
- C. Architect Identification: The Contract Documents dated January 28, 2011 were prepared for the Project by MHTN Architects, 420 East South Temple, Salt Lake City, Utah 84111

#### 1.3 CONSTRUCTION SCHEDULE – MANPOWER REQUIREMENTS

- A. Contractors shall provide adequate personnel and extend workdays and work weeks to comply with the schedule requirements of this project.
- B. Schedule shall be as follows:
  - 1. Notice to Proceed – April 1, 2011
  - 2. Start Construction Date April 7, 2011
  - 3. Final Completion August 1, 2011
  - 4. Related contract work of separate Phase Ends July 1, 2011

#### 1.4 USE OF PREMISES

- A. General: The Contractor shall have full use of the construction area for operations. The Contractor's use of premises is limited only by the continuing administrative operations in the adjacent facilities under the Grandstand..

#### 1.5 SPECIFICATION FORMATS AND CONVENTIONS

- A. Specification Format: The Specifications are organized into Divisions and Sections using the 16-division format and CSI/CSC's "MasterFormat" numbering system.
  - 1. Section Identification: The Specifications use section numbers and titles to help cross-referencing in the Contract Documents. Sections in the Project Manual are in numeric sequence; however, the sequence is incomplete. Consult the table of contents at the be-

gining of the Project Manual to determine numbers and names of sections in the Contract Documents.

- B. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
1. Abbreviated Language: Language used in the Specifications and other Contract Documents is abbreviated. Words and meanings shall be interpreted as appropriate. Words implied, but not stated, shall be inferred as the sense requires. Singular words shall be interpreted as plural, and plural words shall be interpreted as singular where applicable as the context of the Contract Documents indicates.
  2. Imperative mood and streamlined language are generally used in the Specifications. Requirements expressed in the imperative mood are to be performed by Contractor. Occasionally, the indicative or subjunctive mood may be used in the Section Text for clarity to describe responsibilities that must be fulfilled indirectly by Contractor or by others when so noted.
    - a. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not used)

END OF SECTION 011000

## SECTION 012200 - UNIT PRICES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for unit prices.
- B. Related Sections include the following:
  - 1. Division 1 Section "Contract Modification Procedures" for procedures for submitting and handling Change Orders.
  - 2. Division 1 Section "Quality Requirements" for general testing and inspecting requirements.

#### 1.3 DEFINITIONS

- A. Unit price is **an amount proposed by bidders, stated on the Bid Form, as** a price per unit of measurement for materials or services added to or deducted from the Contract Sum by appropriate modification, if estimated quantities of Work required by the Contract Documents are increased or decreased.

#### 1.4 PROCEDURES

- A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, overhead, and profit.
- B. Measurement and Payment: Refer to individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- D. List of Unit Prices: A list of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 LIST OF UNIT PRICES

1. Unit Price No. 1: Remove and replace 4 inch thick asphalt paving Price per Square yard
2. Unit Price No. 2: Remove and replace 8 inch thick compacted aggregate base course.  
Price per square yard.

END OF SECTION 012200

## SECTION 012500 - CONTRACT MODIFICATION PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements for handling and processing Contract modifications.

#### 1.3 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

#### 1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
  - 1. Proposal Requests issued by Architect are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
  - 2. Within **7 days** after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
    - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    - c. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change.
  - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.

2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
5. Comply with requirements in Division 1 Section "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.

C. Proposal Request Form: Use AIA Document G709 for Proposal Requests.

#### 1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on **AIA Document G701**.

#### 1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: **Architect** may issue a Construction Change Directive on AIA Document G714. Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

- B. Documentation: Maintain detailed records on a time and material basis of work required by the **Construction** Change Directive.

1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used).

END OF SECTION 012500

## SECTION 012900 - PAYMENT PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
  - 1. Division 1 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
  - 2. Division 1 Section "Construction Progress Documentation" for administrative requirements governing preparation and submittal of Contractor's Construction Schedule and Submittals Schedule.

#### 1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment. Schedule included in the RFP will serve as a Schedule of Values

#### 1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
  - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
    - a. Application for Payment forms with Continuation Sheets.
    - b. Submittals Schedule.
  - 2. Subschedules: Where the Work is separated into phases requiring separately phased payments, provide subschedules showing values correlated with each phase of payment.
  - 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate.
  - 4. Round amounts to nearest whole dollar; total shall equal the Contract Sum.

5. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
  - a. Differentiate between items stored on-site and items stored off-site. Include evidence of insurance or bonded warehousing if required.
6. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
7. Allowances (if required): Provide a separate line item in the Schedule of Values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
8. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
  - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.
9. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

#### 1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
  1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction Work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Forms: Use **AIA Document G702 and AIA Document G703 Continuation Sheets** as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
  1. Entries shall match data on the Schedule of Values and Contractor's Construction Schedule. Use updated schedules if revisions were made.
  2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.

- E. Transmittal: Submit 2 signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from every entity who is lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
1. Submit partial waivers on each item for amount requested, before deduction for retainage, on each item.
  2. When an application shows completion of an item, submit final or full waivers.
  3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
  4. Waiver Delays: Submit each Application for Payment with Contractor's waiver of mechanic's lien for construction period covered by the application.
    - a. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
  5. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- G. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
  2. Schedule of Values.
  3. Contractor's Construction Schedule (preliminary if not final).
  4. Products list.
  5. Schedule of unit prices (if any)
  6. Submittals Schedule (preliminary if not final).
  7. List of Contractor's staff assignments.
  8. Copies of building permits.
  9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
  10. Initial progress report.
  11. Report of preconstruction conference.
  12. Certificates of insurance and insurance policies if not provided to Owner at contract signing.
  13. Performance and payment bonds.
  14. Initial settlement survey and damage report if required.
- H. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.

- I. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
  1. Evidence of completion of Project closeout requirements.
  2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  3. Updated final statement, accounting for final changes to the Contract Sum.
  4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
  5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
  6. AIA Document G707, "Consent of Surety to Final Payment."
  7. Evidence that claims have been settled.
  8. Final, liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

## SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
  - 1. General project coordination procedures.
  - 2. Conservation.
  - 3. Coordination Drawings.
  - 4. Administrative and supervisory personnel.
  - 5. Project meetings.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
  - 1. Division 1 Section "Summary" for a description of the Work and responsibility for coordination activities not in this Section.
  - 2. Division 1 Section "Execution Requirements" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
  - 3. Division 1 Section "Closeout Procedures" for coordinating Contract closeout.

#### 1.3 COORDINATION

- A. Coordination: Contractor shall coordinate its construction operations with those of other contractors in separate phases where required, and entities to ensure efficient and orderly installation of each part of the Work. Each contractor shall coordinate its operations with operations of other contractors under this contract or others, included in different Sections, that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. If necessary, prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
  - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
  - 1. Preparation of Contractor's Construction Schedule.
  - 2. Preparation of the Schedule of Values.
  - 3. Installation and removal of temporary facilities and controls.
  - 4. Delivery and processing of submittals.
  - 5. Progress meetings.
  - 6. Preinstallation conferences.
  - 7. Project closeout activities.
  
- D. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.
  - 1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work.

#### 1.4 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
  - 1. Indicate relationship of components shown on separate Shop Drawings.
  - 2. Indicate required installation sequences.
  - 3. Refer to Division 16 Section "Basic Electrical Materials and Methods" for specific Coordination Drawing requirements for electrical installations.
  
- B. Staff Names. Within 5 days of starting construction operations, submit a list of the principal staff assignments, including superintendent and other personnel in attendance at Project site. List addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
  - 1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone.

#### 1.5 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work.
  - 1. Include special personnel required for coordination of operations with sub-contractors.

#### 1.6 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
  2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
  3. Minutes: The Architect will record significant discussions and agreements achieved and distribute the meeting minutes to everyone concerned, including Owner and Contractor, within 2 days of the meeting.
- B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than **7** days after execution of the Agreement unless otherwise directed by Owner.. Hold the conference at Project site. Conduct the meeting to review responsibilities and personnel assignments.
1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; manufacturers; suppliers; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  2. Agenda: Discuss items of significance that could affect progress, including the following:
    - a. Tentative construction schedule.
    - b. Phasing.
    - c. Critical work sequencing.
    - d. Designation of responsible personnel.
    - e. Procedures for processing field decisions and Change Orders.
    - f. Procedures for processing Applications for Payment.
    - g. Distribution of the Contract Documents.
    - h. Submittal procedures.
    - i. Preparation of Record Documents.
    - j. Use of the premises.
    - k. Responsibility for temporary facilities and controls.
    - l. Parking availability.
    - m. Office, work, and storage areas.
    - n. Equipment deliveries and priorities.
    - o. First aid.
    - p. Security.
    - q. Site Upkeep.
    - r. Working hours.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before construction activities that requires coordination with other construction as a part of weekly progress meetings.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
  2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
    - a. Contract Documents.
    - b. Options.
    - c. Related Change Orders.
    - d. Purchases.
    - e. Deliveries.

- f. Submittals.
  - g. Review of mockups.
  - h. Possible conflicts.
  - i. Compatibility problems.
  - j. Time schedules.
  - k. Weather limitations.
  - l. Manufacturer's written recommendations.
  - m. Warranty requirements.
  - n. Compatibility of materials.
  - o. Acceptability of substrates.
  - p. Temporary facilities and controls.
  - q. Space and access limitations.
  - r. Regulations of authorities having jurisdiction.
  - s. Testing and inspecting requirements.
  - t. Required performance results.
  - u. Protection of construction and personnel.
3. Record significant conference discussions, agreements, and disagreements.
  4. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress and coordination meetings at intervals as directed by the Contractor. Coordinate dates of meetings with preparation of payment requests.
1. Attendees: In addition to representatives of Owner and Architect, each subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
    - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    - b. Review present and future needs of each entity present, including the following:
      - 1) Interface requirements.
      - 2) Sequence of operations.
      - 3) Status of submittals.
      - 4) Deliveries.
      - 5) Off-site fabrication.
      - 6) Access.
      - 7) Site utilization.
      - 8) Temporary facilities and controls.
      - 9) Work hours.
      - 10) Hazards and risks.
      - 11) Progress cleaning.
      - 12) Quality and work standards.
      - 13) Change Orders.

- 14) Documentation of information for payment requests.
3. Reporting: The Architect will prepare meeting minutes and distribute to each party present and to parties who should have been present.
    - a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01310

## SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
  - 1. Preliminary Construction Schedule.
  - 2. Contractor's Construction Schedule.
  - 3. Daily construction reports.
  - 4. Field condition reports.
  - 5. Special reports.
- B. Related Sections include the following:
  - 1. Division 1 Section "Payment Procedures" for submitting the Schedule of Values.
  - 2. Division 1 Section "Project Management and Coordination" for submitting and distributing meeting and conference minutes.
  - 3. Division 1 Section "Submittal Procedures" for submitting schedules and reports.
  - 4. Division 1 Section "Quality Requirements" for submitting a schedule of tests and inspections.
  - 5. Division 1 Section "Closeout Procedures" for submitting Project Record Documents at Project closeout.

#### 1.3 SUBMITTALS

- A. Preliminary Construction Schedule: Submit **two** printed copies; one a single sheet of reproducible media, and one a print.
- B. Contractor's Construction Schedule: Submitted as part of RFP Response
- C. Daily Construction Reports: Submit one copy at **weekly** intervals.
- D. Field Condition Reports: Submit one copy at time of discovery of differing conditions.
- E. Special Reports: Submit one copy at time of unusual event.

#### 1.4 QUALITY ASSURANCE

- A. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination." Review methods and procedures related to the Preliminary Construction Schedule and Contractor's Construction Schedule, including, but not limited to, the following:

1. Discuss constraints, including **phasing, storage areas**.
2. Review time required for review of submittals and resubmittals.
3. Review requirements for tests and inspections by independent testing and inspecting agencies, If required
4. Review time required for completion and startup procedures.
5. Review and finalize list of construction activities to be included in schedule.
6. Review submittal requirements and procedures.
7. Review procedures for updating schedule.

#### 1.5 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities
- B. Coordinate Contractor's Construction Schedule with the Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.
  1. Secure time commitments for performing critical elements of the Work including delivery of equipment from parties involved.
  2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

### PART 2 - PRODUCTS

#### 2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Procedures: Comply with procedures contained in AGC's "Construction Planning & Scheduling."
- B. Time Frame: Extend schedule from date established for **commencement of the Work or the Notice to Proceed** to date of **Substantial Completion**.
- C. Activities: Treat each separate area as a separate numbered activity for each principal element of the Work. Comply with the following:
  1. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 30 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
  2. Submittal Review Time: Include review and resubmittal times indicated in Division 1 Section "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
  3. Startup and Testing Time: Include days for startup and testing as required by the Electrical Consultant.
  4. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Phasing: Arrange list of activities on schedule by phase or separate areas of the work,
2. Work Restrictions: Show the effect of the following items on the schedule:
  - a. Coordination with existing construction.
  - b. Uninterruptible services.
  - c. Use of premises restrictions.
  - d. Provisions for future construction.
  - e. Seasonal variations.
  - f. Environmental control.
3. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
  - a. Subcontract awards, if any.
  - b. Submittals.
  - c. Purchases.
  - d. Fabrication.
  - e. Sample testing.
  - f. Deliveries.
  - g. Installation.
  - h. Tests and inspections.
  - i. Adjusting.
  - j. Startup and placement into final use and operation.

- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, Percentage completion milestones and Final Completion.
- F. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis to demonstrate the effect of the proposed change on the overall project schedule.

## 2.2 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
  1. List of subcontractors at Project site, if any.
  2. List of separate contractors at Project site where applicable
  3. Approximate count of personnel at Project site.
  4. High and low temperatures and general weather conditions.
  5. Accidents.
  6. Meetings and significant decisions.
  7. Unusual events (refer to special reports).
  8. Stoppages, delays, shortages, and losses.
  9. Emergency procedures.
  10. Orders and requests of authorities having jurisdiction.
  11. Change Orders received and implemented.
  12. Construction Change Directives received.
  13. Services connected and disconnected.
  14. Equipment or system tests and startups.
  15. Partial Completions.
  16. Substantial Completions.

- B. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare a detailed report. Submit with a request for information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

## 2.3 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day of an occurrence. Distribute copies of report to parties affected by the occurrence.
- B. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

## PART 3 - EXECUTION

### 3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At weekly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one day before each regularly scheduled progress meeting.
  - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
  - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
  - 3. As the Work progresses, indicate Actual Completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect, Owner, sub-contractors, testing and inspecting agencies, if applicable and other parties identified by Contractor with a need-to-know schedule responsibility.
  - 1. Post copies in Project meeting rooms and temporary field offices.
  - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

## SECTION 013300 - SUBMITTAL PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other miscellaneous submittals.
- B. Related Sections include the following:
  - 1. Division 1 Section "Payment Procedures" for submitting Applications for Payment.
  - 2. Division 1 Section "Project Management and Coordination" for submitting Coordination Drawings.
  - 3. Division 1 Section "Construction Progress Documentation" for submitting schedules and reports, including Contractor's Construction Schedule and the Submittals Schedule
  - 4. Division 1 Section "Quality Requirements" for submitting test and inspection reports and Delegated-Design Submittals.
  - 5. Division 1 Section "Closeout Procedures" for submitting warranties Project Record Documents and operation and maintenance manuals.

#### 1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Architect's responsive action.
- B. Informational Submittals: Written information that does not require Architect's approval. Submittals may be rejected for not complying with requirements.

#### 1.4 SUBMITTAL PROCEDURES

- A. General: Electronic copies of CAD Drawings of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
    - a. **Architect reserves** the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

- C. Processing Time: Allow enough time for submittal review, including time for resubmittals, as follows. Time for review shall commence on **Architect's** receipt of submittal.
1. Initial Review: Allow 7 business days for initial review of each submittal. Allow additional time if processing must be delayed to permit coordination with subsequent submittals. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
  2. Concurrent Review: Where concurrent review of submittals by Architect's consultants, Owner, or other parties is required, allow 10 business days for initial review of each submittal.
  3. If intermediate submittal is necessary, process it in same manner as initial submittal.
  4. Allow 5 additional days for processing each resubmittal.
  5. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing.
- D. Identification: Place a permanent label or title block on each submittal for identification.
1. Indicate name of firm or entity that prepared each submittal on label or title block.
  2. Provide a space approximately **4 by 5 inches (100 by 125 mm)** on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
  3. Include the following information on label for processing and recording action taken:
    - a. Project name.
    - b. Date.
    - c. Name and address of Architect
    - d. Name and address of Contractor.
    - e. Name and address of subcontractor, if any
    - f. Name and address of supplier.
    - g. Name of manufacturer.
    - h. Unique identifier, including revision number.
    - i. Number and title of appropriate Specification Section.
    - j. Drawing number and detail references, as appropriate.
    - k. Other necessary identification.
- E. Deviations: Highlight, encircle, or otherwise identify deviations from the Contract Documents on submittals.
- F. Additional Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions of the Contract Documents, initial submittal may serve as final submittal.
1. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.
  2. Additional copies submitted for maintenance manuals will **not** be marked with action taken and will be returned.
- G. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will **return submittals, without review**, received from sources other than Contractor.
1. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements of the Contract Documents, including

- minor variations and limitations. Include the same label information as the related submittal.
2. Include Contractor's certification stating that information submitted complies with requirements of the Contract Documents.
  3. Transmittal Form: Provide locations on form for the following information:
    - a. Project name.
    - b. Date.
    - c. Destination (To:).
    - d. Source (From:).
    - e. Names of subcontractor, manufacturer, and supplier.
    - f. Category and type of submittal.
    - g. Submittal purpose and description.
    - h. Submittal and transmittal distribution record.
    - i. Remarks.
    - j. Signature of transmitter.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Use only final submittals with mark indicating action taken by Architect in connection with construction.

## PART 2 - PRODUCTS

### 2.1 ACTION SUBMITTALS

- A. General: Prepare and submit Action Submittals required by individual Specification Sections.
1. Number of Copies: Submit **FOUR** copies of each submittal, unless otherwise indicated. Architect will return one copy. Mark up and retain copy as a Project Record Document.
  2. Modifications of the number required may be modified by the Architect to fit specific project needs where additional copies may be required for portions of the work.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
  2. Mark each copy of each submittal to show which products and options are applicable.
  3. Include the following information, as applicable:
    - a. Manufacturer's written recommendations.
    - b. Manufacturer's product specifications.
    - c. Manufacturer's installation instructions.
    - d. Standard color charts.
    - e. Manufacturer's catalog cuts.
    - f. Wiring diagrams showing factory-installed wiring.
    - g. Printed performance curves.
    - h. Operational range diagrams.
    - i. Standard product operating and maintenance manuals.

- j. Compliance with recognized trade association standards.
    - k. Compliance with recognized testing agency standards.
    - l. Application of testing agency labels and seals.
    - m. Notation of coordination requirements.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
  - 1. Preparation: Include the following information, as applicable:
    - a. Dimensions.
    - b. Identification of products.
    - c. Fabrication and installation drawings.
    - d. Roughing-in and setting diagrams.
    - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
    - f. Shopwork manufacturing instructions.
    - g. Templates and patterns.
    - h. Schedules.
    - i. Design calculations.
    - j. Compliance with specified standards.
    - k. Notation of coordination requirements.
    - l. Notation of dimensions established by field measurement.
  - 2. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.
  - 3. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least **8-1/2 by 11 inches (215 by 280 mm)** but no larger than **30 by 40 inches (750 by 1000 mm)**.
  - 4. Number of Copies: Submit copies of each submittal, as follows:
    - a. Initial Submittal: Submit FOUR blue- or black-line prints. Architect, will return one print.
    - b. Final Submittal: Submit FOUR blue- or black-line prints, unless prints are required for operation and maintenance manuals. Submit nine prints where prints are required for operation and maintenance manuals. **Mark up and retain one returned print as a Project Record Drawing.**
- D. Coordination Drawings: Comply with requirements in Division 1 Section "Project Management and Coordination."
- E. Samples: Prepare physical units of materials or products, including the following:
  - 1. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
  - 2. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from the same material to be used for the Work, cured and finished in manner specified, and physically identical with the product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
  - 3. Preparation: Mount, display, or package Samples in manner specified to facilitate review of qualities indicated. Prepare Samples to match Architect's sample where so indicated. Attach label on unexposed side that includes the following:

- a. Generic description of Sample.
  - b. Product name or name of manufacturer.
  - c. Sample source.
4. Additional Information: On an attached separate sheet, prepared on Contractor's letter-head, provide the following:
  - a. Size limitations.
  - b. Compliance with recognized standards.
  - c. Availability.
  - d. Delivery time.
5. Submit Samples for review of kind, color, pattern, and texture for a final check of these characteristics with other elements and for a comparison of these characteristics between final submittal and actual component as delivered and installed.
  - a. Refer to individual Specification Sections for requirements for Samples that illustrate workmanship, fabrication techniques, details of assembly, connections, operation, and similar construction characteristics.
6. Number of Samples for Initial Selection: Submit two full sets of available choices where establishment of a level of quality is required to be selected from manufacturer's product line. Architect will return submittal with options selected.
7. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
  - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
  - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- F. Product Schedule or List: Prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
  1. Type of product. Include unique identifier for each product.
  2. Location .
- G. Contractor's Construction Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation" for Construction Manager's action.
- H. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
  1. Name, address, and telephone number of entity performing subcontract or supplying products.
  2. Number and title of related Specification Section(s) covered by subcontract.
  3. Drawing number and detail references, as appropriate, covered by subcontract.

## 2.2 INFORMATIONAL SUBMITTALS

- A. General: Prepare and submit Informational Submittals required by other Specification Sections.
  - 1. Number of Copies: Submit FOUR copies of each submittal, unless otherwise indicated. Architect will not return copies.
  - 2. Certificates and Certifications: Provide a notarized statement that includes signature of Contractor, testing agency, or design professional responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of the company.
  - 3. Test and Inspection Reports: Comply with requirements in Division 1 Section "Quality Requirements."
- B. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- C. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements.
- D. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on AWS forms. Include names of firms and personnel certified.
- E. Installer Certificates: Prepare written statements on manufacturer's letterhead certifying that Installer complies with requirements and, where required, is authorized for this specific Project.
- F. Manufacturer Certificates: Prepare written statements on manufacturer's letterhead certifying that manufacturer complies with requirements. Include evidence of manufacturing experience where required.
- G. Material Certificates: Prepare written statements on manufacturer's letterhead certifying that material complies with requirements.
- H. Material Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements.
- I. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements.
- J. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements.
- K. Product Test Reports: Prepare written reports indicating current product produced by manufacturer complies with requirements. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- L. Research/Evaluation Reports: Prepare written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:

1. Name of evaluation organization.
  2. Date of evaluation.
  3. Time period when report is in effect.
  4. Product and manufacturers' names.
  5. Description of product.
  6. Test procedures and results.
  7. Limitations of use.
- M. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements in Division 1 Section "**Closeout Procedures.**"
- N. Design Data: Prepare written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable.
- O. Manufacturer's Instructions: Prepare written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:
1. Preparation of substrates.
  2. Required substrate tolerances.
  3. Sequence of installation or erection.
  4. Required installation tolerances.
  5. Required adjustments.
  6. Recommendations for cleaning and protection.
- P. Insurance Certificates and Bonds: Prepare written information indicating current status of insurance or bonding coverage. Include name of entity covered by insurance or bond, limits of coverage, amounts of deductibles, if any, and term of the coverage.
- Q. Material Safety Data Sheets: Submit information directly to Owner. If submitted to Architect, Architect will not review this information but will return it with no action taken.

### PART 3 - EXECUTION

#### 3.1 ARCHITECT'S ACTION

- A. General: ARCHITECT WILL NOT REVIEW SUBMITTALS THAT DO NOT BEAR CONTRACTOR'S APPROVAL STAMP AND WILL RETURN THEM WITHOUT ACTION.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or modifications required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action taken.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will reject and return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Submittals not required by the Contract Documents will not be reviewed and may be discarded.

END OF SECTION 013300



MHTN  
ARCHITECTS

## License and Indemnification Agreement

Project: STEWART STADIUM TRACK RENOVATION

MHTN Project Number: 2010576.00

In response to the Receiver's request to obtain Drawings, Specifications, electronic data, and/or other Instruments of Service (the "Information") produced by MHTN Architects, Inc. ("MHTN") for the above referenced project, MHTN and the Receiver agree to the following:

Receiver's authorized representative to initial Receiver's assent to each term in the space provided.

- \_\_\_\_\_ 1. MHTN grants to the Receiver a non-exclusive license to the Information for production of the Receiver's portion of the work for this project only. The Receiver shall not transfer or assign this license. MHTN retains its copyrights, the right to retain electronic data or other reproducible copies of the Information, and the right to use information, ideas, and/or concepts contained in the Information in the normal course of the its professional activities.
  
- \_\_\_\_\_ 2. The Information is for information purposes only. Under no circumstances shall the conveyance of the Information be deemed a sale by MHTN. MHTN makes no warranties, express or implied, of merchantability or of fitness of the Information for a particular purpose.
  
- \_\_\_\_\_ 3. The Receiver shall remove all title blocks and other references to MHTN, MHTN's consultants, and the project owner from the electronic data contained in the Information upon receipt.
  
- \_\_\_\_\_ 4. The Receiver shall remove all notes, text, and detail cuts from the electronic data contained in the Information upon receipt.
  
- \_\_\_\_\_ 5. Use of the Information shall be at Receiver's sole risk and without liability to MHTN or its consultants. The Receiver shall make no claim against MHTN or its consultants. The Receiver shall defend, indemnify, and hold harmless MHTN, MHTN's consultants, and agents and employees of any of them from and against all claims, damages, losses, and expenses, including but not limited to attorney fees and costs, arising out of the Receiver's use of the Information.

Receiver Company Name: \_\_\_\_\_

Officer & Title (printed): \_\_\_\_\_

Officer & Title (signed): \_\_\_\_\_

Date: \_\_\_\_\_

MHTN Architects, Inc.

Representative & Title (printed): \_\_\_\_\_

Representative & Title (signed): \_\_\_\_\_

Date: \_\_\_\_\_

## SECTION 014000 - QUALITY CONTROL

### PART 1 GENERAL

#### 1.01 REQUIREMENTS INCLUDED

- A. General Quality Control
- B. Workmanship
- C. Manufacturer's Instructions
- D. Manufacturer's Certificates
- E. Manufacturer's Field Services
- F. Testing Laboratory Services

#### 1.02 RELATED REQUIREMENTS

- A. General Conditions: Inspection and testing required by governing authorities.
- B. Section 01105 - Administrative Provisions
- C. Section 01330 - Submittals: Shop Drawings, Product Data, Manufacturer's Instructions.

#### 1.03 QUALITY CONTROL - GENERAL

- A. Maintain quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce work of specified quality.

#### 1.04 WORKMANSHIP

- A. Comply with industry standards except when more restrictive tolerances or specified requirements indicate more rigid standards or more precise workmanship.
- B. Perform work by persons qualified to produce workmanship of specified quality.
- C. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, and racking.

#### 1.05 MANUFACTURERS' INSTRUCTIONS

- A. Comply with instructions in full detail, including each step in sequence. Should instructions conflict with Contract Documents, request clarification from Engineer before proceeding.

#### 1.06 MANUFACTURERS' CERTIFICATES

- A. When required by individual Specifications Section, submit manufacturer's certificate, in duplicate, that products meet or exceed specified requirements.

#### 1.07 MANUFACTURERS' FIELD SERVICES

- A. When specified in respective Specification Sections, require supplier to provide qualified personnel to observe field conditions, quality of workmanship, as applicable, and to make appropriate recommendations.
- B. Representative shall submit written report to Engineer listing observations and recommendations.

1.08 TESTING LABORATORY SERVICES

- A. Owner will employ and pay for services of an Independent Testing Laboratory to perform inspections, tests, and other services required by individual Specification Sections.
- B. Services will be performed in accordance with requirements of local jurisdiction having authority and with specified standards.
- C. Reports will be submitted to Owner in duplicate giving observations and results of tests, indicating compliance or non-compliance with specified standards and with Contract Documents.
- D. Contractor shall cooperate with Testing Laboratory personnel; furnish tools, samples of materials, mix design, equipment, storage and assistance as requested.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTIONS

Not Used.

END OF SECTION

## SECTION 014200 - REFERENCES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": The term "approved," when used in conjunction with Architect's action on Contractor's submittals, applications, and requests, is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": Terms such as "directed," "requested," "authorized," "selected," "approved," "required," and "permitted" mean directed by Architect, requested by Architect, and similar phrases.
- D. "Indicated": The term "indicated" refers to graphic representations, notes, or schedules on Drawings; or to other paragraphs or schedules in Specifications and similar requirements in the Contract Documents. Terms such as "shown," "noted," "scheduled," and "specified" are used to help the user locate the reference.
- E. "Regulations": The term "regulations" includes laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, as well as rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": The term "furnish" means to supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": The term "install" describes operations at Project site including unloading, temporary storage, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": The term "provide" means to furnish and install, complete and ready for the intended use.
- I. "Installer": An installer is Contractor or another entity engaged by Contractor, as an employee, subcontractor, or contractor of lower tier, to perform a particular construction operation, including installation, erection, application, and similar operations.
- J. The term "experienced," when used with the term "installer," means having successfully completed a minimum of **five** previous projects similar in size and scope to this Project; being familiar with the special requirements indicated; and having complied with requirements of authorities having jurisdiction.
  - 1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name,

such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.

- K. "Project site" is the space available for performing construction activities, either exclusively or in conjunction with others performing other work as part of Project. The extent of Project site is shown on the Drawings and may or may not be identical with the description of the land on which Project is to be built.

### 1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of the date of the Contract Documents, unless otherwise indicated.
- C. Conflicting Requirements: Where compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
  - 1. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of the requirements. Refer uncertainties to Architect for a decision before proceeding.
- D. Copies of Standards: Each entity engaged in construction on Project must be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
  - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from the publication source and make them available on request.
- E. Abbreviations and Names: Abbreviations and acronyms are frequently used in the Specifications and other Contract Documents to represent the name of a trade association, standards-developing organization, authorities having jurisdiction, or other entity in the context of referencing a standard or publication. Where abbreviations and acronyms are used in the Specifications or other Contract Documents, they mean the recognized name of these entities. Refer to Gale Research's "Encyclopedia of Associations" or Columbia Books' "National Trade & Professional Associations of the U.S.," which are available in most libraries.

PART 2 - PRODUCTS - (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

## SECTION 014533 – STRUCTURAL TESTS AND SPECIAL INSPECTIONS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This section includes administrative and procedural requirements required for compliance with the International Building Code, Chapter 17, Structural Tests and Special Inspections.
- B. Structural testing and special inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve contractor of responsibility for compliance with other construction document requirements.
  - 1. Specific quality-assurance and control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
  - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality assurance and control procedures that facilitate compliance with the construction document requirements.
  - 3. Requirements for contractor to provide quality-assurance and control services required by architect, owner, or authorities having jurisdiction are not limited by provisions of this section.
- C. The owner will engage one or more qualified special inspectors and/or testing agencies to conduct structural tests and special inspections specified in this section and related sections and as maybe specified in other divisions of these specifications.
- D. Related Sections include but are nor limited to the following;
  - 1. 033000 CAST-IN-PLACE CONCRETE
  - 2. 312000 EARTH WORK
  - 3. 321216 ASPHALT PAVING
  - 4. 321313 CONCRETE PAVING
- E. Approved Agency: An established and recognized agency regularly engaged in conducting tests or furnishing inspection services, when such agency has been approved by the building official.
- F. Construction Documents: Written, graphic and pictorial documents prepared or assembled for describing the design, location and physical characteristics of the elements of a project necessary for obtaining a building permit. Construction Documents include all supplemental instruction, sketches, addenda, and revisions to the drawings and specifications issued by the registered design professional beyond those issued for a building permit.
- G. Shop Drawings / Submittal Data: Written, graphic and pictorial documents prepared and / or assembled by the contractor based on the Construction Documents.

- H. Structural Observations: Visual observation of the structural system by a representative of the registered design professional's office for the general conformance to the approved construction documents. Structural observations are not considered part of the structural tests and special inspections and do not replace inspections and testing by the testing agency or special inspector.
- I. Special Inspector: A qualified person who demonstrating competence, to the satisfaction of the code enforcement official and registered design professional in responsible charge, for inspection of the particular type of construction or operation requiring special inspection. The special inspector shall be a licensed professional engineer or engineering intern or a qualified representative from the testing agency.
- J. Special Inspection, Continuous: The full-time observation of work requiring special inspection by an approved special inspector who is present in the area where the work is being performed.
- K. Special Inspection, Periodic: The part-time or intermittent observation of work requiring special inspection by an approved special inspector who is present in the area where the work has been ort is being performed and at the completion of the work.
- L. Testing Agency: A qualified materials testing laboratory under the responsible charge of a licensed professional engineer, approved by the code enforcement official and the registered design professional in responsible charge, to measure, examine, test, calibrate, or otherwise determine the characteristics or performance of construction materials and verify confirmation with construction documents.

### 1.3 QUALITY ASSURANCE

- A. Testing Agency Qualifications:
  - 1. Minimum qualifications of inspection and testing agencies and their personnel shall comply with ASTM E329-03 Standard Specification for agencies on the Testing and / or Inspection of Materials used in construction.
    - a. Inspectors and individuals performing tests shall be certified for the work being performed as outlined in the appendix of the ASTM E329. Certification by organizations other than those listed must be submitted to the building official for consideration before proceeding with work.
  - 2. In addition to these requirements, local jurisdiction may have additional requirements. It is the responsibility of the testing and inspection agencies to meet local requirements and comply with local procedures.

### 1.4 CONFLICTING REQUIREMENTS, REPORTS AND TEST RESULTS

- A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to the registered design professional in responsible charge for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate,

for the context of requirements. Refer uncertainties to the registered design profession in responsible charge for a decision before proceeding.

- C. The special inspector's reports and testing agencies results shall have precedence over reports and test results provided by the contractor.
- D. Where a conflict exists between the construction documents and approved shop drawings / submittal data, the construction documents shall govern unless the shop drawings / submittal data are more restrictive. All conflicts shall be brought to the attention of the registered design professional in responsible charge.

#### 1.5 SUBMITTAL BY SPECIAL INSPECTOR AND / OR TESTING AGENCY

- A. Special inspectors shall keep and distribute records of inspections. The special inspector shall furnish inspection reports to the building official, and to the registered design professional in responsible charge, contractor, architect, and owner. Reports shall indicate that work inspected was done in conformance to approved construction documents. Discrepancies shall be brought to the immediate attention of the contractor for correction. If the discrepancies are not corrected, the discrepancies shall be brought to the attention of the contractor for correction. If the discrepancies are not corrected the discrepancies shall be brought to the attention of the building official and to the registered design professional in responsible charge prior to the completion of that phase of the work. A final report documenting required special inspections and correction of any discrepancies noted in the inspections shall be submitted at a point in time agreed upon by the permit applicant and the building official prior to the start of work.
  - 1. Special inspection report and test results shall include, but not be limited to, the following:
    - a. Date of inspection.
    - b. Description of inspections or tests performed including location (reference grid lines, floors, elevations etc.).
    - c. Statement noting that the work, material and / or product conforms or does not conform to the construction document requirements.
      - 1) Name and signature of contractor's representative who was notified of work, material, and / or products that do not meet the construction document requirements.
    - d. Name and signature of special inspector and / or testing agency representative performing the work.
- B. Schedule of Non-Compliant Work: Each agent shall maintain a log of work that does not meet the requirements of the construction documents. Include reference to the original inspection / test report and subsequent dates of re-inspection / retesting.
- C. Reports and tests shall be submitted within 1 week of inspection or test. Schedule of Non-Compliant Work shall be updated daily and submitted on monthly intervals.
- D. Final report of Special Inspections. Submitted by each agent listed in the schedule of Structural Testing and Special Inspections.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 CONTRACT RESPONSIBILITY

- A. The contractor shall coordinate the inspection and testing services with the progress of their work. The contractor shall provide sufficient notice to allow proper scheduling of all personnel. The contractor shall provide safe access for performing inspection and on site testing.
- B. The contractor shall submit schedules to the owner, registered design professionals and testing and inspecting agencies. Schedule shall note milestones and durations of time for materials requiring structural tests and special inspections.
- C. Each contractor responsible for the construction of a seismic-force-resisting system, designated seismic system, or component listed in the quality assurance plan shall submit written contractor's statement of responsibility to the building official and the owner prior to the commencement of work on the system or component. The contractor's statement of responsibility shall contain the following:
  - 1. Acknowledgement of awareness of the special requirements contained in the quality assurance plan.
  - 2. Acknowledgement that control will be exercised to obtain conformance with the construction documents approved by the building official.
  - 3. Procedures for exercising control within the contractor's organization, the method and frequency of reporting and the distribution of the reports.
  - 4. Identification and qualifications of the person(s) exercising such control and their position(s) in the organization.
- D. Each contractor responsible for the construction of a main windforce-resisting system, or a wind-resisting component listed in the quality assurance plan shall submit a written statement of responsibility to the building official and owner prior to the commencement of work on the system or component. The contractor's statement of responsibility shall contain the following:
  - 1. Acknowledgement of awareness of the special requirements contained in the quality assurance plan.
  - 2. Acknowledgement that control will be exercised to obtain conformance with the construction documents approved by the building official.
  - 3. Procedures for exercising control within the contractor's organization, the method and frequency of reporting and the distribution of the reports.
  - 4. Identification and qualifications of the person(s) exercising such control and their position(s) in the organization.
- E. The contractor shall repair and/or replace as directed by the Architect or the ownerwork that does not meet the requirements of the construction documents.
  - 1. Contractor shall engage an engineer / Architect to prepare repair and / or replacement procedures.
  - 2. Engineer / Achitect shall be registered in the state in which the project if located. Engineer shall be acceptable to the registered design professional in responsible charge, code enforcement official, and owner.

3. Procedures shall be submitted for review and acceptance by the registered design professional in responsible charge, code enforcement official and owner before proceeding with corrective action.

F. The contractor shall be responsible for costs of:

1. Re-testing and re-inspection of materials, work and / or products that do not meet the requirements of the construction documents and shop drawings / submittal data.
2. Review of the proposed repair and / or replacement procedures by the registered design professional in responsible charge and the inspectors and testing agencies.
3. Repair or replacement of work that does not meet the requirements of the construction documents.

### 3.2 STRUCTURAL OBSERVATIONS

- A. Structural observations may be made periodically as determined by the registered design professional in responsible charge.

### 3.3 TESTING AND INSPECTION

- A. Testing and inspection shall be in accordance with the attached Schedule of Special Inspections.
- B. Reference related specifications for the minimum level of inspections and testing. Provide additional inspections and testing as necessary to determine compliance with the construction drawings.

## PART 4 - SCHEDULES AND FORMS (ATTACHED)

### 4.1 SCHEDULES OF SPECIAL INSPECTIONS.

END OF SECTION 014533

## SECTION 015000 - CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

### PART 1 GENERAL

#### 1.01 REQUIREMENTS INCLUDED

- A. Contractor shall provide all materials, labor, equipment, transportation, fees, permits and other items required to provide construction facilities and temporary controls as indicated or as required to accomplish Work of other sections of these specifications. All construction facilities and temporary controls shall be in accordance with applicable regulations and as specified herein.
- B. Construction facilities and temporary controls includes, but is not limited to the following:
  - 1. Temporary Utilities
  - 2. Barriers and Enclosures
  - 3. Security
  - 4. Temporary Controls
  - 5. Traffic Regulation
  - 6. Protection of Existing Track surface and adjacent construction to remain

#### 1.02 REFERENCES

- A. The applicable provisions of the latest editions of the References listed below shall govern the Work covered under this Section, unless there is a conflict between said References and the requirements of this Section. In the case of such a conflict, the requirements of this Section shall apply.
- B. American National Standards Institute (ANSI)
- C. American Society for Testing of Materials (ASTM)
- D. National Electrical Code (NEC)
- E. National Fire Protection Association (NFPA)
- F. Underwriters Laboratories (UL)
- G. Utah Occupational Safety and Health Division (UOSHD).
- H. American Association of State Highway and Transportation Officials (AASHTO)
- I. Utah Department of Transportation Standard Specifications for Roads and Bridges (UDOT)
- J. Manual of Uniform Traffic Control Devices (MUTCD)

#### 1.3 USE CHARGES

- A. General: Cost or use charges for temporary facilities are not chargeable to Owner or Architect and shall be included in the Contract Sum. Allow other entities to use temporary services and facilities without cost, including, but not limited to, the following:
  - 1. Architect.
  - 2. Testing agencies.
  - 3. Personnel of authorities having jurisdiction.
- B. Water Service: Use water from hydrant mounted meter adjacent to site obtained by the Contractor.
- C. Electric Power Service: Use electric power from Owner's existing system without metering and without payment of use charges.

## PART 2 - PRODUCTS

### 2.1 GENERAL

- A. Contractor shall provide all materials for accomplishing the Work of this Section in accordance with applicable standards and regulations and as specified herein.
- B. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation, or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.

### 2.2 EQUIPMENT

- A. General: Provide equipment suitable for use intended.
- B. Fire Extinguishers: Hand carried, portable, UL rated. Provide class and extinguishing agent as indicated or a combination of extinguishers of NFPA-recommended classes for exposures.
  - 1. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.
- C. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation, or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.

## PART 3 - EXECUTION

### 3.01 TEMPORARY UTILITIES

- A. Provide service required for construction operations.

### 3.02 BARRIERS AND ENCLOSURES

- A. Provide as required to prevent public entry to construction areas and to protect existing facilities and adjacent properties from damage from construction operations.
- B. New construction provide fence around construction site; equip with vehicular and pedestrian gates with locks. Construction: Contractor's option.
- C. Provide barricades and covered walkways as required by governing authorities for public rights-of-way and for public access to existing building(s).
- D. New construction provide barriers around trees and plants designated to remain. Protect against vehicular traffic, stored materials, dumping, chemically injurious materials, and puddling or continuous running water.

### 3.03 SECURITY

- A. Provide temporary enclosures for work in progress . Control traffic in immediate area to minimize damage.
- B. Prohibit traffic on lawn and landscaped areas, except where landscaping is to be replaced.

### 3.04 TEMPORARY CONTROLS

#### A. Surface Water, Erosion and Sediment Control:

1. Surface water shall be controlled so that the construction area is not allowed to become wet from runoff from adjacent areas. Surface water shall be directed away from these areas but not directed toward adjacent property, buildings, or any improvement that may be damaged by water. Surface water shall not be allowed to enter sanitary sewers.
2. Maintain excavations free of water. Provide and operate pumping equipment.
3. Prevent erosion and sedimentation.
4. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.

#### B. Construction Cleaning

1. All public and private areas used as haul roads shall be continuously maintained and cleaned of all construction caused debris such as mud, sand, gravel, soils, pavement fragments, sod, etc. Care shall be taken to prevent spillage on haul routes. Any such spillage shall be removed immediately and the area cleaned.
2. Public roads shall be maintained in accordance with applicable ordinances and regulations.
3. Throughout all phases of construction, including suspension of work, and until final acceptance, the Contractor shall keep the work site clean and shall remove daily all refuse, dirt, damaged materials, unusable materials, and all other trash or debris that he has created from his construction activities.
4. Materials and equipment shall be removed from the site as soon as they are no longer necessary; and upon completion of the work and before final inspection, the entire worksite shall be cleared of equipment, unused materials, and rubbish so as to present a satisfactory clean and neat appearance. All cleanup costs shall be included in the Contractor's Bid.

#### C. Dust Control:

1. Dust control measures shall be implemented by application of water to all work areas, storage areas, haul and access roads, or other areas affected by construction.
2. All work shall be in compliance with the Federal, State, and local air pollution standards, and not cause a hazard or nuisance to personnel and the public in the vicinity of the work.
3. Provide and operate at least 1 mobile tank sprinkling unit or other positive means to prevent air-borne dust from dispersing into atmosphere.
4. Other methods of dust control for haul and access roads may include chemical treatment, light bituminous treatment or other method as approved by the Engineer.

5. Execute work by methods to minimize raising dust from construction operations.

D. Protection of Existing components that remain.

1. The existing track, supporting asphalt paving, curb edging and channel drain systems are to be maintained in a like new condition throughout the course of the work. Any damage incurred shall require patching with materials identical to original and by approved installers to keep existing warranties intact.

2. Supplemental supports to avoid point loads shall be spread across the track area where trucks will access the field site. Daily surveys shall determine if additional supports and protections are needed to insure against damage.

### 3.05 TRAFFIC REGULATION

- A. Control vehicular parking to prevent interference with public traffic and parking, access by emergency vehicles, and Owner's operations.
- B. Monitor parking of construction personnel's vehicles. Maintain vehicular access to and through parking areas.
- C. Prevent parking on or adjacent to access roads or in non-designated areas.
- D. Provide trained and equipped flagmen to regulate traffic when construction operations or traffic encroach on public traffic lanes. Provide control in accordance with local authority having jurisdiction.
- E. Use flares and lights during hours of low visibility to delineate traffic lanes and to guide traffic.
- F. Consult with authorities, establish public thoroughfares to be used for haul routes and site access.
- G. Confine construction traffic to haul routes and designated construction limits.
- H. Provide traffic control at critical areas of haul routes to regulate traffic, to minimize interference with public traffic.
- I. At approaches to site and on site, install at crossroads, detours, parking areas, and elsewhere as needed to direct construction and affected public traffic.
- J. Relocate as Work progresses, to maintain effective traffic control.
- K. Maintain traffic flow to private driveways during entire contract period.
- L. Post-mounted traffic control and informational signs, traffic cones and drums, flagman equipment: As approved by local jurisdictions.
- M. Where local jurisdictions have no requirements, construct and erect according to "Manual on Uniform Traffic Control Devices for Streets and Highways" (MUTCD).
- N. Remove equipment and devices when no longer required, confirm with owner prior to removal. Repair damage caused by installation. Remove post settings to a depth of 3 feet.

### 3.6 SUPPORT FACILITIES INSTALLATION

A. General: Comply with the following:

1. Locate sanitary facilities, and other temporary construction and support facilities for easy access.
2. Maintain support facilities until near Substantial Completion. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

B. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Containerize and clearly label hazardous, dangerous, or unsanitary waste materials separately from other waste. Comply with Division 1 Section "Execution Requirements" for progress cleaning requirements.

1. Develop a waste management plan for Work performed on Project. Indicate types of waste materials Project will produce and estimate quantities of each type. Provide detailed information for on-site waste storage. Provide information on destination of each type of waste material and means to be used to dispose of all waste materials.

C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking-water fixtures. Comply with regulations and health codes for type, number, location, operation, and maintenance of fixtures and facilities.

1. Disposable Supplies: Provide toilet tissue, paper towels, paper cups, and similar disposable materials for each facility. Maintain adequate supply. Provide covered waste containers for disposal of used material.
2. Toilets: Install self-contained toilet units. Shield toilets to ensure privacy. Use of existing facilities will not be permitted while school is in session.

END OF SECTION

## SECTION 016000 - PRODUCT REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following administrative and procedural requirements: selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties;
- B. Related Sections include the following:
  - 1. Division 1 Section "Closeout Procedures" for submitting warranties for contract closeout.
  - 2. Division 2 Sections for specific requirements for warranties on products and installations specified to be warranted.

#### 1.3 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
  - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation, shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
  - 2. New Products: Items that have not previously been incorporated into another project or facility]. Products salvaged or recycled from other projects are not considered new products.
- B. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor are allowed only before bid, and will not be considered in the course of Construction.
- C. Basis-of-Design Product Specification: Where a specific manufacturer's product is named and accompanied by the words "basis of design", "Design Standard" or similar, including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of other named manufacturers.
- D. Manufacturer's Warranty: Preprinted written warranty published by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
- E. Special Warranty: Written warranty required by or incorporated into the Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Owner.

#### 1.4 SUBMITTALS

- A. Product List: Submit a list, in tabular form, showing specified products. Include generic names of products required. Include manufacturer's name and proprietary product names for each product.
1. Coordinate product list with Contractor's Construction Schedule and the Submittals Schedule.
  2. Form: Tabulate information for each product under the following column headings:
    - a. Specification Section number and title.
    - b. Generic name used in the Contract Documents.
    - c. Proprietary name, model number, and similar designations.
    - d. Manufacturer's name and address.
    - e. Supplier's name and address.
    - f. Installer's name and address.
    - g. Projected delivery date or time span of delivery period.
    - h. Identification of items that require early submittal approval for scheduled delivery date.
  3. Initial Submittal: Within 5 days after date of commencement of the Work, submit 8 copies of initial product list. Include a written explanation for omissions of data and for variations from Contract requirements.
    - a. At Contractor's option, initial submittal may be limited to product selections and designations that must be established early in Contract period.
  4. Completed List: Within 7 days after date of commencement of the Work, submit 8 copies of completed product list. Include a written explanation for omissions of data and for variations from Contract requirements.
  5. Architect's Action: Architect will respond in writing to Contractor within 7 days of receipt of completed product list. Architect's response will include a list of unacceptable product selections and a brief explanation of reasons for this action. Architect's response, or lack of response, does not constitute a waiver of requirement that products comply with the Contract Documents
  6. Substitution Requests: Will not be considered due to the limited construction time frame of this Project.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 1 Section "Submittal Procedures." Show compliance with requirements.

#### 1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options.
1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
  2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.

## 1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
  - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
  - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
  - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
  - 4. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
  - 5. Store products to allow for inspection and measurement of quantity or counting of units.
  - 6. Store materials in a manner that will not endanger Project structure.
  - 7. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
  - 8. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
  - 9. Protect stored products from damage.
- B. Storage: Provide a secure location and enclosure at Project site for storage of materials and equipment. Coordinate location with Owner.

## 1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution. Submit a draft for approval before final execution.
  - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
  - 2. Refer to Divisions 2 through 16 Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Division 1 Section "Closeout Procedures."

## PART 2 - PRODUCTS

### 2.1 PRODUCT OPTIONS

- A. General Product Requirements: Provide products that comply with the Contract Documents, that are undamaged, and unless otherwise indicated, that are new at time of installation.
1. Provide products complete with accessories, fasteners, and other items needed for a complete installation and indicated use and effect.
  2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
  3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
  4. Where products are accompanied by the term "as selected," Architect will make selection.
  5. Where products are accompanied by the term "match sample," sample to be matched is Architect's.
  6. Descriptive, performance, and reference standard requirements in the Specifications establish "salient characteristics" of products.
  7. Or Equal: Where products are specified by name and accompanied by the term "or equal" or "or approved equal" or "or approved," comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.
- B. Product Selection Procedures: Procedures for product selection include the following:
1. Product: Where Specification paragraphs or subparagraphs titled "Product" name a single product and manufacturer, provide the product named.
  2. Manufacturer/Source: Where Specification paragraphs or subparagraphs titled "Manufacturer" or "Source" name single manufacturers or sources, provide a product by the manufacturer or from the source named that complies with requirements.
  3. Products: Where Specification paragraphs or subparagraphs titled "Products" introduce a list of names of both products and manufacturers, provide one of the products listed that complies with requirements.
  4. Manufacturers: Where Specification paragraphs or subparagraphs titled "Manufacturers" introduce a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements.
  5. Available Products: Where Specification paragraphs or subparagraphs titled "Available Products" introduce a list of names of both products and manufacturers, provide one of the products listed or another product that complies with requirements. Comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.
  6. Available Manufacturers: Where Specification paragraphs or subparagraphs titled "Available Manufacturers" introduce a list of manufacturers' names, provide a product by one of the manufacturers listed or another manufacturer that complies with requirements. Comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.
  7. Basis-of-Design Products: Where Specification paragraphs or subparagraphs titled "Basis-of-Design Products" or "Design Standards" are included and also introduce or refer to a list of manufacturers' names, provide either the specified product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product

named. Comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.

8. Visual Matching Specification: Where Specifications require matching an established Sample, select a product (and manufacturer) that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches satisfactorily.
9. Visual Selection Specification: Where Specifications include the phrase "as selected from manufacturer's colors, patterns, textures" or a similar phrase, select a product (and manufacturer) that complies with other specified requirements.
  - a. Standard Range: Where Specifications include the phrase "standard range of colors, patterns, textures" or similar phrase, Architect will select color, pattern, or texture from manufacturer's product line that does not include premium items.
  - b. Full Range: Where Specifications include the phrase "full range of colors, patterns, textures" or similar phrase, Architect will select color, pattern, or texture from manufacturer's product line that includes both standard and premium items.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000



SUBSTITUTION REQUEST (After the Bidding Phase)

Project: Substitution Request Number: From: To: Date: A/E Project Number: Re: Contract For:

Specification Title: Description: Section: Page: Article/Paragraph:

Proposed Substitution: Manufacturer: Address: Phone: Trade Name: Model No.: Installer: Address: Phone:

History: [ ] New product [ ] 2-5 years old [ ] 5-10 yrs old [ ] More than 10 years old

Differences between proposed substitution and specified product:

[ ] Point-by-point comparative data attached - REQUIRED BY A/E

Reason for not providing specified item:

Similar Installation:

Project: Architect: Address: Owner: Date Installed:

Proposed substitution affects other parts of Work: [ ] No [ ] Yes; explain

Savings to Owner for accepting substitution: (\$ )

Proposed substitution changes Contract Time: [ ] No [ ] Yes [Add] [Deduct] days.

Supporting Data Attached: [ ] Drawings [ ] Product Data [ ] Samples [ ] Tests [ ] Reports [ ]

# SUBSTITUTION REQUEST (Continued)

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted by: \_\_\_\_\_

Signed by: \_\_\_\_\_

Firm: \_\_\_\_\_

Address: \_\_\_\_\_

Telephone: \_\_\_\_\_

Attachments: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## A/E's REVIEW AND ACTION

- Substitution approved - Make submittals in accordance with Specification Section 01330.
- Substitution approved as noted - Make submittals in accordance with Specification Section 01330.
- Substitution rejected - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by:

Date:

Additional Comments:     Contractor     Subcontractor     Supplier     Manufacturer     A/E     \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## SECTION 01700 - EXECUTION REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes general procedural requirements governing execution of the Work including, but not limited to, the following:
  - 1. General installation of products.
  - 2. Coordination of Owner-installed products.
  - 3. Progress cleaning.
  - 4. Protection of installed construction.
  - 5. Correction of the Work.
- B. Related Sections include the following:
  - 1. Division 1 Section "Project Management and Coordination" for procedures for coordinating field engineering with other construction activities.
  - 2. Division 1 Section "Cutting and Patching" for procedural requirements for cutting and patching necessary for the installation or performance of other components of the Work.
  - 3. Division 1 Section "Closeout Procedures" for Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.

### PART 2 - PRODUCTS (Not Used)

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Existing Conditions: The existence and location of construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.
  - 1. Before construction, verify the location and points of connection of utility services.
- B. Existing Utilities: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; and underground electrical services to avoid any interference with work of this Contract.

2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- C. Acceptance of Conditions: Examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
1. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
    - a. Description of the Work.
    - b. List of detrimental conditions, including substrates.
    - c. List of unacceptable installation tolerances.
    - d. Recommended corrections.
  2. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
1. Notify **Architect/Owner** not less than **two** days in advance of proposed utility interruptions.
  2. Do not proceed with utility interruptions without **Owner's** written permission. Service interruption must be coordinated with times outside normal school hours and where required, of duration to permit reheating or cooling of the facility prior to time for occupancy.
- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect. Include a detailed description of problem encountered, together with recommendations for changing the Contract Documents. **Submit requests on CSI Form 13.2A, "Request for Interpretation"**, included at end of this Section, or contractors standard form if acceptable to Architect.

### 3.4 INSTALLATION

- A General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
1. Make vertical work plumb and make horizontal work level.
  2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.

- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of the Work.
  - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
  - 2. Allow for building movement, including thermal expansion and contraction.
- G. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- H. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

### 3.5 PROGRESS CLEANING

- A. General: Clean Project site daily, including common areas. Coordinate progress cleaning for joint-use areas where more than one installer has worked. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
  - 2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80 deg F (27 deg C).
  - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.

1. Cutting and Patching: Clean areas and spaces where cutting and patching are performed.
- G. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted.
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

### 3.6 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

### 3.7 CORRECTION OF THE WORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes.
- B. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- C. Restore permanent facilities used during construction to their specified condition.
- D. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.

END OF SECTION 017000



# REQUEST FOR INTERPRETATION

Project: _____	R.F.I. Number: _____
_____	From: _____
To: _____	Date: _____
_____	A/E Project Number: _____
Re: _____	Contract For: _____

Specification Section: _____	Paragraph: _____	Drawing Reference: _____	Detail: _____
------------------------------	------------------	--------------------------	---------------

Request:

Signed by: _____	Date: _____
------------------	-------------

Response:

Attachments

Response From: _____	To: _____	Date Rec'd: _____	Date Ret'd: _____
----------------------	-----------	-------------------	-------------------

Signed by: _____	Date: _____
------------------	-------------

Copies:  Owner     Consultants     \_\_\_\_\_     \_\_\_\_\_     \_\_\_\_\_     \_\_\_\_\_     File

## SECTION 017310 - CUTTING AND PATCHING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes procedural requirements for cutting and patching where existing systems require repair.
- B. Related Sections include the following:
  - 1. Division 2 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.

#### 1.3 DEFINITIONS

- A. Cutting: Removal of existing construction necessary to permit installation or performance of other Work.
- B. Patching: Fitting and repair work required to restore surfaces to original conditions after installation of other Work.

#### 1.4 SUBMITTALS

- A. Cutting and Patching Proposal: Submit a proposal describing procedures at least 5 days before the time cutting and patching will be performed, requesting approval to proceed. Include the following information:
  - 1. Extent: Describe cutting and patching, show how they will be performed, and indicate why they cannot be avoided.
  - 2. Changes to Existing Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building's appearance and other significant visual elements.
  - 3. Products: List products to be used and firms or entities that will perform the Work.
  - 4. Dates: Indicate when cutting and patching will be performed.
  - 5. Utilities: List utilities that cutting and patching procedures will disturb or affect. List utilities that will be relocated and those that will be temporarily out of service. Indicate how long service will be disrupted. Coordinate with Owner's requirements to avoid shut-down of any portion of the facility
  - 6. Architect's Approval: Obtain approval of cutting and patching proposal before cutting and patching. Approval does not waive right to later require removal and replacement of unsatisfactory work.

#### 1.5 QUALITY ASSURANCE

- A. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
- B. Miscellaneous Elements: Do not cut and patch the following elements or related components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
  - 1. Paving.
  - 2. Track Surfacing.
- C. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- D. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

## 1.6 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.
- B. The existing track requires the existing warranty to continue by providing and installing original manufacturer's approved materials and details as required by this warranty. Coordinate with Owner and Architect regarding information available on existing track system.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections of these Specifications.
- B. Existing Materials: Use materials identical to existing materials. For exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
  - 1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
  - 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut where required.
- B. Protection: Protect existing construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

### 3.3 PERFORMANCE

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
  - 1. Cut existing construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Cutting: Cut existing construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
  - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use. Over-cutting of concrete for new openings is not permitted; hand-cut corners as required.
  - 2. Existing Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
  - 3. Paving: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
  - 4. Excavating and Backfilling: Comply with requirements in applicable Division 2 Sections where required by cutting and patching operations.
  - 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
  - 6. Proceed with patching after construction operations requiring cutting are complete.
- C. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are invisible. Provide ma-

materials and comply with installation requirements specified in other Sections of these Specifications.

1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.

END OF SECTION 017310

## SECTION 017700 - CLOSEOUT PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
  - 1. Inspection procedures.
  - 2. Project Record Documents.
  - 3. Final cleaning.
- B. Related Sections include the following:
  - 1. Division 1 Section "Payment Procedures" for requirements for Applications for Payment for Substantial and Final Completion.
  - 2. Division 1 Section "Execution Requirements" for progress cleaning of Project site.
  - 3. Division 1 Section "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
  - 4. Division 1 Section "Operation and Maintenance Data" for operation and maintenance manual requirements.
  - 5. Division 2 Sections for specific closeout and special cleaning requirements for products of those Sections.

#### 1.3 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.
  - 1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
  - 2. Advise Owner of pending insurance changeover requirements.
  - 3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  - 4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  - 5. Prepare and submit Project Record Documents, operation and maintenance manuals, and similar final record information.
  - 6. Submit test records.
  - 7. Terminate and remove temporary facilities from Project site, along with construction tools, and similar elements.
  - 8. Complete final cleaning requirements, including touchup painting.

9. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

2. Results of completed inspection will form the basis of requirements for Final Completion.

#### 1.4 FINAL COMPLETION

A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:

1. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."

2. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.

3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.

4. Instruct Owner's personnel in operation, adjustment, and maintenance of, equipment, and systems.

B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

#### 1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

A. Preparation: Submit **three** copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

1. Organize list of areas in sequential order,

2. Include the following information at the top of each page:

a. Project name.

b. Date.

c. Name of Architect

d. Name of Contractor.

e. Page number.

## 1.6 PROJECT RECORD DOCUMENTS

- A. General: Do not use Project Record Documents for construction purposes. Protect Project Record Documents from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.
- B. Record Drawings: Maintain and submit one set of blue- or black-line white prints of Contract Drawings and Shop Drawings.
  - 1. Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
    - a. Give particular attention to information on concealed elements that cannot be readily identified and recorded later.
    - b. Accurately record information in an understandable drawing technique.
    - c. Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
    - d. Mark Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. Where Shop Drawings are marked, show cross-reference on Contract Drawings.
  - 2. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at the same location.
  - 3. Mark important additional information that was either shown schematically or omitted from original Drawings.
  - 4. Note Construction Change Directive numbers, Change Order numbers, alternate numbers, and similar identification where applicable.
  - 5. Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location. Organize into manageable sets; bind each set with durable paper cover sheets. Include identification on cover sheets.
- C. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications. Mark copy to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
  - 3. Note related Change Orders, Record Drawings and Product Data, where applicable.
- D. Record Product Data: Submit one copy of each Product Data submittal. Mark one set to indicate the actual product installation where installation varies substantially from that indicated in Product Data.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
  - 3. Note related Change Orders, Record Drawings, and Record Specifications, where applicable.

- E. Miscellaneous Record Submittals: Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

## 1.7 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
  - 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive **8-1/2-by-11-inch (115-by-280-mm)** paper.
  - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
  - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

## PART 3 - EXECUTION

### 3.1 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations
- B. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
  - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
  - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.

- c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
  - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
  - e. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
- C. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.

END OF SECTION 017700

## **SECTION 310700 GENERAL SITE CONSTRUCTION REQUIREMENTS**

### **PART 1 GENERAL**

#### **1.1 SUMMARY**

- A. Includes But Not Limited to
  - 1. General procedures and requirements for Site Work.

### **PART 2 PRODUCTS - Not Used**

### **PART 3 EXECUTION**

#### **3.1 PREPARATION**

- A. Site Verification Of Conditions
  - 1. 48 hours minimum prior to performing any work on site, contact Blue Stakes to arrange for utility location services.
  - 2. Perform minor, investigative excavations to verify location of various existing underground facilities at sufficient locations to assure that no conflict with the proposed work exists and sufficient clearance is available to avoid damage to existing facilities.
  - 3. Perform investigative excavating 5 days minimum in advance of performing any excavation or underground work.
  - 4. Upon discovery of conflicts or problems with existing facilities, notify Architect by phone or fax within 24 hours. Follow telephone or fax notification with letter and diagrams indicating conflict or problem and sufficient measurements and details to evaluate problem.
  - 5. Notify Owner of utilities a minimum of 48 hours prior to an work taking place.

#### **3.2 PREPARATION**

- A. Protection
  - 1. Spillage -
    - a. Avoid spillage by covering and securing loads when hauling on or adjacent to public streets or highways.
    - b. Remove spillage and sweep, wash, or otherwise clean project, streets, and highways.
  - 2. Dust Control -
    - a. Take precautions necessary to prevent dust nuisance, both on-site and adjacent to public and private properties.
    - b. Correct or repair damage caused by dust.
  - 3. Erosion Control -
    - a. Take precautions necessary to prevent erosion and transportation of soil downstream, to adjacent properties, and into on-site or off-site drainage systems.
    - b. Develop, install, and maintain an erosion control plan if required by law.

- c. Repair and correct damage caused by erosion.
  - 4. Existing Plants And Features - Do not damage tops, trunks, and roots of existing trees and shrubs on site which are intended to remain. Do not use heavy equipment within branch spread. Interfering branches may be removed only with permission of Architect. Do not damage other plants and features which are to remain.
  - 5. Protect site from fire caused by welding, cutting, smoking, or other sources of ignition.
- B. If specified precautions are not taken or corrections and repairs made promptly, Owner may take such steps as may be deemed necessary and deduct costs of such from monies due to Contractor. Such action or lack of action on Owner's part does not relieve Contractor from responsibility for proper protection of the Work.
- C. Fees
- 1. Contractor shall be responsible for all off site street cut fees, encroachment permit fees, and bonding associated with the construction of the proposed facility.

### 3.3 REPAIR / RESTORATION

- A. Adjust existing covers, boxes, and vaults to grade.
- B. Replace broken or damaged covers, boxes, and vaults.
- C. Independently confirm size, location, and number of covers, boxes, and vaults which require adjustment.

### 3.4 FIELD QUALITY CONTROL

- A. Notify Architect 48 hours prior to performing excavation or fill work.
- B. If work has been interrupted by weather, scheduling, or other reason, notify Architect 24 hours minimum prior to intended resumption of grading or compacting.
- C. Owner reserves right to require additional testing to re-affirm suitability of completed work including compacted soils which have been exposed to adverse weather conditions.

END OF SECTION 310700

## **SECTION 311000 - SITE CLEARING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Removing curb wall
  - 2. Removing old rubberized track surface
  - 3. Temporary erosion and sedimentation control measures.
- B. Related Sections include the following:
  - 1. Division 01 Section "Temporary Facilities and Controls" for temporary utilities, temporary construction and support facilities, temporary security, protection facilities, and temporary erosion and sedimentation control procedures.
  - 2. Division 02 Section "Structure Demolition" for demolition of buildings, structures, and site improvements.
  - 3. Division 31 Section "Earth Moving" for soil materials, excavating, backfilling, and site grading.

#### **1.3 DEFINITIONS**

- A. Track Surface: Rubberize coating on asphalt track.

#### **1.4 SUBMITTALS**

- A. Photographs or videotape, sufficiently detailed, of existing conditions of trees and plantings, adjoining construction, and site improvements that might be misconstrued as damage caused by site clearing.
- B. Record drawings, according to Division 01 Section "Project Record Documents," identifying and accurately locating capped utilities and other subsurface structural, electrical, and mechanical conditions.

## 1.5 QUALITY ASSURANCE

- A. Pre-installation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."

## 1.6 PROJECT CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.
  - 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
  - 2. Provide alternate routes around closed or obstructed traffic ways if required by authorities having jurisdiction.
- B. Improvements on Adjoining Property: Authority for performing site clearing indicated on property adjoining Owner's property will be obtained by Owner before award of Contract.
  - 1. Do not proceed with work on adjoining property until directed by Architect.
- C. Salvable Improvements: Carefully remove items indicated to be salvaged and store on Owner's premises where indicated.
- D. Utility Locator Service: Notify utility locator service for area where Project is located before site clearing.
- E. Do not commence site clearing operations until temporary erosion and sedimentation control measures are in place.

## PART 2 - PRODUCTS

### 2.1 SOIL MATERIALS

- A. Satisfactory Soil Materials: Requirements for satisfactory soil materials are specified in Division 31 Section "Earth Moving."
  - 1. Obtain approved borrow soil materials off-site when satisfactory soil materials are not available on-site.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Protect and maintain benchmarks and survey control points from disturbance during construction.

- B. Protect existing site improvements to remain from damage during construction.
  - 1. Restore damaged improvements to their original condition, as acceptable to Owner.

### 3.2 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- A. Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction, sediment and erosion control Drawings, a sediment and erosion control plan, specific to the site, that complies with EPA 832/R-92-005 or requirements of authorities having jurisdiction, whichever is more stringent.
- B. Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- C. Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

### 3.3 UTILITIES

- A. Owner will arrange for disconnecting and sealing indicated utilities that serve existing structures before site clearing, when requested by Contractor.
  - 1. Verify that utilities have been disconnected and capped before proceeding with site clearing.
- B. Locate, identify, disconnect, and seal or cap off utilities indicated to be removed.
  - 1. Arrange with utility companies to shut off indicated utilities.
  - 2. Owner will arrange to shut off indicated utilities when requested by Contractor.
- C. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
  - 1. Notify Architect not less than two days in advance of proposed utility interruptions.
  - 2. Do not proceed with utility interruptions without Architect's written permission.
- D. Excavate for and remove underground utilities indicated to be removed.
- E. Removal of underground utilities is included in Division 21, Division 22, Division 26, Division 27, and Division 28 Sections covering site utilities.

### 3.4 SITE IMPROVEMENTS

- A. Remove existing above-grade and below-grade improvements as indicated and as necessary to facilitate new construction. Refer to project plans for improvements to be abandoned in place.
- B. Remove slabs, paving, curbs, gutters, and aggregate base as indicated.
  - 1. Unless existing full-depth joints coincide with line of demolition, neatly saw-cut length of existing pavement to remain before removing existing pavement. Saw-cut faces vertically.
  - 2. Paint cut ends of steel reinforcement in concrete to remain to prevent corrosion.

### 3.5 DISPOSAL

- A. Disposal: Remove surplus soil material, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.
  - 1. Separate recyclable materials produced during site clearing from other non-recyclable materials. Store or stockpile without intermixing with other materials and transport them to recycling facilities.

END OF SECTION 311000

## **SECTION 312000 - EARTH MOVING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Refer to the Geotechnical Report titled "Soil, Groundwater, Track Pavement and East Bleacher Study, Stewart Stadium Field Renovation - Northwest Portion of Weber State University Campus" Ogden, Utah – DFCM Project Number: 10280810, Dated January 26, 2011, and "Supplemental Core Samples – Track at Stewart Stadium, Weber State University" dated January 20, 2011, by Gordon Spilker Huber Geotechnical Consultants, Inc., Job No. 012806810, for additional grading requirements.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Preparing sub-grades for pavements and lawns .
  - 2. Excavating and backfilling for structures.
  - 3. Subbase and base course for asphalt paving.
  - 4. Excavating and backfilling for utility trenches.
  - 5. Excavating and backfilling trenches for buried mechanical and electrical utilities and pits for buried utility structures.
- B. Related Sections include the following:
  - 1. Division 01 Section Construction Progress Documentation and Photographic Documentation for recording pre-excitation and earthwork progress.
  - 2. Division 01 Section "Temporary Facilities and Controls" for temporary controls, utilities, and support facilities.
  - 3. Divisions 26 and 27 Sections for installing underground electrical utilities and buried electrical structures.
  - 4. Division 31 Section "Site Clearing" for temporary erosion and sedimentation control measures, site stripping, and removal of above-grade and below-grade improvements and utilities.
  - 5. Division 32 Section "Turf and Grasses" for finish grading, including preparing and placing topsoil and planting soil for lawns.

#### **1.3 UNIT PRICES**

- A. Unit prices for earthwork are included in Division 01 Section "Unit Prices."
- B. Quantity allowances for earthwork are included in Division 01 Section "Allowances."

#### 1.4 DEFINITIONS

- A. Backfill: Soil material or controlled low-strength material used to fill an excavation.
  - 1. Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.
  - 2. Final Backfill: Backfill placed over initial backfill to fill a trench.
- B. Base Course: Course placed between the subbase course and hot-mix asphalt paving.
- C. Bedding Course: Course placed over the excavated subgrade in a trench before laying pipe.
- D. Borrow Soil: Satisfactory soil imported from off-site for use as fill or backfill.
- E. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.
  - 1. Authorized Additional Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions as directed by Architect. Authorized additional excavation and replacement material will be paid for according to Contract provisions for unit prices and changes in the work.
  - 2. Bulk Excavation: Excavation more than 10-feet in width and more than 30-feet in length.
  - 3. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions without direction by Architect. Unauthorized excavation, as well as remedial work directed by Architect, shall be without additional compensation.
- F. Fill: Soil materials used to raise existing grades.
- G. Structures: Curbs, electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
- H. Subbase Course: Course placed between the subgrade and base course for hot-mix asphalt pavement, or course placed between the subgrade and a cement concrete pavement or a cement concrete or hot-mix asphalt walk.
- I. Subgrade: Surface or elevation remaining after completing excavation, or top surface of a fill or backfill immediately below subbase, drainage fill, or topsoil materials.
- J. Utilities: On-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.

#### 1.5 SUBMITTALS

- A. Product Data: For the following:
  - 1. Each type of plastic warning tape.
  - 2. Geotextile.
  - 3. Controlled low-strength material, including design mixture.

- B. Samples: 12-by-12-inch Sample of sub-drainage and other geotextiles used.
- C. Material Test Reports: From a qualified testing agency indicating and interpreting test results for compliance of the following with requirements indicated:
  - 1. Classification according to ASTM D 2487 of each on-site and borrow soil material proposed for fill and backfill.
  - 2. Laboratory compaction curve according to ASTM D698 or ASTM D1557 for each on-site and borrow soil material proposed for fill and backfill.
- D. Blasting Plan: NOT ALLOWED
- E. Pre-excavation Photographs or Videotape: Show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by earthwork operations. Submit before earthwork begins.

#### 1.6 QUALITY ASSURANCE

- A. Geotechnical Testing Agency Qualifications: An independent testing agency qualified according to ASTM E 329 to conduct soil materials and rock-definition testing, as documented according to ASTM D 3740 and ASTM E 548.
- B. Pre-excavation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."

#### 1.7 PROJECT CONDITIONS

- A. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted in writing by Architect and then only after arranging to provide temporary utility services according to requirements indicated.
  - 1. Notify Architect not less than two days in advance of proposed utility interruptions.
  - 2. Do not proceed with utility interruptions without Architect's written permission.
  - 3. Contact utility-locator service for area where Project is located before excavating.
- B. Demolish and completely remove from site existing underground utilities indicated to be removed. Coordinate with utility companies to shut off services if lines are active.

### PART 2 - PRODUCTS

#### 2.1 SOIL MATERIALS

- A. General: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.

- B. Satisfactory Soils: ASTM D 2487 Soil Classification Groups GW, GP, GM, SW, SP, and SM or AASHTO M 145 Soil Classification Groups A-1, A-2-4, A-2-5, and A-3, or a combination of these groups; free of rock or gravel larger than 3-inches in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter. Native rock crushed to meet the above requirements and free from significant porosity may also be used as satisfactory soils.
- C. Unsatisfactory Soils: Soil Classification Groups GC, SC, CL, ML, OL, CH, MH, OH, and PT according to ASTM D 2487 or A-2-6, A-2-7, A-4, A-5, A-6, and A-7 according to AASHTO M 145, or a combination of these groups.
  - 1. Unsatisfactory soils also include satisfactory soils not maintained within 2 percent of optimum moisture content at time of compaction.
- D. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch sieve and not more than 12 percent passing a No. 200 sieve.
- E. Base Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 95 percent passing a 1-inch sieve and not more than 8 percent passing a No. 200 sieve. Sand Equivalent of no less than 35.
- F. Engineered Fill: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch sieve and not more than 8 percent passing a No. 200 sieve.
- G. Bedding Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; except with 100 percent passing a 3/4-inch sieve and not more than 8 percent passing a No. 200 sieve.
- H. Drainage Course: Narrowly graded mixture of washed or crushed stone, or crushed or uncrushed gravel; ASTM D 448; coarse-aggregate grading Size 57; with 100 percent passing a 1-1/2-inch sieve and 0 to 5 percent passing a No. 8 sieve.
- I. Filter Material: Narrowly graded mixture of natural or crushed gravel, or crushed stone and natural sand; ASTM D 448; coarse-aggregate grading Size 67; with 100 percent passing a 1-inch sieve and 0 to 5 percent passing a No. 4 sieve.
- J. Sand: ASTM C 33; fine aggregate, natural, or manufactured sand.
- K. Impervious Fill: Clayey gravel and sand mixture capable of compacting to a dense state.

## 2.2 GEOTEXTILES

- A. Subsurface Drainage Geotextile: Non-woven needle-punched geotextile, manufactured for subsurface drainage applications, made from polyolefins or polyesters; with elongation greater than 50 percent; complying with AASHTO M 288 and the following, measured per test methods referenced:
  - 1. Survivability: Class 2; AASHTO M 288.

2. Grab Tensile Strength: 157 lbf; ASTM D 4632.
3. Sewn Seam Strength: 142 lbf; ASTM D 4632.
4. Tear Strength: 56 lbf; ASTM D 4533.
5. Puncture Strength: 56 lbf; ASTM D 4833.
6. Apparent Opening Size: **No. 60** sieve, maximum; ASTM D 4751.
7. Permittivity: 0.2 per second, minimum; ASTM D 4491.
8. UV Stability: 50 percent after 500 hours' exposure; ASTM D 4355.

B. Separation Geotextile: Woven geotextile fabric, manufactured for separation applications, made from polyolefins or polyesters; with elongation less than 50 percent; complying with AASHTO M 288 and the following, measured per test methods referenced:

1. Survivability: Class 2; AASHTO M 288.
2. Grab Tensile Strength: 247 lbf; ASTM D 4632.
3. Sewn Seam Strength: 222 lbf; ASTM D 4632.
4. Tear Strength: 90 lbf; ASTM D 4533.
5. Puncture Strength: 90 lbf; ASTM D 4833.
6. Apparent Opening Size: No. 60 sieve, maximum; ASTM D 4751.
7. Permittivity: 0.02 per second, minimum; ASTM D 4491.
8. UV Stability: 50 percent after 500 hours' exposure; ASTM D 4355.

## 2.3 CONTROLLED LOW-STRENGTH MATERIAL

A. Controlled Low-Strength Material: Low-density, self-compacting, flowable concrete material as follows:

1. Portland Cement: ASTM C 150, Type II.
2. Fly Ash: ASTM C 618, Class C or F.
3. Normal-Weight Aggregate: ASTM C 33, 3/4-inch to 3/8-inch nominal maximum aggregate size.
4. Foaming Agent: ASTM C 869.
5. Water: ASTM C 94/C 94M.
6. Air-Entraining Admixture: ASTM C 260.

B. Produce low-density, controlled low-strength material with the following physical properties:

1. As-Cast Unit Weight: 30 to 36 lb/cu. ft. at point of placement, when tested according to ASTM C 138/C 138M.
2. Compressive Strength: 80 psi, when tested according to ASTM C 495.

## 2.4 ACCESSORIES

A. Warning Tape: Acid- and alkali-resistant polyethylene film warning tape manufactured for marking and identifying underground utilities, 6 inches wide and 4 mils thick, continuously inscribed with a description of the utility; colored as follows:

B. Detectable Warning Tape: Acid- and alkali-resistant polyethylene film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches wide

and 4 mils thick, continuously inscribed with a description of the utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 30 inches deep; colored as follows when required by utility purveyor:

1. Red: Electric.
2. Yellow: Gas, oil, steam, and dangerous materials.
3. Orange: Telephone and other communications.
4. Blue: Water systems.
5. Green: Sewer systems.

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earthwork operations.
- B. Preparation of subgrade for earthwork operations including removal of debris, obstructions, and deleterious materials from ground surface is specified in Division 31 Section "Site Clearing."
- C. Protect and maintain erosion and sedimentation controls, which are specified in Division 31 Section "Site Clearing," during earthwork operations.
- D. Provide protective insulating materials to protect subgrades and foundation soils against freezing temperatures or frost.

#### 3.2 DEWATERING

- A. Prevent surface water and ground water from entering excavations, from ponding on prepared subgrades, and from flooding Project site and surrounding area.
- B. Protect subgrades from softening, undermining, washout, and damage by rain or water accumulation.
  1. Reroute surface water runoff away from excavated areas. Do not allow water to accumulate in excavations. Do not use excavated trenches as temporary drainage ditches.
  2. Install a dewatering system to keep subgrades dry and convey ground water away from excavations. Maintain until dewatering is no longer required.

#### 3.3 EXPLOSIVES

1. Explosives: Not Permitted

### 3.4 EXCAVATION, GENERAL

- A. Unclassified Excavation: Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in the Contract Sum or the Contract Time will be authorized for rock excavation or removal of obstructions.
1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.
  2. Remove rock to lines and grades indicated to permit installation of permanent construction without exceeding the following dimensions:
    - a. 24 inches outside of concrete forms other than at footings.
    - b. 12 inches outside of concrete forms at footings.
    - c. 6 inches outside of minimum required dimensions of concrete cast against grade.
    - d. Outside dimensions of concrete walls indicated to be cast against rock without forms or exterior waterproofing treatments.
    - e. 6 inches beneath bottom of concrete slabs on grade.
    - f. 6 inches beneath pipe in trenches, and the greater of 24 inches wider than pipe or 42 inches wide.

### 3.5 EXCAVATION FOR STRUCTURES

- A. Excavate to indicated elevations and dimensions within a tolerance of plus or minus **1 inch (25 mm)**. If applicable, extend excavations a sufficient distance from structures for placing and removing concrete formwork, for installing services and other construction, and for inspections.
1. Excavations for Footings and Foundations: Do not disturb bottom of excavation. Excavate by hand to final grade just before placing concrete reinforcement. Trim bottoms to required lines and grades to leave solid base to receive other work.
  2. Pile Foundations: Stop excavations 6 to 12 inches above bottom of pile cap before piles are placed. After piles have been driven, remove loose and displaced material. Excavate to final grade, leaving solid base to receive concrete pile caps.
  3. Excavation for Underground Tanks, Basins, and Mechanical or Electrical Utility Structures: Excavate to elevations and dimensions indicated within a tolerance of plus or minus 1 inch. Do not disturb bottom of excavations intended as bearing surfaces.

### 3.6 EXCAVATION FOR WALKS AND PAVEMENTS

- A. Excavate surfaces under walks and pavements to indicated lines, cross sections, elevations, and subgrades.

### 3.7 EXCAVATION FOR UTILITY TRENCHES

- A. Excavate trenches to indicated gradients, lines, depths, and elevations.

1. Beyond building perimeter, excavate trenches to allow installation of top of pipe below frost line.
- B. Excavate trenches to uniform widths to provide the following clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches higher than top of pipe or conduit, unless otherwise indicated.
1. Clearance: 12 inches each side of pipe or conduit.
- C. Trench Bottoms: Excavate and shape trench bottoms to provide uniform bearing and support of pipes and conduit. Shape subgrade to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits. Remove projecting stones and sharp objects along trench subgrade.
1. For pipes and conduit less than 6 inches in nominal diameter and flat-bottomed, multiple-duct conduit units, hand-excavate trench bottoms and support pipe and conduit on an undisturbed subgrade.
  2. For pipes and conduit 6 inches or larger in nominal diameter, shape bottom of trench to support bottom 90 degrees of pipe circumference. Fill depressions with tamped sand backfill.
  3. Excavate trenches 6 inches deeper than elevation required in rock or other unyielding bearing material to allow for bedding course.

### 3.8 SUBGRADE INSPECTION

- A. Notify Architect when excavations have reached required subgrade.
- B. If Architect determines that unsatisfactory soil is present, continue excavation and replace with compacted backfill or fill material as directed.
- C. Proof-roll subgrade below the building slabs and pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
1. Completely proof-roll subgrade in one direction, repeating proof-rolling in direction perpendicular to first direction. Limit vehicle speed to 3 mph.
  2. Proof-roll with a loaded 10-wheel, tandem-axle dump truck weighing not less than 15 tons or vehicle with similar unit axel weight.
  3. Excavate soft spots, unsatisfactory soils, and areas of excessive pumping or rutting, as determined by Architect, and replace with compacted backfill or fill as directed.
- D. Authorized additional excavation and replacement material will be paid for according to Contract provisions for unit prices and changes in the Work.
- E. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by Architect, without additional compensation.

### 3.9 UNAUTHORIZED EXCAVATION

- A. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill, with 28-day compressive strength of 2500 psi, may be used when approved by Architect.
  - 1. Fill unauthorized excavations under other construction or utility pipe as directed by Architect.

### 3.10 STORAGE OF SOIL MATERIALS

- A. Stockpile borrow soil materials and excavated satisfactory soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
  - 1. Stockpile soil materials away from edge of excavations.

### 3.11 BACKFILL

- A. Place and compact backfill in excavations promptly, but not before completing the following:
  - 1. Construction below finish grade including, where applicable, subdrainage, dampproofing, waterproofing, and perimeter insulation.
  - 2. Surveying locations of underground utilities for Record Documents.
  - 3. Testing and inspecting underground utilities.
  - 4. Removing concrete formwork.
  - 5. Removing trash and debris.
  - 6. Removing temporary shoring and bracing, and sheeting.
  - 7. Installing permanent or temporary horizontal bracing on horizontally supported walls.
- B. Place backfill on subgrades free of mud, frost, snow, or ice.

### 3.12 UTILITY TRENCH BACKFILL

- A. Place backfill on subgrades free of mud, frost, snow, or ice.
- B. Place and compact bedding course on trench bottoms and where indicated. Shape bedding course to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits.
- C. Backfill trenches excavated under footings and within 18 inches of bottom of footings with satisfactory soil; fill with concrete to elevation of bottom of footings. Concrete is specified in Division 03 Section "Cast-in-Place Concrete."
- D. Provide 4-inch- thick, concrete-base slab support for piping or conduit less than 12 inches below surface of roadways. After installing and testing, completely encase piping or conduit in a minimum of 4 inches of concrete before backfilling or placing roadway subbase.

- E. Place and compact initial backfill of subbase material or satisfactory soil, free of particles larger than 1 inch in any dimension, to a height of 12 inches over the utility pipe or conduit.
  - 1. Carefully compact initial backfill under pipe haunches and compact evenly up on both sides and along the full length of utility piping or conduit to avoid damage or displacement of piping or conduit. Coordinate backfilling with utilities testing.
- F. Controlled Low-Strength Material: Place initial backfill of controlled low-strength material to a height of 12 inches over the utility pipe or conduit.
- G. Backfill voids with satisfactory soil while installing and removing shoring and bracing.
- H. Place and compact final backfill of satisfactory soil to final subgrade elevation.
- I. Controlled Low-Strength Material: Place final backfill of controlled low-strength material to final subgrade elevation.
- J. Install warning tape directly above utilities, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

### 3.13 SOIL FILL

- A. Plow, scarify, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so fill material will bond with existing material.
- B. Place and compact fill material in layers to required elevations as follows:
  - 1. Under grass and planted areas, use satisfactory soil material.
  - 2. Under walks and pavements, use satisfactory soil material.
  - 3. Under steps and ramps, use engineered fill.
  - 4. Under footings and foundations, use engineered fill.
- C. Place soil fill on subgrades free of mud, frost, snow, or ice.

### 3.14 SOIL MOISTURE CONTROL

- A. Uniformly moisten or aerate subgrade and each subsequent fill or backfill soil layer before compaction to within 2 percent of optimum moisture content.
  - 1. Do not place backfill or fill soil material on surfaces that are muddy, frozen, or contain frost or ice.
  - 2. Remove and replace, or scarify and air dry otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.

### 3.15 COMPACTION OF SOIL BACKFILLS AND FILLS

- A. Place backfill and fill soil materials in layers not more than 12-inches in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers. Reduce loose depths as needed to achieve required compactions.
- B. Place backfill and fill soil materials evenly on all sides of structures to required elevations, and uniformly along the full length of each structure.
- C. Compact soil materials to not less than the following percentages of maximum dry unit weight according to ASTM D 698 or ASTM D 1557:
  - 1. Under structures, building slabs, steps, and pavements, scarify and recompact top 12 inches of existing subgrade and each layer of backfill or fill soil material at 95 percent.
  - 2. Under walkways, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 95 percent.
  - 3. Under lawn or unpaved areas, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 85 percent.
  - 4. For utility trenches, compact each layer of initial and final backfill soil material at 85 percent if in landscaping areas or 95 percent if under structures, pavements, or walks.

### 3.16 GRADING

- A. General: Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.
  - 1. Provide a smooth transition between adjacent existing grades and new grades.
  - 2. Cut out soft spots, fill low spots, and trim high spots to comply with required surface tolerances.
- B. Site Grading: Slope grades to direct water away from bleachers and to prevent ponding. Finish subgrades to required elevations within the following tolerances:
  - 1. Lawn or Unpaved Areas: Plus or minus 1 inch.
  - 2. Walks: Plus or minus 1/2 inch
  - 3. Pavements: Plus or minus 1/4 inch
- C. Grading inside Building Lines: Finish subgrade to a tolerance of 1/4 inch when tested with a 10-foot straightedge.

### 3.17 SUBBASE AND BASE COURSES

- A. Place subbase and base course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place subbase and base course under pavements and walks as follows:

1. Install separation geotextile on prepared subgrade according to manufacturer's written instructions, overlapping sides and ends where called for on details and on plans.
  2. Place base course material over subbase course under hot-mix asphalt pavement.
  3. Shape subbase and base course to required crown elevations and cross-slope grades.
  4. Place subbase and base course 6 inches or less in compacted thickness in a single layer.
  5. Place subbase and base course that exceeds 6 inches in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches thick or less than 3 inches thick.
  6. Compact subbase and base course at optimum moisture content to required grades, lines, cross sections, and thickness to not less than 95 percent of maximum dry unit weight according to ASTM D 698 or ASTM D 1557.
- C. Pavement Shoulders: Place shoulders along edges of subbase and base course to prevent lateral movement. Construct shoulders, at least 12 inches wide, of satisfactory soil materials and compact simultaneously with each subbase and base layer to not less than 95 percent of maximum dry unit weight according to ASTM D 698 or ASTM D 1557 where called for on project plans.

### 3.18 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified independent geotechnical engineering testing agency to perform field quality-control testing.
- B. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earthwork only after test results for previously completed work comply with requirements.
- C. Footing Subgrade: At footing subgrades, at least one test of each soil stratum will be performed to verify design bearing capacities. Subsequent verification and approval of other footing subgrades may be based on a visual comparison of subgrade with tested subgrade when approved by Architect.
- D. Testing agency will test compaction of soils in place according to ASTM D 1556, ASTM D 2167, ASTM D 2922, and ASTM D 2937, as applicable. Tests will be performed at the following locations and frequencies:
1. Paved Areas: At subgrade and at each compacted fill and backfill layer, at least 1 test for every 2000 sq. ft. or less of paved area or building slab, but in no case fewer than 3 tests.
  2. Foundation Wall Backfill: At each compacted backfill layer, at least 1 test for each 100 feet or less of wall length, but no fewer than 2 tests.
  3. Trench Backfill: At each compacted initial and final backfill layer, at least 1 test for each 150 feet or less of trench length, but no fewer than 2 tests.
- E. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil to depth required; recompact and retest until specified compaction is obtained.

3.19 PROTECTION

- A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.
- B. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.
  - 1. Scarify or remove and replace soil material to depth as directed by Architect; reshape and recompact.
- C. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.
  - 1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.20 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Disposal: Remove surplus satisfactory soil and waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Owner's property.
- B. Disposal: Transport surplus satisfactory soil to designated storage areas on Owner's property. Stockpile or spread soil as directed by Architect.
  - 1. Remove waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Owner's property.

END OF SECTION 312000

THIS PAGE LEFT INTENTIONALLY BLANK

## **SECTION 321216 - ASPHALT PAVING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:

1. Cold milling of existing hot-mix asphalt pavement.
2. Hot-mix asphalt patching.
3. Hot-mix asphalt paving.
4. Hot-mix asphalt paving overlay.
5. Asphalt surface treatments.
6. Pavement-marking paint.
7. Traffic-calming devices.

- B. Related Sections:

1. Division 02 Section "Structure Demolition" for demolition, removal, and recycling of existing asphalt pavements, and for geotextiles that are not embedded within courses of asphalt paving.
2. Division 31 Section "Earth Moving" for aggregate subbase and base courses and for aggregate pavement shoulders.
3. Division 32 Sections for other paving installed as part of crosswalks in asphalt pavement areas.
4. Division 32 Section "Concrete Paving Joint Sealants" for joint sealants and fillers at paving terminations.
5. Division 32 Section "Unit Paving" for bituminous setting bed for pavers.

#### **1.3 UNIT PRICES**

- A. Work of this Section is affected by unit prices and as defined in Division 1.

#### **1.4 DEFINITION**

- A. Hot-Mix Asphalt Paving Terminology: Refer to ASTM D 8 for definitions of terms.

## 1.5 SUBMITTALS

- A. Product Data: For each type of product indicated. Include technical data and tested physical and performance properties.
  - 1. Job-Mix Designs: Certification, by authorities having jurisdiction, of approval of each job mix proposed for the Work.
  - 2. Job-Mix Designs: For each job mix proposed for the Work.
- B. Shop Drawings: Indicate pavement markings, lane separations, and defined parking spaces. Indicate, with international symbol of accessibility, spaces allocated for people with disabilities.
- C. Samples: For each paving fabric, 12 by 12 inches minimum if used.
- D. Samples for Verification: For the following products, in manufacturer's standard sizes unless otherwise indicated:
  - 1. Each paving fabric, 12 by 12 inches minimum.
  - 2. Each type and color of preformed traffic-calming device.
  - 3. Each pattern and color of imprinted asphalt and precut marking material.
- E. Qualification Data: For qualified manufacturer and Installer.
- F. Material Certificates: For each paving material, from manufacturer.
- G. Material Test Reports: For each paving material.
- H. Fire Marshal Approval: For the striping plan as it relates to fire lanes and the marking thereof.

## 1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Provide copy of manufacturer's experience for verification of qualifications.
- B. Installer Qualifications: Imprinted-asphalt manufacturer's authorized installer who is trained and approved for installation of imprinted asphalt required for this Project.
- C. Testing Agency Qualifications: Qualified according to ASTM D 3666 for testing indicated.
- D. Regulatory Requirements: Comply with materials, workmanship, and other applicable requirements of city and DOT for asphalt paving work.
  - 1. Measurement and payment provisions and safety program submittals included in standard specifications do not apply to this Section.
- E. Preinstallation Conference: Conduct conference at Project site
  - 1. Review methods and procedures related to hot-mix asphalt paving including, but not limited to, the following:

- a. Review proposed sources of paving materials, including capabilities and location of plant that will manufacture hot-mix asphalt.
- b. Review condition of subgrade and preparatory work.
- c. Review requirements for protecting paving work, including restriction of traffic during installation period and for remainder of construction period.
- d. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pavement-marking materials to Project site in original packages with seals unbroken and bearing manufacturer's labels containing brand name and type of material, date of manufacture, and directions for storage.
- B. Store pavement-marking materials in a clean, dry, protected location within temperature range required by manufacturer. Protect stored materials from direct sunlight.

#### 1.8 PROJECT CONDITIONS

- A. Environmental Limitations: Do not apply asphalt materials if subgrade is wet or excessively damp, if rain is imminent or expected before time required for adequate cure, or if the following conditions are not met:
  1. Prime Coat: Minimum surface temperature of 60 deg F. Not used if paving takes place within 48 hours of final grading and final compaction of road base.
  2. Tack Coat: Minimum surface temperature of 60 deg F.
  3. Slurry Coat: Comply with weather limitations in ASTM D 3910.
  4. Asphalt Base Course: Minimum surface temperature of 40 deg F and rising at time of placement.
  5. Asphalt Surface Course: Minimum surface temperature of 60 deg F at time of placement.
- B. Pavement-Marking Paint: Proceed with pavement marking only on clean, dry surfaces and at a minimum ambient or surface temperature of 40 deg F for oil-based materials 55 deg F for water-based materials, and not exceeding 95 deg F.

### PART 2 - PRODUCTS

#### 2.1 AGGREGATES

- A. General: Use materials and gradations that have performed satisfactorily in previous installations.
- B. Coarse Aggregate: ASTM D 692, sound; angular crushed stone, crushed gravel, or cured, crushed blast-furnace slag.

- C. Fine Aggregate: ASTM D 1073 or AASHTO M 29, sharp-edged natural sand or sand prepared from stone, gravel, cured blast-furnace slag, or combinations thereof.
  - 1. For hot-mix asphalt, limit natural sand to a maximum of 20 percent by weight of the total aggregate mass.
- D. Mineral Filler: ASTM D 242 or AASHTO M 17, rock or slag dust, hydraulic cement, or other inert material.

## 2.2 ASPHALT MATERIALS

- A. Asphalt Cement: AC 20 per ASTM D 3381 for viscosity-graded material except use ductility at 39.2 deg. F., >5 for AC 20 and delete the loss on heating requirement on residue from "Thin-Film Oven Test".
- B. Prime Coat: Not required if paving is done within 48 hours of final compaction.
- C. Tack Coat: ASTM D 977 or AASHTO M 140 emulsified asphalt, or ASTM D 2397 or AASHTO M 208 cationic emulsified asphalt, slow setting, diluted in water, of suitable grade and consistency for application.
- D. Fog Seal: ASTM D 977 or AASHTO M 140 emulsified asphalt, or ASTM D 2397 or AASHTO M 208 cationic emulsified asphalt, slow setting, factory diluted in water, of suitable grade and consistency for application.
- E. Water: Potable.
- F. Undersealing Asphalt: ASTM D 3141, pumping consistency.

## 2.3 AUXILIARY MATERIALS

- A. Herbicide: Commercial chemical for weed control, registered by the EPA. Provide in granular, liquid, or wettable powder form.
- B. Sand: ASTM D 1073 or AASHTO M 29, Grade Nos. 2 or 3.
- C. Paving Geotextile: AASHTO M 288, nonwoven polypropylene; resistant to chemical attack, rot, and mildew; and specifically designed for paving applications.
- D. Joint Sealant: ASTM D 6690 or AASHTO M 324, Type I Type II or III Type IV, hot-applied, single-component, polymer-modified bituminous sealant.
- E. Pavement-Marking Paint: Alkyd-resin type, lead and chromate free, ready mixed, complying with AASHTO M 248, Type N, Type F, and Type S; colors complying with FS TT-P-1952.
  - 1. Color: White, Yellow, Blue, and As indicated.
- F. Pavement-Marking Paint: MPI #32 Alkyd Traffic Marking Paint.

1. Color: White, Yellow, Blue, and As indicated.
- G. Pavement-Marking Paint: Latex, waterborne emulsion, lead and chromate free, ready mixed, complying with FS TT-P-1952, Type II, with drying time of less than 45 minutes.
  1. Color: White, Yellow, Blue, and As indicated.
- H. Pavement-Marking Paint: MPI #97 Latex Traffic Marking Paint.
  1. Color: White, Yellow, Blue, and As indicated.
- I. Glass Beads: AASHTO M 247, Type 1.
- J. Wheel Stops: Precast, air-entrained concrete, 2500-psi minimum compressive strength, 4-1/2 inches high by 9 inches wide by 72 inches. Provide chamfered corners, drainage slots on underside, and holes for anchoring to substrate.
  1. Dowels: Galvanized steel, 3/4-inch diameter, 20-inch minimum length.

#### 2.4 MIXES

- A. Hot-Mix Asphalt: Dense, hot-laid, hot-mix asphalt plant mixes approved by authorities having jurisdiction; designed according to procedures in AI MS-2, "Mix Design Methods for Asphalt Concrete and Other Hot-Mix Types"; and complying with the following requirements:
  1. Provide mixes with a history of satisfactory performance in geographical area where Project is located. Provide mix with the following characteristics:
    - a. Number of compaction blows each end of specimen: 50.
    - b. Satiability based on ASTM D5581: 1200 minimum.
    - c. Flow in 0.01-inch units per ASTM D5581: 10-18.
    - d. Voids in mineral aggregate VMA: 14.
    - e. The percentage of bituminous material by weight added to aggregate will be between 4% and 7% of the weight of the bituminous mixture.
  2. Surface Course: 3-inch minimum compacted thickness and as indicated on the drawings with aggregate meeting the following gradation table

3/4 inch	100
1/2 inch	74-99
3/8 inch	69-91
No. 4	49-65
No. 8	33-47
No. 16	21-35
No. 50	6-18
No. 200	2-6
- B. Emulsified-Asphalt Slurry: ASTM D 3910, Type 1.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Verify that subgrade is dry and in suitable condition to begin paving.
- B. Verify that the road base has been properly compacted and is at the correct line, grade, and slope.
- C. Verify that the road base thickness is as indicated on the project plans.
- D. Verify that sufficient depth at curbs, walks, lips and other vertical edges is available to place the required thickness of compacted asphalt.
- E. Proof-roll subgrade below pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
  - 1. Completely proof-roll subgrade in one direction. Limit vehicle speed to 3 mph.
  - 2. Proof roll with a loaded 10-wheel, tandem-axle dump truck weighing not less than 15 tons or other vehicle with similar axel weight.
  - 3. Excavate soft spots, unsatisfactory soils, and areas of excessive pumping or rutting, as determined by Architect, and replace with compacted backfill or fill as directed.
- F. Proceed with paving only after unsatisfactory conditions have been corrected.
- G. Verify that utilities, traffic loop detectors, and other items requiring a cut and installation beneath the asphalt surface have been completed and that asphalt surface has been repaired flush with adjacent asphalt prior to beginning installation of imprinted asphalt.

### 3.2 PATCHING

- A. Hot-Mix Asphalt Pavement: Saw cut perimeter of patch and excavate existing pavement section to sound base. Excavate rectangular or trapezoidal patches, extending 12 inches into adjacent sound pavement, unless otherwise indicated. Cut excavation faces vertically. Remove excavated material. Recompact existing unbound-aggregate base course to form new subgrade.
- B. Portland Cement Concrete Pavement: Break cracked slabs and roll as required to reseat concrete pieces firmly.
  - 1. Pump hot undersealing asphalt under rocking slab until slab is stabilized or, if necessary, crack slab into pieces and roll to reseat pieces firmly.
  - 2. Remove disintegrated or badly cracked pavement. Excavate rectangular or trapezoidal patches, extending into adjacent sound pavement, unless otherwise indicated. Cut excavation faces vertically. Recompact existing unbound-aggregate base course to form new subgrade.
- C. Tack Coat: Apply uniformly to vertical surfaces abutting or projecting into new, hot-mix asphalt paving at a rate of 0.05 to 0.15 gal./sq. yd.

1. Allow tack coat to cure undisturbed before applying hot-mix asphalt paving.
2. Avoid smearing or staining adjoining surfaces, appurtenances, and surroundings. Remove spillages and clean affected surfaces.

D. Patching: Fill excavated pavements with hot-mix asphalt base mix for full thickness of patch and, while still hot, compact flush with adjacent surface.

E. Patching: Partially fill excavated pavements with hot-mix asphalt base mix and, while still hot, compact. Cover asphalt base course with compacted, hot-mix surface layer finished flush with adjacent surfaces.

### 3.3 REPAIRS

A. Leveling Course: Install and compact leveling course consisting of hot-mix asphalt surface course to level sags and fill depressions deeper than 1 inch in existing pavements.

1. Install leveling wedges in compacted lifts not exceeding 3 inches thick.

B. Crack and Joint Filling: Remove existing joint filler material from cracks or joints to a depth of 1/4 inch.

1. Clean cracks and joints in existing hot-mix asphalt pavement.
2. Use emulsified-asphalt slurry to seal cracks and joints less than 1/4 inch wide. Fill flush with surface of existing pavement and remove excess.
3. Use hot-applied joint sealant to seal cracks and joints more than 1/4 inch wide. Fill flush with surface of existing pavement and remove excess.

### 3.4 SURFACE PREPARATION

A. General: Immediately before placing asphalt materials, remove loose and deleterious material from substrate surfaces. Ensure that prepared subgrade is ready to receive paving.

B. Herbicide Treatment: Not used.

C. Prime Coat: Do not use if paving takes place not more than 48 hours after final compaction and grading of road bases. If paving must be delayed significantly, re-grade and re-compact road base or apply Prime Coat. Apply uniformly over surface of compacted unbound-aggregate base course at a rate of 0.15 to 0.50 gal./sq. yd. Apply enough material to penetrate and seal but not flood surface. Allow prime coat to cure.

1. If prime coat is not entirely absorbed within 24 hours after application, spread sand over surface to blot excess asphalt. Use enough sand to prevent pickup under traffic. Remove loose sand by sweeping before pavement is placed and after volatiles have evaporated.
2. Protect primed substrate from damage until ready to receive paving.

D. Tack Coat: Apply uniformly to surfaces of existing pavement at a rate of 0.05 to 0.15 gal./sq. yd.

1. Allow tack coat to cure undisturbed before applying hot-mix asphalt paving.
2. Avoid smearing or staining adjoining surfaces, appurtenances, and surroundings.
3. Remove and replace items damaged by overspray or clean affected surfaces as directed by architect at no additional cost to owner.

### 3.5 HOT-MIX ASPHALT PLACING

- A. Machine place hot-mix asphalt on prepared surface, spread uniformly, and strike off. Place asphalt mix by hand to areas inaccessible to equipment in a manner that prevents segregation of mix. Place each course to required grade, cross section, and thickness when compacted.
  1. Place hot-mix asphalt surface course in single lift if design thickness is less than 3-inches. If design thickness is more than 3-inches, place in multiple lifts with a minimum thickness of 1.5-inches and a maximum thickness of 3-inches.
  2. Spread mix at minimum temperature of 250 deg F.
  3. Begin applying mix along centerline of crown for crowned sections and on high side of one-way slopes unless otherwise indicated.
  4. Regulate paver machine speed to obtain smooth, continuous surface free of pulls and tears in asphalt-paving mat.
- B. Place paving in consecutive strips not less than 10 feet wide unless infill edge strips of a lesser width are required.
  1. After first strip has been placed and rolled, place succeeding strips and extend rolling to overlap previous strips. Complete a section of asphalt base course before placing asphalt surface course.
- C. Promptly correct surface irregularities in paving course behind paver. Use suitable hand tools to remove excess material forming high spots. Fill depressions with hot-mix asphalt to prevent segregation of mix; use suitable hand tools to smooth surface.

### 3.6 JOINTS

- A. Construct joints to ensure a continuous bond between adjoining paving sections. Construct joints free of depressions, with same texture and smoothness as other sections of hot-mix asphalt course.
  1. Clean contact surfaces and apply tack coat to joints.
  2. Offset longitudinal joints, in successive courses, a minimum of 6 inches.
  3. Offset transverse joints, in successive courses, a minimum of 24 inches.
  4. Construct transverse joints at each point where paver ends a day's work and resumes work at a subsequent time. Construct these joints using either "bulkhead" or "papered" method according to AI MS-22, for both "Ending a Lane" and "Resumption of Paving Operations."
  5. Compact joints as soon as hot-mix asphalt will bear roller weight without excessive displacement.
  6. Compact asphalt at joints to a density within 2 percent of specified course density.

### 3.7 COMPACTION

- A. General: Begin compaction as soon as placed hot-mix paving will bear roller weight without excessive displacement. Compact hot-mix paving with hot, hand tampers or with vibratory-plate compactors in areas inaccessible to rollers.
  - 1. Complete compaction before mix temperature cools to 185 deg F.
- B. Breakdown Rolling: Complete breakdown or initial rolling immediately after rolling joints and outside edge. Examine surface immediately after breakdown rolling for indicated crown, grade, and smoothness. Correct laydown and rolling operations to comply with requirements.
- C. Intermediate Rolling: Begin intermediate rolling immediately after breakdown rolling while hot-mix asphalt is still hot enough to achieve specified density. Continue rolling until hot-mix asphalt course has been uniformly compacted to the following density:
  - 1. Average Density: 96 percent of reference laboratory density according to ASTM D 6927 or AASHTO T 245, but not less than 94 percent nor greater than 100 percent.
- D. Finish Rolling: Finish roll paved surfaces to remove roller marks while hot-mix asphalt is still warm.
- E. Edge Shaping: While surface is being compacted and finished, trim edges of pavement to proper alignment. Bevel edges while asphalt is still hot; compact thoroughly.
- F. Place asphalt so that final compacted asphalt is even with lip of gutter on curbs that drain away from the curb and gutter (open face or depressed curb and gutter). Place asphalt so that final compacted asphalt is 1/4-inch above lip of gutter on curbs that carry water (slope of parking lot is towards the curb). In transition areas, use extra care to make sure that no ponds, bird baths, or depressions are left after paving.
- G. Repairs: Remove paved areas that are defective or contaminated with foreign materials and replace with fresh, hot-mix asphalt. Compact by rolling to specified density and surface smoothness.
- H. Protection: After final rolling, do not permit vehicular traffic on pavement until it has cooled and hardened.
- I. Erect barricades to protect paving from traffic until mixture has cooled enough not to become marked.

### 3.8 INSTALLATION TOLERANCES

- A. Pavement Thickness: Compact each course to produce the thickness indicated within the following tolerances:
  - 1. Surface Course: Plus 1/4 inch, no minus.

- B. Pavement Surface Smoothness: Compact each course to produce a surface smoothness within the following tolerances as determined by using a 10-foot straightedge applied transversely or longitudinally to paved areas:
  - 1. Surface Course: 1/8 inch.
  - 2. Crowned Surfaces: Test with crowned template centered and at right angle to crown. Maximum allowable variance from template is 1/4 inch.
- C. After paving is complete, pour water on paved areas and identify ponds, bird baths, and depressions. Identify the same at open face and transition sections of curb and gutter. Remove and replace asphalt, curb and gutter, road base, and or sub-base as necessary to fix ponds, bird baths, or depressions at no additional cost to owner.

### 3.9 SURFACE TREATMENTS

- A. Fog Seals: Apply fog seal at a rate of 0.10 to 0.15 gal./sq. yd. to existing asphalt pavement and allow to cure. With fine sand, lightly dust areas receiving excess fog seal.
- B. Slurry Seals: Apply slurry coat in a uniform thickness according to ASTM D 3910 and allow curing.
  - 1. Roll slurry seal to remove ridges and provide a uniform, smooth surface.

### 3.10 PAVEMENT MARKING

- A. Do not apply pavement-marking paint until layout, colors, and placement have been verified with Architect and approved by the local jurisdictional fire marshal.
- B. Allow paving to age for 7 days minimum days before starting pavement marking.
- C. Sweep and clean surface to eliminate loose material and dust.
- D. Apply paint with mechanical equipment to produce pavement markings, of dimensions indicated, with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils.
  - 1. Broadcast glass beads uniformly into wet pavement markings at a rate of 6 lb/gal.
- E. Color
  - 1. Yellow: Parking stalls and pedestrian crossings.
  - 2. Blue: Handicap insignia at appropriate stalls.
  - 3. Red: Fire lanes and no parking areas.
  - 4. White: Directional arrows.

### 3.11 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

- B. Thickness: In-place compacted thickness of hot-mix asphalt courses will be determined according to ASTM D 3549.
- C. Surface Smoothness: Finished surface of each hot-mix asphalt course will be tested for compliance with smoothness tolerances.
- D. In-Place Density: Testing agency will take samples of uncompacted paving mixtures and compacted pavement according to ASTM D 979 or AASHTO T 168.
  - 1. Reference maximum theoretical density will be determined by averaging results from four samples of hot-mix asphalt-paving mixture delivered daily to site, prepared according to ASTM D 2041, and compacted according to job-mix specifications.
  - 2. In-place density of compacted pavement will be determined by testing core samples according to ASTM D 1188 or ASTM D 2726. Cores will also be measured for compacted thickness. The owner and architect may also direct additional cores to be taken at locations of their choosing to verify final pavement thickness.
    - a. One core sample will be taken for every 1000 sq. yd. or less of installed pavement, with no fewer than 3 cores taken.
    - b. Field density of in-place compacted pavement may also be determined by nuclear method according to ASTM D 2950 and correlated with ASTM D 1188 or ASTM D 2726.
    - c. Coordinate the time and locations of all holes so that cores may be filled.
- E. The contractor will replace and compact hot-mix asphalt where core tests were taken.
- F. Remove and replace or install additional hot-mix asphalt where test results or measurements indicate that it does not comply with specified requirements.

### 3.12 DISPOSAL

- A. Except for material indicated to be recycled, remove excavated materials from Project site and legally dispose of them in an EPA-approved landfill.
  - 1. Do not allow milled materials to accumulate on-site.

END OF SECTION 321216

THIS PAGE LEFT INTENTIONALLY BLANK

## SECTION 321313 CONCRETE PAVING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes exterior cement concrete pavement for the following:
  - 1. Curbs
  - 2. Walkways.
- B. Related Sections include the following:
  - 1. Division 03 Section "Cast-in-Place Concrete" for general building applications of concrete.
  - 2. Division 31 Section "Earth Moving" for subgrade preparation, grading, and subbase course.
  - 3. Division 32 Section "Concrete Paving Joint Sealants" for joint sealants of joints in concrete pavement and at isolation joints of concrete pavement with adjacent construction.

#### 1.3 DEFINITIONS

- A. Cementitious Materials: Portland cement alone or in combination with one or more of blended hydraulic cement, fly ash and other pozzolans, and ground granulated blast-furnace slag.

#### 1.4 SUBMITTALS

- A. Product Data: For each type of manufactured material and product indicated.
- B. Design Mixtures: For each concrete pavement mixture. Include alternate mixture designs when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
- C. Samples: 10-lb sample of exposed aggregate.
- D. Qualification Data: For manufacturer and testing agency.

- E. Material Test Reports: From a qualified testing agency indicating and interpreting test results for compliance of the following with requirements indicated, based on comprehensive testing of current materials:
  - 1. Aggregates. Include service record data indicating absence of deleterious expansion of concrete due to alkali-aggregate reactivity.
- F. Material Certificates: Signed by manufacturers certifying that each of the following materials complies with requirements:
  - 1. Cementitious materials.
  - 2. Steel reinforcement and reinforcement accessories.
  - 3. Fiber reinforcement.
  - 4. Admixtures.
  - 5. Curing compounds.
  - 6. Applied finish materials.
  - 7. Bonding agent or epoxy adhesive.
  - 8. Joint fillers.
- G. Field quality-control test reports.
- H. Minutes of preinstallation conference.

#### 1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Manufacturer of ready-mixed concrete products who complies with ASTM C 94/C 94M requirements for production facilities and equipment.
  - 1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."
- B. Testing Agency Qualifications: An independent agency qualified according to ASTM C 1077 and ASTM E 329 for testing indicated, as documented according to ASTM E 548.
  - 1. Personnel conducting field tests shall be qualified as ACI Concrete Field Testing Technician, Grade 1, according to ACI CP-01 or an equivalent certification program.
- C. ACI Publications: Comply with ACI 301, "Specification for Structural Concrete," unless modified by requirements in the Contract Documents.
- D. Concrete Testing Service: Engage a qualified independent testing agency to perform material evaluation tests and to design concrete mixtures.
- E. Mockups: Cast mockups of full-size sections of concrete pavement to demonstrate typical joints, surface finish, texture, color, and standard of workmanship.

1. Build mockups in the location and of the size indicated or, if not indicated, as directed by Architect.
  2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
  3. Obtain Architect's approval of mockups before starting construction.
  4. Maintain approved mockups during construction in an undisturbed condition as a standard for judging the completed pavement.
  5. Demolish and remove approved mockups from the site when directed by Architect.
  6. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.
- F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."
1. Before submitting design mixtures, review concrete pavement mixture design and examine procedures for ensuring quality of concrete materials and concrete pavement construction practices. Require representatives, including the following, of each entity directly concerned with concrete pavement, to attend conference:
    - a. Contractor's superintendent.
    - b. Independent testing agency responsible for concrete design mixtures.
    - c. Ready-mix concrete producer.
    - d. Concrete pavement subcontractor.

## 1.6 PROJECT CONDITIONS

- A. Traffic Control: Maintain access for vehicular and pedestrian traffic as required for other construction activities.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products specified.
  2. Products: Subject to compliance with requirements, provide one of the products specified.
  3. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
  4. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

## 2.2 FORMS

- A. Form Materials: Plywood, metal, metal-framed plywood, or other approved panel-type materials to provide full-depth, continuous, straight, smooth exposed surfaces.
  - 1. Use flexible or curved forms for curves with a radius 100 feet or less.
- B. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.

## 2.3 STEEL REINFORCEMENT (NO REINFORCEMENT USED FOR FLATWORK)

- A. Plain-Steel Welded Wire Reinforcement: ASTM A 185, fabricated from as-drawn steel wire into flat sheets.
- B. Deformed-Steel Welded Wire Reinforcement: ASTM A 497, flat sheet.
- C. Reinforcing Bars: ASTM A 615/A 615M, Grade 60; deformed.
- D. Steel Bar Mats: ASTM A 184/A 184M; with ASTM A 615/A 615M, Grade 60, deformed bars; assembled with clips.
- E. Plain Steel Wire: ASTM A 82.
- F. Deformed-Steel Wire: ASTM A 496.
- G. Joint Dowel Bars: Plain steel bars, ASTM A 615/A 615M, Grade 60. Cut bars true to length with ends square and free of burrs.
- H. Tie Bars: ASTM A 615/A 615M, Grade 60, deformed.
- I. Hook Bolts: ASTM A 307, Grade A, internally and externally threaded. Design hook-bolt joint assembly to hold coupling against pavement form and in position during concreting operations, and to permit removal without damage to concrete or hook bolt.
- J. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars, welded wire reinforcement, and dowels in place. Manufacture bar supports according to CRSI's "Manual of Standard Practice" from steel wire, plastic, or precast concrete of greater compressive strength than concrete, and as follows:
  - 1. Equip wire bar supports with sand plates or horizontal runners where base material will not support chair legs.
  - 2. For epoxy-coated reinforcement, use epoxy-coated or other dielectric-polymer-coated wire bar supports.

## 2.4 CONCRETE MATERIALS

- A. Cementitious Material: Use the following cementitious materials, of the same type, brand, and source throughout the Project:
  - 1. Portland Cement and as specified in Division 3 except that for exterior concrete, the minimum compressive strength is 4000 psi at 28 days.
- B. Normal-Weight Aggregates: ASTM C 33, coarse aggregate, uniformly graded. Provide aggregates from a single source with documented service record data of at least 10 years' satisfactory service in similar pavement applications and service conditions using similar aggregates and cementitious materials.
  - 1. Maximum Coarse-Aggregate Size: 1 inch nominal.
  - 2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
- C. Exposed Aggregate: Selected, hard, and durable; washed; free of materials with deleterious reactivity to cement or that cause staining; from a single source, with gap-graded coarse aggregate as follows:
  - 1. Aggregate Sizes: 3/4 to 1 inch nominal.
  - 2. Aggregate Source, Shape, and Color and as required by the architect.
- D. Water: ASTM C 94/C 94M.
- E. Air-Entraining Admixture: ASTM C 260.
- F. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material.
  - 1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.
  - 2. Retarding Admixture: ASTM C 494/C 494M, Type B.
  - 3. Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type D.
  - 4. High-Range, Water-Reducing Admixture: ASTM C 494/C 494M, Type F.
  - 5. High-Range, Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type G.
  - 6. Plasticizing and Retarding Admixture: ASTM C 1017/C 1017M, Type II.

## 2.5 FIBER REINFORCEMENT

- A. Synthetic Fiber: Monofilament or fibrillated polypropylene fibers engineered and designed for use in concrete pavement, complying with ASTM C 1116, Type III, 1/2 to 1-1/2 inches long.
  - 1. Products:
    - a. Monofilament Fibers:

- 1) Axim Concrete Technologies; Fibrasol IIP.
- 2) Euclid Chemical Company (The); Fiberstrand 100.
- 3) FORTA Corporation; Forta Mono.
- 4) Grace, W. R. & Co.--Conn.; Grace MicroFiber.
- 5) Metalcrete Industries; Polystrand 1000.
- 6) SI Concrete Systems; Fibermix Stealth.

b. Fibrillated Fibers:

- 1) Axim Concrete Technologies; Fibrasol F.
- 2) FORTA Corporation; Forta.
- 3) Euclid Chemical Company (The); Fiberstrand F.
- 4) Grace, W. R. & Co.--Conn.; Grace Fibers.
- 5) SI Concrete Systems; Fibermesh.

## 2.6 CURING MATERIALS

- A. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. dry.
- B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- C. Water: Potable.
- D. Evaporation Retarder: Waterborne, monomolecular film forming; manufactured for application to fresh concrete.
  1. Products:
    - a. Axim Concrete Technologies; Cimfilm.
    - b. Burke by Edeco; BurkeFilm.
    - c. ChemMasters; Spray-Film.
    - d. Conspec Marketing & Manufacturing Co., Inc.; Aquafilm.
    - e. Dayton Superior Corporation; Sure Film.
    - f. Euclid Chemical Company (The); Eucobar.
    - g. Kaufman Products, Inc.; Vapor Aid.
    - h. Lambert Corporation; Lambco Skin.
    - i. L&M Construction Chemicals, Inc.; E-Con.
    - j. MBT Protection and Repair, ChemRex Inc.; Confilm.
    - k. Meadows, W. R., Inc.; Sealtight Evapre.
    - l. Metalcrete Industries; Waterhold.
    - m. Nox-Crete Products Group, Kinsman Corporation; Monofilm.
    - n. Sika Corporation, Inc.; SikaFilm.
    - o. Symons Corporation; Finishing Aid.
    - p. Vexcon Chemicals, Inc.; Certi-Vex EnvioAssist.
- E. Clear Waterborne Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B.

1. Products:
  - a. Anti-Hydro International, Inc.; AH Curing Compound #2 DR WB.
  - b. Burke by Edoko; Aqua Resin Cure.
  - c. ChemMasters; Safe-Cure Clear.
  - d. Conspec Marketing & Manufacturing Co., Inc.; W.B. Resin Cure.
  - e. Dayton Superior Corporation; Day Chem Rez Cure (J-11-W).
  - f. Euclid Chemical Company (The); Kurez DR VOX.
  - g. Kaufman Products, Inc.; Thinfilm 420.
  - h. Lambert Corporation; Aqua Kure-Clear.
  - i. L&M Construction Chemicals, Inc.; L&M Cure R.
  - j. Meadows, W. R., Inc.; 1100 Clear.
  - k. Nox-Crete Products Group, Kinsman Corporation; Resin Cure E.
  - l. Symons Corporation; Resi-Chem Clear.
  - m. Tamms Industries Inc.; Horncure WB 30.
  - n. Unitex; Hydro Cure 309.
  - o. Vexcon Chemicals, Inc.; Certi-Vex Enviocure 100.
  
- F. White Waterborne Membrane-Forming Curing Compound: ASTM C 309, Type 2, Class B.
  1. Products:
    - a. Anti-Hydro International, Inc.; AH Curing Compound #2 WP WB.
    - b. Burke by Edoco; Resin Emulsion White.
    - c. ChemMasters; Safe-Cure 2000.
    - d. Conspec Marketing & Manufacturing Co., Inc.; W.B. Resin Cure.
    - e. Dayton Superior Corporation; Day-Chem White Pigmented Cure (J-10-W).
    - f. Euclid Chemical Company (The); Kurez VOX White Pigmented.
    - g. Kaufman Products, Inc.; Thinfilm 450.
    - h. Lambert Corporation; Aqua Kure-White.
    - i. L&M Construction Chemicals, Inc.; L&M Cure R-2.
    - j. Meadows, W. R., Inc.; 1200-White.
    - k. Symons Corporation; Resi-Chem White.
    - l. Tamms Industries, Inc.; Horncure 200-W.
    - m. Unitex; Hydro White.
    - n. Vexcon Chemicals, Inc.; Certi-Vex Enviocure White 100.

## 2.7 RELATED MATERIALS

- A. Expansion- and Isolation-Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber or ASTM D 1752, cork or self-expanding cork.
  
- B. Color stain: Match Architect's sample or as selected by Architect from manufacturer's full range of stains.

- C. Slip-Resistive Aggregate Finish: Factory-graded, packaged, rustproof, nonglazing, abrasive aggregate of fused aluminum-oxide granules or crushed emery with emery aggregate containing not less than 50 percent aluminum oxide and not less than 20 percent ferric oxide; unaffected by freezing, moisture, and cleaning materials.
- D. Bonding Agent: ASTM C 1059, Type II, non-redispersible, acrylic emulsion or styrene butadiene.
- E. Epoxy Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to requirements, and as follows:
  - 1. Types I and II, non-load bearing and types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.
- F. Chemical Surface Retarder: Water-soluble, liquid-set retarder with color dye, for horizontal concrete surface application, capable of temporarily delaying final hardening of concrete to a depth of 1/8 to 1/4 inch.
  - 1. Products:
    - a. Burke by Edeco; True Etch Surface Retarder.
    - b. ChemMasters; Exposee.
    - c. Conspec Marketing & Manufacturing Co., Inc.; Delay S.
    - d. Euclid Chemical Company (The); Surface Retarder S.
    - e. Kaufman Products, Inc.; Expose.
    - f. Metalcrete Industries; Surfard.
    - g. Nox-Crete Products Group, Kinsman Corporation; Crete-Nox TA.
    - h. Scofield, L. M. Company; Lithotex.
    - i. Sika Corporation, Inc.; Rugasol-S.
    - j. Vexcon Chemicals, Inc.; Certi-Vex Envioset.

## 2.8 CONCRETE MIXTURES

- A. Prepare design mixtures, proportioned according to ACI 301, for each type and strength of normal-weight concrete determined by either laboratory trial mixes or field experience.
  - 1. Use a qualified independent testing agency for preparing and reporting proposed concrete mixture designs for the trial batch method.
- B. Proportion mixtures to provide normal-weight concrete with the following properties:
  - 1. Compressive Strength (28 Days): 5000 psi
  - 2. Maximum Water-Cementitious Materials Ratio at Point of Placement: 0.45
  - 3. Select slump limit from options in subparagraph below or revise to suit Project.
  - 4. Slump Limit: 4 inches, plus or minus 1 inch.
- C. Add air-entraining admixture at manufacturer's prescribed rate to result in normal-weight concrete at point of placement having an air content as follows:

1. Air Content: 5-8 percent nominal maximum aggregate size.
- D. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.
- E. Chemical Admixtures: Use admixtures according to manufacturer's written instructions.
  1. Use water-reducing admixture, high-range, water-reducing admixture, high-range, water-reducing and retarding admixture, plasticizing, and retarding admixture in concrete, as required, for placement and workability.
  2. Specify admixtures as part of submittal. Verify that admixtures proposed do not adversely effect stained concrete and will not modify colors of stain.
  3. Coordinate acceptability of admixtures with architect.
- F. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement according to ACI 301 requirements as follows:
  1. Fly Ash or Pozzolan: 25 percent.
  2. Ground Granulated Blast-Furnace Slag: 50 percent.
  3. Combined Fly Ash or Pozzolan, and Ground Granulated Blast-Furnace Slag: 50 percent, with fly ash or pozzolan not exceeding 25 percent.
- G. Synthetic Fiber: Uniformly disperse in concrete mix at manufacturer's recommended rate, but not less than 1.0 lb/cu. yd. where specified and approved in mix submittal.

## 2.9 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, and mix concrete materials and concrete according to ASTM C 94/C 94M. Furnish batch certificates for each batch discharged and used in the Work.
  1. When air temperature is between 85 deg F and 90 deg F, reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F, reduce mixing and delivery time to 60 minutes.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine exposed subgrades and subbase surfaces for compliance with requirements for dimensional, grading, and elevation tolerances.
- B. Proof-roll prepared subbase surface below concrete pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding.

1. Completely proof-roll subbase in one direction. Limit vehicle speed to 3 mph.
  2. Proof-roll with a loaded 10-wheel tandem-axle dump truck weighing not less than 15 tons or similar axel weight vehicle.
  3. Subbase with soft spots and areas of pumping or rutting exceeding depth of 1/2 inch require correction according to requirements in Division 31 Section "Earth Moving."
- C. Proceed with concrete pavement operations only after nonconforming conditions have been corrected and subgrade is ready to receive pavement.

### 3.2 PREPARATION

- A. Remove loose material from compacted subbase surface immediately before placing concrete.

### 3.3 EDGE FORMS AND SCREED CONSTRUCTION

- A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides for pavement to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

### 3.4 STEEL REINFORCEMENT

- A. General: Comply with CRSI's "Manual of Standard Practice" for fabricating, placing, and supporting reinforcement.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, or other bond-reducing materials.
- C. Arrange, space, and securely tie bars and bar supports to hold reinforcement in position during concrete placement. Maintain minimum cover to reinforcement.
- D. Install welded wire reinforcement in lengths as long as practicable. Lap adjoining pieces at least one full mesh, and lace splices with wire. Offset laps of adjoining widths to prevent continuous laps in either direction.
- E. Install fabricated bar mats in lengths as long as practicable. Handle units to keep them flat and free of distortions. Straighten bends, kinks, and other irregularities, or replace units as required before placement. Set mats for a minimum 2-inch overlap of adjacent mats.

### 3.5 JOINTS

- A. General: Form construction, isolation, and contraction joints and tool edgings true to line with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline, unless otherwise indicated.
  - 1. When joining existing pavement, place transverse joints to align with previously placed joints, unless otherwise indicated.
  
- B. Construction Joints: Set construction joints at side and end terminations of pavement and at locations where pavement operations are stopped for more than one-half hour unless pavement terminates at isolation joints.
  - 1. Continue steel reinforcement across construction joints, unless otherwise indicated. Do not continue reinforcement through sides of pavement strips, unless otherwise indicated.
  - 2. Provide tie bars at sides of pavement strips where indicated.
  - 3. Butt Joints: Use bonding agent at joint locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
  - 4. Keyed Joints: Provide preformed keyway-section forms or bulkhead forms with keys, unless otherwise indicated. Embed keys at least 1-1/2 inches into concrete.
  - 5. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt-coat one-half of dowel length to prevent concrete bonding to one side of joint.
  
- C. Isolation Joints: Form isolation joints of preformed joint-filler strips abutting concrete curbs, catch basins, manholes, inlets, structures, walks, other fixed objects, and where indicated.
  - 1. Locate expansion joints at intervals of 50 feet, unless otherwise indicated.
  - 2. Extend joint fillers full width and depth of joint.
  - 3. Terminate joint filler not less than 1/2 inch or more than 1 inch below finished surface if joint sealant is indicated.
  - 4. Place top of joint filler flush with finished concrete surface if joint sealant is not indicated.
  - 5. Furnish joint fillers in one-piece lengths. Where more than one length is required, lace or clip joint-filler sections together.
  - 6. Protect top edge of joint filler during concrete placement with metal, plastic, or other temporary preformed cap. Remove protective cap after concrete has been placed on both sides of joint.
  
- D. Contraction Joints: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of the concrete thickness, as follows:
  - 1. Grooved Joints: Form contraction joints after initial floating by grooving and finishing each edge of joint with grooving tool to a 1/4-inch radius. Repeat grooving of contraction joints after applying surface finishes. Eliminate groover marks on concrete surfaces.

2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch-wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before developing random contraction cracks.
  3. Doweled Contraction Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt coat one-half of dowel length to prevent concrete bonding to one side of joint.
- E. Edging: Tool edges of pavement, gutters, curbs, and joints in concrete after initial floating with an edging tool to a 1/4-inch radius. Repeat tooling of edges after applying surface finishes. Eliminate tool marks on concrete surfaces.

### 3.6 CONCRETE PLACEMENT

- A. Inspection: Before placing concrete, inspect and complete formwork installation, steel reinforcement, and items to be embedded or cast in. Notify other trades to permit installation of their work.
- B. Remove snow, ice, or frost from subbase surface and reinforcement before placing concrete. Do not place concrete on frozen surfaces.
- C. Moisten subbase to provide a uniform dampened condition at time concrete is placed. Do not place concrete around manholes or other structures until they are at required finish elevation and alignment.
- D. Comply with ACI 301 requirements for measuring, mixing, transporting, and placing concrete.
- E. Do not add water to concrete during delivery or at Project site.
- F. Do not add water to fresh concrete after testing.
- G. Deposit and spread concrete in a continuous operation between transverse joints. Do not push or drag concrete into place or use vibrators to move concrete into place.
- H. Consolidate concrete according to ACI 301 by mechanical vibrating equipment supplemented by hand spading, rodding, or tamping.
  1. Consolidate concrete along face of forms and adjacent to transverse joints with an internal vibrator. Keep vibrator away from joint assemblies, reinforcement, or side forms. Use only square-faced shovels for hand spreading and consolidation. Consolidate with care to prevent dislocating reinforcement, dowels, and joint devices.
- I. Place concrete in two operations; strike off initial pour for entire width of placement and to the required depth below finish surface. Lay welded wire fabric or fabricated bar mats immediately in final position. Place top layer of concrete, strike off, and screed.

1. Remove and replace concrete that has been placed for more than 15 minutes without being covered by top layer, or use bonding agent if approved by Architect.
- J. Screed pavement surfaces with a straightedge and strike off.
- K. Commence initial floating using bull floats or darbies to impart an open textured and uniform surface plane before excess moisture or bleed water appears on the surface. Do not further disturb concrete surfaces before beginning finishing operations or spreading surface treatments.
- L. Curbs: When automatic machine placement is used for curb and gutter placement, submit revised mix design and laboratory test results that meet or exceed requirements. Produce curbs and gutters to required cross section, lines, grades, finish, and jointing as specified for formed concrete. If results are not approved, remove and replace with formed concrete.
- M. When adjoining pavement lanes are placed in separate pours, do not operate equipment on concrete until pavement has attained 85 percent of its 28-day compressive strength.
- N. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
  1. When air temperature has fallen to or is expected to fall below 40 deg F, uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg F and not more than 80 deg F at point of placement.
  2. Do not use frozen materials or materials containing ice or snow.
  3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mix designs.
- O. Hot-Weather Placement: Comply with ACI 301 and as follows when hot-weather conditions exist:
  1. Cool ingredients before mixing to maintain concrete temperature below 90 deg F at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.
  2. Cover steel reinforcement with water-soaked burlap so steel temperature will not exceed ambient air temperature immediately before embedding in concrete.
  3. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade moisture uniform without standing water, soft spots, or dry areas.

### 3.7 FLOAT FINISHING

- A. General: Do not add water to concrete surfaces during finishing operations.

- B. Float Finish: Begin the second floating operation when bleed-water sheen has disappeared and concrete surface has stiffened sufficiently to permit operations. Float surface with power-driven floats, or by hand floating if area is small or inaccessible to power units. Finish surfaces to true planes. Cut down high spots and fill low spots. Refloat surface immediately to uniform granular texture.
  - 1. Burlap Finish: Drag a seamless strip of damp burlap across float-finished concrete, perpendicular to line of traffic, to provide a uniform, gritty texture.
  - 2. Medium-to-Fine-Textured Broom Finish: Draw a soft bristle broom across float-finished concrete surface perpendicular to line of traffic to provide a uniform, fine-line texture.
  - 3. Medium-to-Coarse-Textured Broom Finish: Provide a coarse finish by striating float-finished concrete surface 1/16 to 1/8 inch deep with a stiff-bristled broom, perpendicular to line of traffic.
  - 4. Coordinate with architect the locations of each type of finish.

### 3.8 CONCRETE PROTECTION AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
- B. Comply with ACI 306.1 for cold-weather protection.
- C. Evaporation Retarder: Apply evaporation retarder to concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- D. Begin curing after finishing concrete but not before free water has disappeared from concrete surface.
- E. Curing Methods: Cure concrete by moisture curing, moisture-retaining-cover curing, curing compound, or a combination of these as follows:
  - 1. Moist Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
    - a. Water.
    - b. Continuous water-fog spray.
    - c. Absorptive cover, water saturated and kept continuously wet. Cover concrete surfaces and edges with 12-inch lap over adjacent absorptive covers.
  - 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
  - 3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to

heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

### 3.9 PAVEMENT TOLERANCES

A. Comply with tolerances of ACI 117 and as follows:

1. Elevation: 1/4 inch.
2. Thickness: Plus 3/8 inch, minus 1/4 inch.
3. Surface: Gap below 10-foot-long, unlevelled straightedge not to exceed 1/4 inch.
4. Lateral Alignment and Spacing of Tie Bars and Dowels: 1 inch.
5. Vertical Alignment of Tie Bars and Dowels: 1/4 inch.
6. Alignment of Tie-Bar End Relative to Line Perpendicular to Pavement Edge: 1/2 inch.
7. Alignment of Dowel-Bar End Relative to Line Perpendicular to Pavement Edge: Length of dowel 1/4 inch per 12 inches.
8. Joint Spacing: 3 inches.
9. Contraction Joint Depth: Plus 1/4 inch, no minus.
10. Joint Width: Plus 1/8 inch, no minus.

### 3.10 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.

B. Testing Services: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:

1. Testing Frequency: Obtain at least 1 composite sample for each 100 cu. yd. or 5000 sq. ft. or fraction thereof of each concrete mix placed each day.
  - a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
2. Slump: ASTM C 143/C 143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mix. Perform additional tests when concrete consistency appears to change.
3. Air Content: ASTM C 231, pressure method; one test for each composite sample, but not less than one test for each day's pour of each concrete mix.
4. Concrete Temperature: ASTM C 1064; one test hourly when air temperature is 40 deg F and below and when 80 deg F and above, and one test for each composite sample.
5. Compression Test Specimens: ASTM C 31/C 31M; cast and laboratory cure one set of three standard cylinder specimens for each composite sample.
6. Compressive-Strength Tests: ASTM C 39/C 39M; test 1 specimen at 7 days and 2 specimens at 28 days.

- a. A compressive-strength test shall be the average compressive strength from 2 specimens obtained from same composite sample and tested at 28 days.
- C. Strength of each concrete mix will be satisfactory if average of any 3 consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi.
- D. Test results shall be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- F. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect.
- G. Remove and replace concrete pavement where test results indicate that it does not comply with specified requirements.
- H. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

### 3.11 REPAIRS AND PROTECTION

- A. Remove and replace concrete pavement that is broken, damaged, or defective or that does not comply with requirements in this Section.
- B. Drill test cores, where directed by Architect, when necessary to determine magnitude of cracks or defective areas. Fill drilled core holes in satisfactory pavement areas with portland cement concrete bonded to pavement with epoxy adhesive.
- C. Protect concrete from damage. Exclude traffic from pavement for at least 14 days after placement. When construction traffic is permitted, maintain pavement as clean as possible by removing surface stains and spillage of materials as they occur.
- D. Maintain concrete pavement free of stains, discoloration, dirt, and other foreign material. Sweep concrete pavement not more than two days before date scheduled for Substantial Completion inspections.

END OF SECTION 321313

## **SECTION 32 13 73 CONCRETE PAVING JOINT SEALANTS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Expansion and contraction joints within cement concrete pavement.
  - 2. Joints between cement concrete and asphalt pavement.
- B. Related Sections include the following:
  - 1. Division 07 Section "Joint Sealants" for sealing nontraffic and traffic joints in locations not specified in this Section.
  - 2. Division 32 Section "Asphalt Paving" for constructing joints between concrete and asphalt pavement.
  - 3. Division 32 Section "Concrete Paving" for constructing joints in concrete pavement.

#### **1.3 SUBMITTALS**

- A. Product Data: For each joint-sealant product indicated.
- B. Samples for Verification: For each type and color of joint sealant required. Install joint-sealant samples in 1/2-inch wide joints formed between two 6-inch long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.
- C. Product Certificates: For each type of joint sealant and accessory, signed by product manufacturer.
- D. Qualification Data: For installer and testing agency.
- E. Compatibility and Adhesion Test Reports: From sealant manufacturer, indicating the following:
  - 1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
  - 2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion.
- F. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for sealants.

#### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An employer of workers trained and approved by manufacturer.
- B. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.
- C. Preconstruction Compatibility and Adhesion Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.
  - 1. Use ASTM C 1087 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
  - 2. Submit not fewer than six (6) pieces of each type of material, including joint substrates, shims, joint-sealant backings, secondary seals, and miscellaneous materials.
  - 3. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
  - 4. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures including use of specially formulated primers.
  - 5. Testing will not be required if joint-sealant manufacturers submit joint preparation data that are based on previous testing of current sealant products for adhesion to, and compatibility with, joint substrates and other materials matching those submitted.
- D. Product Testing: Obtain test results for "Product Test Reports" Paragraph in "Submittals" Article from a qualified testing agency based on testing of current sealant products within a 36-month period preceding the commencement of the Work.
  - 1. Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 for testing indicated, as documented according to ASTM E 548.

#### 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to Project site in original unopened containers or bundles with labels indicating manufacturer, product name and designation, color, expiration date, pot life, curing time, and mixing instructions for multi-component materials.
- B. Store and handle materials to comply with manufacturer's written instructions to prevent their deterioration or damage due to moisture, high or low temperatures, contaminants, or other causes.

#### 1.6 PROJECT CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
  - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer.
  - 2. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
  - 3. When joint substrates are wet or covered with frost.
  - 4. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
  - 5. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products listed in other Part 2 articles.
- B. Products: Subject to compliance with requirements, provide one of the products listed in other Part 2 articles.

### 2.2 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backing materials, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer based on testing and field experience.
- B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

### 2.3 COLD-APPLIED JOINT SEALANTS

- A. Multi-component Jet-Fuel-Resistant Sealant for Concrete: Pourable, chemically curing elastomeric formulation complying with the following requirements for formulation and with ASTM C 920 for type, grade, class, and uses indicated:
  - 1. Urethane Formulation: Type M; Grade P; Class 12-1/2; Uses T, M, and, as applicable to joint substrates indicated, O.
    - a. Available Products:
      - 1) Pecora Corporation; Urexpan NR-300.
      - 2) Engineer approved equal.
  - 2. Coal-Tar-Modified Polymer Formulation: Type M; Grade P; Class 25; Uses T and, as applicable to joint substrates indicated, O.
    - a. Available Products:
      - 1) Meadows, W. R., Inc.; Sealtight Gardox.
      - 2) Engineer Approved Equal.
  - 3. Bitumen-Modified Urethane Formulation: Type M; Grade P; Class 25; Uses T, M, and, as applicable to joint substrates indicated, O.
    - a. Available Products:
      - 1) Tremco Sealant/Waterproofing Division; Vulkem 202.
      - 2) Engineer approved Equal.
- B. Single-Component Jet-Fuel-Resistant Urethane Sealant for Concrete: Single-component, pourable, coal-tar-modified, urethane formulation complying with ASTM C 920 for Type S; Grade P; Class 25; Uses T, M, and, as applicable to joint substrates indicated, O.

1. Available Products:
  - a. Sonneborn, Div. of ChemRex, Inc.; Sonomeric 1.
  - b. Engineer Approved Equal.
  
- C. Type NS Silicone Sealant for Concrete: Single-component, low-modulus, neutral-curing, nonsag silicone sealant complying with ASTM D 5893 for Type NS.
  1. Available Products:
    - a. Crafcoc Inc.; RoadSaver Silicone.
    - b. Dow Corning Corporation; 888.
    - c. Engineer Approved Equal.
  
- D. Type SL Silicone Sealant for Concrete and Asphalt: Single-component, low-modulus, neutral-curing, self-leveling silicone sealant complying with ASTM D 5893 for Type SL.
  1. Available Products:
    - a. Crafcoc Inc.; RoadSaver Silicone SL.
    - b. Dow Corning Corporation; 890-SL.
    - c. Engineer Approved Equal.
  
- E. Multi-component Low-Modulus Sealant for Concrete and Asphalt: Proprietary formulation consisting of reactive petropolymer and activator components producing a pourable, self-leveling sealant.
  1. Available Products:
    - a. Meadows, W. R., Inc.; Sof-Seal.
    - b. Engineer Approved Equal.

## 2.4 HOT-APPLIED JOINT SEALANTS

- A. Jet-Fuel-Resistant Elastomeric Sealant for Concrete: Single-component formulation complying with ASTM D 3569.
  1. Available Products:
    - a. Crafcoc Inc.; Superseal 444/777.
    - b. Meadows, W. R., Inc.; Poly-Jet 3569.
    - c. Engineer Approved Equal.
  
- B. Jet-Fuel-Resistant Sealant for Concrete and Tar Concrete: Single-component formulation complying with ASTM D 3581.
  1. Available Products:
    - a. Crafcoc Inc.; Superseal 1614A.
    - b. Meadows, W. R., Inc.; Poly-Jet 1614.
    - c. Meadows, W. R., Inc.; Poly-Jet 3406.
    - d. Meadows, W. R., Inc.; Poly-Jet 3569.
    - e. Engineer Approved Equal.

C. Elastomeric Sealant for Concrete: Single-component formulation complying with ASTM D 3406.

1. Available Products:

- a. Crafcro Inc.; Superseal 444/777.
- b. Meadows, W. R., Inc.; Poly-Jet 3406.
- c. Engineer Approved Equal.

D. Sealant for Concrete and Asphalt: Single-component formulation complying with ASTM D 3405.

1. Available Products:

- a. Koch Materials Company; Product No. 9005.
- b. Koch Materials Company; Product No. 9030.
- c. Meadows, W. R., Inc.; Sealtight Hi-Spec.
- d. Engineer Approved Equal.

## 2.5 JOINT-SEALANT BACKER MATERIALS

- A. General: Provide joint-sealant backer materials that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by joint-sealant manufacturer based on field experience and laboratory testing.
- B. Round Backer Rods for Cold- and Hot-Applied Sealants: ASTM D 5249, Type 1, of diameter and density required to control sealant depth and prevent bottom-side adhesion of sealant.
- C. Backer Strips for Cold- and Hot-Applied Sealants: ASTM D 5249; Type 2; of thickness and width required to control sealant depth, prevent bottom-side adhesion of sealant, and fill remainder of joint opening under sealant.
- D. Round Backer Rods for Cold-Applied Sealants: ASTM D 5249, Type 3, of diameter and density required to control sealant depth and prevent bottom-side adhesion of sealant.

## 2.6 PRIMERS

- A. Primers: Product recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
  - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions.
- B. Joint Priming: Prime joint substrates where indicated or where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

### 3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install backer materials of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
  - 1. Do not leave gaps between ends of backer materials.
  - 2. Do not stretch, twist, puncture, or tear backer materials.
  - 3. Remove absorbent backer materials that have become wet before sealant application and replace them with dry materials.
- D. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
  - 1. Place sealants so they directly contact and fully wet joint substrates.
  - 2. Completely fill recesses provided for each joint configuration.
  - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- E. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
  - 1. Remove excess sealants from surfaces adjacent to joint.
  - 2. Use tooling agents that are approved in writing by joint-sealant manufacturer and that do not discolor sealants or adjacent surfaces.
- F. Provide joint configuration to comply with joint-sealant manufacturer's written instructions, unless otherwise indicated.
- G. Provide recessed joint configuration for silicone sealants of recess depth and at locations indicated.

3.4 CLEANING

- A. Clean off excess sealants or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved by manufacturers of joint sealants and of products in which joints occur.

3.5 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately and replace with joint sealant so installations with repaired areas are indistinguishable from the original work.

END OF SECTION 321373

THIS PAGE LEFT INTENTIONALLY BLANK

## SECTION 321823 – POURED ATHLETIC TRACK SURFACE SYSTEMS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes polyurethane track surface with “Hobart” texture installed over asphalt substrate
  1. Track related sports accessories (Discus ring, sleeves for discus cage)
  2. Striping of track surface and track and field areas.
  3. Re-striping of track included once in the warranty period
  4. Surveyor verification that all markings are within standards established by NCAA

#### B. RELATED WORK

1. Division 32 Section “Asphalt Paving for paving wearing course in this Contract that is placed over sub-base provided under separate contract.

#### 1.3 DESCRIPTION OF WORK

- A. The contracted work to be done under these specifications consists of furnishing all the required labor, materials, equipment, parts and supplies necessary for the installation of the running track surface.
- B. The work hereunder shall be done and conform to the standards for track construction as prescribed or approved by the NCAA, or IAAF.
- C. The Track Installer shall provide all labor, materials and equipment to perform the following work:
  1. Review Bidding documents and specifications, verify suitability of installation of the base to corrected levels and the in-ground track and field equipment.
  2. Sufficiently clean down all areas to be surfaced and protect all areas not to receive synthetic surface.
  3. Approve asphalt surfacing installed as work of this contract.
  4. Install approved synthetic surfacing material on all areas as defined by the Bidding documents.
  5. Install removable synthetic surfacing (rubber or full pour polyurethane), as covers in all throwing circles within synthetic aprons, on pole vault box covers, on long/triple jump blanking boards and, if included, apply synthetic surfacing to the sand pit covers.
  6. Stripe all lane lines, start-finish lines, event markings, 5 sets of lane numbers (one color) and runway borders according to NFHS standards per the listing hereafter.

D. 400m track markings ( NCAA based) contrasting colors required

1. Official NCAA Events:

- a) 100 meters One directions on home straight- a-way
- b) 100 meter hurdles One directions on home straight-a-way
- c) 110 meter hurdles One directions on home straight-a-way
- d) 200 meters All in lanes, one turn
- e) 400 meters All in lanes
- f) 300 meter hurdles All in lanes
- g) 800 meters Water fall start and 1-turn stagger
- h) 1600 meters Water fall start
- i) 3200 meters Water fall start
- j) 400 meter relay (4 x 100 meters) All in lanes
- a) 800 meter relay (4 x 200 meters) All in lanes
- k) 1600 meter relay (4 x 400 meters) Three Turn Stagger
- l) 3200 meter relay (4 x 800 meters)
- m) Shot Put, Discus, and Hammer events - paint dividing lines;
- n) Shot Put, Discus, Hammer, - paint sector lines (not in circle or on runway)
- o) Pole vault, long jump, triple jump - paint runway lines
- p) Common Finish Line - alternating solid black square with open square
- q) Lane Numbers - paint prior to common finish line, client to confirm whether facing direction of running or camera
- r) Relay Exchange Zones, all per the NCAA rule book.

2. Other Events:

- a) 1-mile run
- b) Common finish line paint lean lines at 1 meter intervals, total 5 meters.

3. Paint:

- a) All lane lines, start and finish lines to receive 2 coats, colors per NCAA rule book
- b) Numbers are to be 30" high; five (5) sets of numbers are required, location verified by Owner prior to installation.

1.3 SUBMITTALS

- A. The following information shall be submitted in accordance with Division 1 requirements.

- B. Standard printed specifications of the synthetic surfacing system that is being installed.
- C. Installation process and requirements for the base, and any conditions that may limit the sports installation, or affect quality of installation.
- D. Temperature / climatic conditions limiting quality of installation.
- E. Provide documentation that shows the selected specified and installed product meets the IAAF Performance Specification for Synthetic Surfaced Athletics Tracks (Outdoor) and is certified in terms of the IAAF certification system as updated on April 1, 1999.
- F. Provide a list of completed facilities, as listed in the Owner's Request for Proposal, which are certified to meet NCAA rules & regulations, utilizing the same product as specified.
- G. Shop Drawings: Show the following:
  - 1. Installation details
  - 2. Layout of all lanes, markings, colors required for NCAA compliant track.
- H. Samples for Initial Selection: For type of system indicated. 12 x 12 inch sample.
- I. Qualification Data: For **Installer**.
- J. Warranty: Special warranty specified in this Section.

#### 1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain athletic track surface system materials, **including primers and binders**, through one source from a single manufacturer.
  - 1. Provide secondary materials **including adhesives, primers**, and repair materials of type and from source recommended by manufacturer of playground surface system materials.
- B. Contractor Qualifications
  - 1. The CONTRACTOR and MANUFACTURER must have a minimum of 5 years of experience in the installation of full depth poured-in place two component elastomeric polyurethane synthetic track surfacing.
  - 2. The MANUFACTURER must have a minimum of 10 years of experience with the compounding of two-part polyurethane for athletic surfaces.
  - 3. The CONTRACTOR shall have 10 years experience with the aliphatic coating.
  - 4. The SUPERVISOR of the installation must have installed a minimum of 5 full depth two component polyurethane tracks with an encapsulated texture in the last 3 years. A reference list must be submitted.

#### 1.5 PROJECT CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit surface system installation to be performed according to manufacturers' written instructions and warranty requirements.

- B. Installation shall not take place if adjacent or concurrent construction generates excessive dust, abrasives or any other byproduct that, in the opinion of the installer, would be harmful to the track material, until completion of such works.
- C. If, in the opinion of the installer of the synthetic material, the weather and/or climatic conditions are detrimental to the proper installation of the surfacing materials, work shall be delayed until conditions are acceptable.
- D. Minimum install temperature is 50 degrees Fahrenheit and rising as recommended by Manufacturer. Installation shall be executed only in dry conditions.

## 1.6 WARRANTY

- A. The warranty on the all-weather running track surface shall endure for five (5) years from the date of acceptance. This five-year warranty is to be provided directly by the track-surfacing contractor to the Owner. It is to include the standard company warranty and also include a two-year warranty bond from an A-rated insurance company licensed to do business in the state. This two-year warranty from the bonding company is to be payable to the Owner.
- B. The warranty shall cover defects in materials, excessive color change, excessive wear, and any other feature which is not deemed ordinary wear on a running track.

## 1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.  
  
Poured Goods: Sheet product or filler material for emergency patches equal to 2 percent of the total amount installed on the track

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

Manufacturers: Subject to compliance with requirements, manufacturers include the following.

Beynon Sports Surfaces "BSS 1000"  
Hellas Sportracks 4000  
Rekortan M99

### 2.2 SYNTHETIC SEAMLESS SURFACE

- A. Performance Standards  
The new synthetic track surfacing system shall exhibit the following minimum performance standards as required by IAAF:

- A. **Thickness Average -  $\geq 13\text{mm}$**
- B. Force Reduction 35 to 50
- C. Modified Vertical Deformation 0.6 to 1.8
- D. Friction: TRRL Skid Resistance  $\geq 47$
- E. Tensile Strength  $\geq 0.5$
- F. Elongation at break  $\geq 40$

## 2.3 TRACK SYSTEM MATERIALS

- A. Elastomeric Polyurethane
  - 1. Two-component U.V. stabilized elastomeric polyurethane
  - 2. The elastomeric polyurethane shall be GRAY in color. Matching Dynamic Charcoal color as a design standard.
- B. EPDM Granulate
  - 1. EPDM granulates shall be .5 to 1.5mm in size and peroxide cured.
  - 2. EPDM granulates and the U.V. stabilized elastomeric polyurethane shall be color matched.
- C. Rubber Granulate
  - 1. butyl rubber processed ground to a graded size not to exceed .5 – 1mm.
  - 2. A maximum of twenty percent, by weight, of the butyl rubber will be allowed in the force reduction layer.
- D. Aliphatic Coating
  - 1. Single Component moisture cured aliphatic coating
  - 2. Aliphatic Coating shall be gray color matching the UV stabilized elastomeric polyurethane.
- E. . No clear or two component coatings will be allowed.
- F. Paint Striping: Single component, moisture cured aliphatic polyurethane. WHITE with contrasting colors to NCAA standards.

## 2.4 TRACK COMPONENTS

### A. Force Reduction Layer

The butyl granules and UV stabilized elastomeric polyurethane shall be metered and mixed together on site to regulate the ratio/quantity of butyl, not to exceed fourteen percent in the system and to insure an even distribution of the granules throughout the 8mm force reduction layer. No multi-layered system allowed.

### B. Resilient Wearing Layer

The .5 to 1.5 millimeter EPDM granules shall be mechanically integrated with an UV stabilized elastomeric polyurethane to the full depth of the 5mm wearing layer. The resilient textured finish shall be a dense matrix of encapsulated EPDM granules in a "Hobart" texture.

C. Protective Coating

The initial pigmented aliphatic polyurethane coating shall be spray applied over the entire synthetic surfaced area at a rate of 125 square feet per gallon. The second pigmented aliphatic polyurethane coating shall be spray applied over the initial application at a rate of 125 square feet per gallon in the opposite direction to provide uniform coverage

## 2.5 TRACK AND FIELD EQUIPMENT

A. Provide and install all permanent, inground track event equipment installed integrally with the surface as may be required and shown on the project drawings.

B. Equipment is available from the following manufacturers:

1. SportsEdge
2. SportsField

C. The following inground equipment is required :

1. Discus ring – Equal to Sportsedge No. 374
2. Discus ground sleeves – 8 required to support existing cage.

## PART 3 - EXECUTION

### 3.1 INSTALLATION REQUIREMENTS

A. The Track Installer is to purchase and install all synthetic surfacing, including on pole vault box covers, and take-off board blanking lids; surfacing on junction boxes installed flush with asphalt within synthetic finished areas.

### 3.2 EXAMINATION

- A. Prior to the arrival of the installation crew, check the asphalt base for the following:
1. Dimensional accuracy
  2. Strength
  3. Surface preparation
  4. Planarity – Surface tolerance of 1/8 inch in 10 feet or as required by the manufacturer.
- B. Discovered deficiencies will be corrected in accordance with manufacturers standards.

### 3.2 SURFACE PREPARATION

- A. Asphalt Substrates: Provide sound surface free of laitance, efflorescence, and any contaminants incompatible with surface system.
1. Repair unsatisfactory surfaces and fill holes and depressions. Treat control joints and other nonmoving substrate cracks to prevent telegraphing through surface system.

- a.. Leveling and Patching Material: Portland cement-based grout or epoxy- or polyurethane-based formulation suitable for exterior use and approved by system manufacturer. No cold tar patching, skin patching or sand mix patching will be acceptable.

- B. Entire surface shall be swept or power blown to remove all dirt, oil, grease, or any other foreign matter. The surface shall be free from any loose material.

### 3.3 LIMITATIONS

- A. Asphalt base cure time is 14-21 days before application of the surface.
- B. Apply the surfacing materials only during favorable weather conditions. Work is to progress only when the installer can guarantee adequate curing.
- C. No application of the surfacing shall be conducted during rainfall, when rain is imminent, when freezing temperatures are forecasted or exist, or when gusting winds are occurring.
- D. During surface installation and striping, all sprinkler systems must be shut off, or controlled so that no water falls on the track or event surfaces. This MUST be coordinated with the General Contractor and Landscaping Sub-contractors.
- E. All materials will be installed in strict compliance with the manufacturer's recommendations

### 3.4 INSTALLATION, GENERAL

- A. General: Comply with system manufacturer's written installation instructions. Install surface system over area and in thickness indicated.

### 3.5 INSTALLATION OF SEAMLESS SYSTEMS

- A. The Synthetic track surfacing system components shall be processed and installed by specially designed machinery with automatic electronic portioning, which provides continuous mixing, feeding and finishing for accurate quality controlled installation.
  - 1. No hand mixing will be allowed.

### 3.6 STRIPING

- A. Prior to striping, Contractor shall verify with the owner's representative for exact locations, size, shape, and color of the lines and markings before proceeding with markings and striping.
- B. A professional surveyor shall establish all locations for striping and lanes.
- C. All striping shall be accomplished by experienced personnel specializing in all-weather running track striping.
- D. Provide lane lines, starting lines, and markings required, and conform to the standards for track construction as prescribed by the NFSHSA, NCAA, or IAAF.
- E. Calculations shall be made to the nearest 1/100th of a foot.

- F. Angles shall be set by using a transit or theodolite capable of reading direct to 20 seconds.
- G. Measurement shall be made with a steel tape in engineering scale.
- H. Markings shall be clearly identified and color-coded on a detailed drawing to be provided to the owner upon completion.
- I. The Installer shall submit a certification of accuracy prepared by the registered Engineer or Surveyor. The Engineer or Surveyor shall certify the actual line markings on the facility, not the line markers drawings or computations. The track markings and layout must meet NFHS requirements and the requirements of the drawings and specifications.

### 3.7 INSTALLATION OF IN-GROUND TRACK AND FIELD EQUIPMENT

- A. The installation of field equipment is the responsibility of this Section.
- B. Provide each field event item and install as per the manufacturer's specifications and NFHS rules. The items where synthetic surfacing material must be installed up to or on top of must be installed prior to the installation of the synthetic surfacing material. The pole-vault box covers, take-off board blanking lids, shall receive track and field surfacing.

### 3.8 CLEANING

- A. Upon completion of all work, remove all containers, surplus materials, and installation debris. Leave area of work in clean orderly condition.
- B. Setting time prior to cleaning shall be in accordance with manufacturers standards or a minimum of 72 hours, whichever is greater.
- C. Finished surface shall be delivered to the Owner ready for use.

### 3.9 PROTECTION

- A. Provide signage at track perimeter to Prevent traffic over system for not less than 48 hours after installation.

END OF SECTION 321823

# APPENDIX

Geotechnical Information: Data on the indicated subsurface conditions are not intended as representations or warranties of accuracy or continuity between soil borings and is made available solely for the convenience of the Contractor. It is expressly understood that the Owner will not be responsible for interpretations or conclusions drawn therefrom by the Contractor.

Additional test borings and exploratory tests may be made by the Contractor as desired, at no cost to the owner.

January 20, 2011  
Job No. 0128-068-10

MHTN Architects, Inc.  
400 East South Temple, Suite 100  
Salt Lake City, Utah 84111

**Attention: Mr. Randy Boudrero**

Ladies and Gentlemen:

Re: Supplemental Cores Samples  
Track at Stewart Stadium  
Weber State University

## **1. INTRODUCTION**

As part of the Weber State University (WSU) Stewart Stadium field improvements, plans are to upgrade the rubber-coated track surrounding the football field. In order to further define the existing track structural section, six supplemental four-inch diameter core samples were taken. Prior to initiating the work, core locations were selected and marked by Ms. Tiffany Anderson of WSU Facilities Management. The core locations along with asphalt concrete and base course thickness at each location are shown on the attached Figure 1, Site Plan.

## **2. FIELD WORK**

Cores were completed using an electric powered core machine with a four-inch inside diameter core barrel. The core barrel was advanced through the rubberized track surface and underlying asphalt concrete and down into the base course. The thickness of each component (rubberized track surfacing, asphalt concrete, and base course) was then measured. The core holes were backfilled with three-eighths-inch minus asphalt concrete patch and hand-compacted in place.

## **3. OBSERVATIONS**

The rubberized layer at the surface was approximately three-eighths of an inch thick and attached to underlying asphalt concrete. The underlying asphalt concrete thickness observed ranged from three and one-half to four and one-half inches thick. Through visual inspection of the cores, the asphalt concrete section looks to be in good condition and was placed in two compacted lifts making up the total thickness. Laboratory testing was not completed on the asphalt concrete core samples. Though density tests could not be completed on the underlying base course, this base course appeared to be compacted.

The following table summarized the core sections observed:

<b>Core Number</b>	<b>Rubberized Surfacing Thickness (inches)</b>	<b>Asphalt Concrete Thickness (inches)</b>	<b>Base Course Thickness (inches)</b>
1	$\frac{3}{8}$	4	6
2	$\frac{3}{8}$	4½	6
3	$\frac{3}{8}$	4¼	6
4	$\frac{3}{8}$	3½	6
5	$\frac{3}{8}$	3¾	6
6	$\frac{3}{8}$	3¾	6
B-10	1	4	4

We appreciate the opportunity of providing this service for you. If you have any questions or require additional information, please do not hesitate to contact us.


Respectfully submitted,

**GSH Geotechnical Consultants, Inc.**



Bryan N. Roberts, P.E.  
State of Utah No. 276476  
Project Geotechnical Engineer

Reviewed by:




William J. Gordon, P.E.  
State of Utah No. 146417  
President/Senior Geotechnical Engineer

BNR/WJG:sn

Encl. Figure 1, Site Plan

Addressee (1 + email)

c: Mr. Mark Babbitt, Great Basin Engineering – North (1 + email)  
Ms. Tiffany Anderson, Weber State University (1 + email)



**KEY:**

- Borings
- Cores
- Asphalt Concrete Thickness (inches)  
/  
Base Thickness (inches)

TAYLOR AVENUE

SKYLINE DRIVE

FIGURE 1  
SITE PLAN



REFERENCE:  
ADAPTED FROM AERIAL PHOTOGRAPH  
DOWNLOADED FROM 2009 GOOGLE EARTH

APPROXIMATE SCALE: 1" = 86'