



State of Utah

GARY R. HERBERT  
Governor

SPENCER J. COX  
Lieutenant Governor

## Department of Administrative Services

KENNETH A. HANSEN  
Interim Executive Director

### Division of Facilities Construction and Management

ERIC R. THOLEN  
Director

## DFCM Addendum No. 2

Date: July 18, 2016

To: Design / Build Teams

From: Matt Boyer – Project Manager

Reference: Marina Dredging – Great Salt Lake State Park  
Division of Parks and Recreation – Magna, Utah  
DFCM Project No. 15247510

Subject: **DFCM Addendum No. 2**

Pages	Addendum Cover Sheet	1 page
	<u>Engineer's Addendum No. 2</u>	<u>2 pages</u>
	Total	3 pages

**Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.**

**2.1 SCHEDULE CHANGES:** There are no Project Schedule changes.

**2.2 GENERAL ITEMS:** See attached Engineer's Addendum No. 2 dated July 18, 2016.

## MEMORANDUM

---

**DATE:** 7/18/16  
**TO:** Matt Boyer, Program Director DFCM  
**CC:**  
**FROM:** Paul Taylor, P.E.  
**SUBJECT:** 15247510 DFCM Great Salt Lake Marina Dredging - Addendum #2

---

Please find below, J-UB's responses to the bid related questions as submitted by potential bidders. The questions are in regular font, and our responses are in italics.

### **Question #1 - OHWM**

"Facility program document states " the pond May be constructed using materials from the site provided that the bottom of the pond not be excavated any lower than elevation for 4202.0"

This requires that all barrow material be handled twice and hauled to the levee alignment.

Excavation to 4200 (OHWM) would allow much of the barrow to be taken from inside and adjacent to the alignment/\$ savings."

*The programming document listed the 4202.0 elevation to provide a slight cushion above the OHWM of 4200.0 In reviewing the documents submitted to the USACE to obtain the "no permit required" status we described a process that would keep excavations above 4201.0. As not to jeopardize this status, the State can allow excavation to 4201.0 while keeping within the limits already reviewed by the USACE. The Contractor may; at his risk; pursue with the USACE, excavation down to, but not below, the OHWM of 4200.0. All risks associated with any additional requirements or responsibilities associated with this decreased margin of error shall be accepted solely by the contractor.*

### **Question #2 – Discharging of decant water**

The question of whether or not a discharge at the disposal pond was discussed at the mandatory pre-bid.

*Discussions with the USACE Jason Gipson, Bountiful USACE Office, indicate that allowing **ANY** discharge of previously dredged materials, including "clean" water for this project would require obtaining a permit from the Corps. This is an option the State is willing to consider. The State recognizes that this potential permitting effort would likely require additional time, but could*

*substantially increase the volume of material that could be dredged for the contract price. The State is willing to allow up to an additional 6 months to the contractor to pursue this option, moving the completion date to July 14, 2017; if this option is pursued. It should be clear that this risk is the risk of the contractor. If the contractor elects to pursue this course of action, it does not alleviate the other terms of the contract. If this effort is unsuccessful or cannot be completed within the time allowed, the contractor will remain under obligation to complete the stated amount of dredging for the contract price and within the project deadline, on or before July 14, 2017. All costs associated with pursuing this option need to be included in the compensation for this contract.*